

ARBORICULTURAL IMPACT ASSESSMENT REPORT FOR:

75 Lawn Road London NW3 2XB

INSTRUCTING PARTY:

Private Client c/o Benjemin Beth Projects Ltd Samera House 136 -138 High Street Esher KT10 9QJ

REPORT PREPARED BY

David Gardner MSc MArborA & Adam Hollis MSc ARB MICFor FArbor A MRICS C Env

Ref: BBP/75LR/AIA/01

Date: 17th March 2023

The content and format of this report are for the exclusive use of the client in planning. It may not be sold, lent, hired out or divulged to any third party, not directly involved in the subject matter without Landmark Trees' written consent.

Web: www.landmarktrees.co.uk e-mail: info@landmarktrees.co.uk Tel: 0207 851 4544



London Office: Holden House, 4th Floor, 57 Rathbone Place London W1T 1JU Registered Office: 15 Abbey Road, Oxford OX2 0AD Landmark Trees is the trading name of Landmark trees Ltd. Registered in Wales. Reg No. 3882076 PART 1: MAIN TEXT

Section	Content	Page №
1.0	SUMMARY	3
2.0	INTRODUCTION	4
3.0	SITE CHARACTERISTICS	8
4.0	DEVELOPMENT CONSTRAINTS	11
5.0	TABLE OF IMPACTS	14
6.0	ARBORICULTURAL IMPLICATIONS	15
7.0	CONCLUSION	17
8.0	RECOMMENDATIONS	18
9.0	COMPLIANCE	21
10.0	REFERENCES	22

PART 2 - APPENDICES

APPENDIX 1	Survey Data	25
APPENDIX 2	Recommended Tree Works	27

PART 3 - PLANS

PLAN 1	Tree Constraints Plan	30
PLAN 2	Impact Assessment Plan(s)	32

DOCUMENT HISTORY

Revision	Status	Comments	Date
Rev 0	Authorised	For External Issue (to Planning)	17/03/23

1. SUMMARY

- 1.1 The existing site is a residential property with substantive rear garden containing one tree that potentially constrains development. The proposal includes the construction of a lightweight garden room.
- 1.2 There is one tree within close proximity to the development that therefore needs to be assessed. This comprises a mature common ash judged as being of high quality trees. All trees are material constraints on development, but this specimen requires particular consideration.
- 1.3 The report has assessed the impacts of the development proposals and concludes there would be at most a very low impact on the resource: there will be no loss of canopy cover and whilst the default position is that structures be located outside the Root Protection Area* (RPA) of trees to be retained, the adoption of a no-dig construction methodology for the garden room means that no ground works will be required. The report has therefore demonstrated that the tree(s) can remain viable and that there is no need for the area lost to encroachment to be compensated for elsewhere, contiguous with the RPA; the report also proposes a series of mitigation measures to improve the soil environment that is used by the tree for growth. Net impacts are assessed therefore as being very low.
- 1.4 Notwithstanding the above assurances, the report sets out a series of recommendations prior and during construction that will ensure impacts to trees are minimised. These are detailed in sections 6.3 and 8 of this report.
- 1.5 In conclusion, the proposal, through following the above recommendations, will have no, or very limited, impact on the existing trees and is acceptable.

* British Standards Institute: Trees in relation to design, demolition and construction BS 5837: 2012 HMSO, London

2. INTRODUCTION

2.1 Terms of Reference

- 2.1.1 Benjemin Beth Projects Ltd instructed Landmark Trees (LT) to prepare this Arboricultural Impact Assessment on behalf of their client, to support a full planning application submitted to the London Borough of Camden ('LBC').
- 2.1.2 The application relates to the construction of a lightweight garden room within the rear garden of the application site.
- 2.1.3 This report will assess the impact on trees and their constraints, identified in our survey. Although the proposals were known at the time of the survey, Landmark Trees endeavour to survey each site blind, working from a topographical survey, wherever possible, with the constraints plan informing their evolution. The purpose of the report is to provide guidance on how trees and other vegetation can be integrated into construction and development design schemes. The overall aim is to ensure the protection of amenity by trees which are appropriate for retention.
- 2.1.4 Trees are a material consideration for a Local Planning Authority when determining planning applications, whether or not they are afforded the statutory protection of a Tree Preservation Order or Conservation Area. British Standard BS 5837:2012 Trees in Relation to Design, Demolition and Construction sets out the principles and procedures to be applied to achieve a harmonious and sustainable relationship between trees and new developments. The Standard recommends a sequence of activities (see Fig.1 overleaf) that starts in the initial feasibility and design phase (RIBA Stage 2 'Concept Design' as defined in 2012) with a survey to qualify and quantify the trees on site and establish the arboricultural constraints to development (above- and below-ground) to inform the design in an iterative process, and continues with an assessment of the arboricultural impacts of the final design and measures to mitigate such impacts should they be negative. Detailed technical specifications for mitigation and protection measures are devised in the design phase that follows (RIBA Stage 3-4 'Developed and Technical design'), and the sequence ends with the Implementation and Aftercare phase (RIBA Stages 5-7) with the implementation of those measures once planning permission is granted, guided by Arboricultural Method Statements (RIBA Stage 4-5, 'Technical Design and Construction) and professional guidance where appropriate.
- 2.1.5 This report is produced to support the Design Team to the Scheme Design Approvals stage in the process chart overleaf.



Figure 1 The design and construction process and tree care

2.2 Drawings Supplied

2.2.1 The drawings supplied by the client and relied upon by Landmark Trees in the formulation of our survey plans are:

Existing site survey: 75 Lawn Road Garden Masterplan Proposals: 75 Lawn Road Garden Masterplan

2.3 Scope & Limitations of Survey

- 2.3.1 As Landmark Trees' (LT) arboricultural consultant, Conor Fitzpatrick surveyed the trees on site on the 7th of March 2023, recording relevant qualitative data in order to assess both their suitability for retention and their constraints upon the site, in accordance with British Standard 5837:2012 Trees in relation to design, demolition and construction – Recommendations [BS5837:2012].
- 2.3.2 Our survey of the trees, the soils and any other factors, is of a preliminary nature. The trees were SURVEYED on the basis of the Visual Tree Assessment method expounded by Mattheck and Breloer (The Body Language of Trees, DoE booklet Research for Amenity Trees No. 4, 1994). LT have not taken any samples for analysis and the trees were not climbed but inspected from ground level.
- 2.3.3 The results of the tree survey, including material constraints arising from existing trees that merit retention, should be used (along with any other relevant baseline data) to inform feasibility studies and design options. For this reason, the tree survey should be completed and made available to designers prior to and/or independently of any specific proposals for development. Tree surveys undertaken after a detailed design has been prepared can identify significant conflicts: in such cases, the nature of and need for the proposed development should be set against the quality and values of affected trees. The extent to which the design can be modified to accommodate those trees meriting retention should be carefully considered. Where proposed development is subject to planning control, a tree survey should be regarded as an important part of the evidence base underpinning the design and access statement
- 2.3.4 A tree survey is generally considered invalid in planning terms after 2 years, but changes in tree condition may occur at any time, particularly after acute (e.g. storm events) or prolonged (e.g. drought) environmental stresses or injuries (e.g. root severance). Routine surveys at different times of the year and within two three years of each other (subject to the incidence of the above stresses) are recommended for the health and safety management of trees remote from highways or busy access routes. Annual surveys are recommended for the latter.
- 2.3.5 The survey does not cover the arrangements that may be required in connection with the laying or removal of underground services.

Instructing party: Private Client c/o Benjemin Beth Projects Ltd, Samera House, 136 -138 High Street, Esher, Surrey KT10 9QJ Prepared by: David Gardner & Adam Hollis of Landmark Trees, Holden House, 4th Floor, 57 Rathbone Place, London W1T 4JU

2.4 Survey Data & Report Layout

- 2.4.1 Detailed records of individual trees are given in the survey schedule in Appendix 1. General husbandry recommendations are provided within Appendix 2. These may still be relevant to providing a safe site of work, of course. Planning considerations notwithstanding, we trust these necessary recommendations are passed on to relevant parties with due diligence and the trees to be managed appropriately.
- 2.4.2 A site plan identifying the surveyed trees, based on the Instructing Party's drawings / topographical survey is provided in Part 3 of this report. This plan also serves as the Tree Constraints Plan with the theoretical Recommended Protection Areas (RPA's), tree canopies and shade constraints, (from BS5837: 2012) overlain onto it. These constraints are then overlain in turn onto the Instructing Party's proposals to create a second Arboricultural Impact Assessment Plan in Part 3. General observations, discussion, conclusions and recommendations follow, below.

7

3. SITE CHARACTERISTICS

3.1 Property Description & Planning Context



Photograph 1: Aerial view of application site (Source: Google Maps)

- 3.1.1 This property is located in the Gospel Oak Ward within the Parkhill Conservation Area approximately 75m to the east of Belsize Park station
- 3.1.2 There are a number of level changes within the site.
- 3.1.3 We understand that the ash tree in the rear garden is protected by a Tree Preservation Order: it is a criminal offence to prune, damage or fell such trees without permission from the local authority.
- 3.1.4 Relevant local planning policies comprise Policies G1 and G7 of the London Plan 2021 and Policies A3, D1 and D2 of the Camden Local Plan (adopted 3rd July 2017).
- 3.1.5 The wider site is currently being developed under planning permission 2018/2136/P.

3.2 Soil Description



Figure 2: Extract from the BGS Geology of Britain Viewer

- 3.2.1 In terms of the British Geological Survey, the site overlies the London Clay Formation (see indicated location on Fig.1 plan extract above). The associated soils are generally, highly shrinkable clay; e.g. slowly permeable seasonally waterlogged fine loam over clay. Such highly plastic soils are prone to movement: subsidence and heave. The actual distribution of the soil series are not as clearly defined on the ground as on plan and there may be anomalies in the actual composition of clay, silt and sand content.
- 3.2.2 Clay soils are prone to compaction during development with damage to soil structure potentially having a serious impact on tree health. The design of foundations near problematic tree species will also need to take into consideration subsidence risk. Further advice from the relevant experts on the specific soil properties can be sought as necessary.

3.3 Subject Trees

- 3.3.1 The subject tree comprises a mature common ash assessed as being category* A (High Quality). For the sake of consistency, the same numbering system adopted in our previous tree survey has been maintained.
- 3.3.2 Full details of the surveyed trees can be found in Appendix 1 of this report.
- 3.3.3 There are recommended works for the tree, these are listed in Appendix 2.

*page 9 of: British Standards Institute: Trees in relation to design, demolition and construction BS 5837: 2012 HMSO, London

Instructing party: Private Client c/o Benjemin Beth Projects Ltd, Samera House, 136 -138 High Street, Esher, Surrey KT10 9QJ Prepared by: David Gardner & Adam Hollis of Landmark Trees, Holden House, 4th Floor, 57 Rathbone Place, London W1T 4JU



Photograph 1: Rear garden of 75 Lawn Road, London NW3 2XB

4. DEVELOPMENT CONSTRAINTS

- 4.1 Primary Constraints
 - 4.1.1 BS5837: 2012 gives Recommended Protection Areas (RPA's) for any given tree size. The individual RPA's are calculated in the Tree Schedule in Appendix 1 to this report, or rather the notional radius of that RPA, based on a circular protection zone. The prescribed radius is 12-x stem diameter at 1.5m above ground level, except where composite formulae are used in the case of multi-stemmed trees.
 - 4.1.2 Circular RPA's are appropriate for individual specimen trees grown freely, but where there is ground disturbance, the morphology of the RPA can be modified to an alternative polygon, as shown in the diagram below (Figure 2). Alternatively, one need principally remember that RPA's are area-based and not linear notional rather than fixed entities.





4.1.3 In BS5837, paragraph 4.6.2 states that RPA's should reflect the morphology and disposition of the roots; where pre-existing site conditions or other factors indicate that rooting has occurred asymmetrically, a polygon of equivalent area should be produced. Modifications to the shape of the RPA should reflect a soundly based arboricultural assessment of likely root distribution. This can be done as a desktop / theoretical exercise but is not altogether (scientifically) reliable and may also invite disagreement / differences of opinion as to that distribution.

- 4.1.4 LT prefer where possible and practical to raise the issue of modification but suspend judgment until such time as more reliable site investigations have been undertaken (Tree Radar scans and / or trial pits). Of course, the justification for these investigations will depend upon whether trees are (or are likely to be once modified) subject to impacts and also upon their quality / condition: it is generally not worth commissioning a radar study to locate the roots of a poor- or low-quality tree. On other occasions, there may not be the opportunity to commission investigations, either because the access is restricted by ownership / tenancy or the report's turnaround simply does not allow it, and they may need to follow on or be conditioned. No a priori RPA modifications have been made in this instance on account of prevailing site conditions.
- 4.1.5 The quality of trees will also be a consideration: U Category trees are discounted from the planning process in view of their limited useful life expectancy. Again, Category-C trees would not normally constrain development individually, unless they provide some external screening function.
- 4.1.6 At paragraph 5.1.1. BS5837: 2012 notes that "Care should be exercised over misplaced tree preservation; attempts to retain too many or unsuitable trees on a site are liable to result in excessive pressure on the trees during demolition or construction work, or post-completion demands on their removal."
- 4.1.7 In theory, only moderate quality trees and above are significant material constraints on development. However, low quality trees comprise a constraint in aggregate, in terms of any collective loss / removal, where replacement planting is generally considered appropriate.
- 4.1.8 In this instance, the high quality of the ash tree means it poses potentially significant constraints to development.

4.3 Secondary Constraints

- 4.3.1 The second type of constraint produced by trees that are to be retained is that the proximity of the proposed development to the trees should not threaten their future with ever increasing demands for tree surgery or felling to remove nuisance shading (Figure 3), honeydew deposition or perceived risk of harm.
- 4.3.2 The shading constraints are crudely determined from BS5837 by drawing an arc from northwest to east of the stem base at a distance equal to the height of the tree, as shown in the diagram opposite. Shade is less of a constraint on nonresidential developments, particularly where rooms are only ever temporarily occupied.



- 4.3.3 This arc (see Figure 4) represents the effects that a tree will have on layout through shade, based on shadow patterns of 1x tree height for a period May to Sept inclusive 10.00-18.00 hrs daily.
- 4.3.4 Assuming that it will be retained, the orientation of the tree means it has the potential to provide a variety of secondary constraints, including shading, organic deposition and the potential need to maintain crown clearance in the future. The significance of these constraints will vary depending on the location and proximity to the proposed re-development which is considered below (in Sections 5 & 6). As specified by BS5837, this section (4) of the report considers only the site as it is, not in the light of pending proposals.

Note: Sections 5 & 6 below will now assess the impacts of the proposals upon constraints identified in Section 4 above. Table 1 in Section 5 presents the impacts in tabular form (drawing upon survey data presented in Appendices 1 & 2). Impacts are presented in terms of whole tree removal and the effect on the landscape or partial encroachment (% of RPA) and its effect on individual tree health. Section 6 discusses the table data, elaborating upon the impacts' significance and mitigation.

Table 1: Arboricultural Impact Assessment

(Impacts assessed prior to mitigation and rated with reference to Matheny & Clark (1998))

Hide irrelevant Show All Trees

Ref: BBP_75LR_AIA

B.S. Cat.	Tree No.	Species	Impact	Tree / RPA Affected	Age	Growth Vitality	Species Tolerance	Impact on Tree Rating	Impact on Site Rating	Mitigation
A	Т3	Ash, Common	Garden Room Construction within RPA	6.7 m ² 2.78 %	Mature	Normal	Moderate	Very Low	Very Low	No-dig construction
			Irrigation Tank & Path Installation within RPA							No-dig construction

6. ARBORICULTURAL IMPLICATIONS

- 6.1 Rating of Primary Impacts
 - 6.1.1 The principal impact in the current proposals comprises the encroachments of the RPA of the ash tree by the garden room. In this instance, the inherently lightweight nature of the structure means that non-invasive footings such as an above ground cellular confinement system infilled with aggregate can be employed. Thus, as there will be no disturbance of the soil, the encroachment shown on plan is entirely academic. The proposed irrigation tank and garden pathway will also be constructed using an above ground cellular confinement system as will any base of the proposed sculpture.
 - 6.1.2 In order to avoid extensive manual trenching within the RPA, we recommend that the electrical services to the garden room be affixed above ground to the southern boundary treatment before being buried at a suitable point.
 - 6.1.3 The proposed decompaction of the planting area in the rear garden by hand digging should take account of the protected status of the tree and be undertaken by experienced operatives with the retention of roots encountered being a priority.
 - 6.1.4 Our working position is that the retaining wall and steps up into the garden within the RPA of the ash tree that are shown on our Arboricultural Impact Assessment plan are consented under the existing planning consent and assume that the outer line of the encroachment will be manually excavated in conjunction with pre-emptive root pruning.
 - 6.1.5 In our view, the tree(s) are of a species, age and condition sufficient to remain viable in the circumstances, provided the series of mitigation measures outlined below are followed to both reduce the immediate impact of working methods and also improve the soil environment that is used by the tree for growth. Supervision and monitoring of such measures will also be essential. Subject to these provisos the net impacts are assessed as being very low.
 - 6.1.6 The tree in question is shown in Table 1 above to be a healthy specimen of a species with a good resistance to development impacts, and of an age quite capable of tolerating these highly limited impacts. Nor do the site characteristics suggest specific soil anomalies (e.g. heavy clay) having a bearing on such considerations, provided appropriate measures (e.g. ground protection) are taken.
 - 6.1.7 As per BS5837 recommendations (at 5.3.a), the above assessment demonstrates that the tree can remain viable.

6.2 Rating of Secondary Impacts

6.2.1 There will always be some level of secondary impacts of honeydew / litter deposition and partial shade on this site, regardless of development. Whilst the proposals do introduce a structure closer to the ash tree than the existing arrangement, the tree is already under a cyclical pruning regime and thus the status quo is unlikely to change with further development, which is the salient point for planning to consider. Thus, the secondary impacts of development are minimal.

6.3 Mitigation of Impacts

- 6.3.1 The garden room, irrigation tank and garden path will all require a no-dig construction technique, using a cellular confinement system with no fines aggregate for the sub-base. The finished section is likely to be a minimum of 75mm above grade, depending on final specification, which will need to be factored into the overall finished site levels. If the proposed sculpture requires a solid base, this will also be formed using this methodology.
- 6.3.2 The electrical supply to the garden building should be run above ground for as far as possible to minimise excavation within the RPA. Where it needs to be buried, this excavation should be carried out manually under arboricultural supervision with any roots encountered retained.

7. CONCLUSION

- 7.1 The potential impacts of development are all very low given there is no loss of canopy cover and only theoretical RPA encroachments of trees retained. In the latter case, the report has demonstrated as per BS5837 paragraph 5.3.1 (a) that the tree(s) can remain viable.
- 7.2 The full potential of the impacts can thus be largely mitigated through design and precautionary measures. These measures can be elaborated in Method Statements in the discharge of planning conditions.
- 7.3 The species affected are generally tolerant of root disturbance / crown reduction and the retained trees are generally in good health and capable of sustaining these reduced impacts. Therefore, the proposals will not have any significant impact on either the retained trees or wider landscape thereby complying with Policies G1 and G7 of the London Plan 2021 and Policies G1 and G7 of the London Plan 2021 and Policies A3, D1 and D2 of the Camden Local Plan (adopted 3rd July 2017).
- 7.4 Thus, with suitable mitigation and supervision the scheme is recommended to planning.

8. **RECOMMENDATIONS**

- 8.1 Specific Recommendations
 - 8.1.1 Tree works recommendations in Appendix 2 are not part of the current application, but requirements of general maintenance that will need to be applied for (subject to para. 3.3 of this report and any other relevant constraints in planning or leasehold) by the client separately. Consent for the current planning application does not impart any consent for the Appendix 2 maintenance works. Please note, though, the owner and / or manager of a property have a duty to maintain a safe site of work and to protect occupiers of the surrounding land / members of the public from tree hazards. Works recommended in this report should be enacted in a timely fashion by the relevant party regardless of the progress of the development.
 - 8.1.2 Excavation and construction impacts within the RPA's of trees identified in Table 1 above, will need to be controlled by method statements specifying mitigation methods suggested in para 6.3 above and by consultant supervision as necessary. These method statements can be provided as part of the discharge of conditions.

- 8.2 General Recommendations for Sites Being Developed with Trees / Outline Arboricultural Method Statement
 - 8.2.1 Any trees which are in close proximity to the proposed development should be protected with a Tree Protection Barrier (TPB). Protective barrier fencing should be installed immediately following the completion of the tree works, remaining in situ for the entire duration of the development unless otherwise agreed in writing by the Council. It should be appropriate for the intensity and proximity of the development, usually comprising steel, mesh panels 2.4m in height ('Heras') and should be mounted on a scaffolding frame (shown in Fig 2 of BS5837:2012). The position of the TPB can be shown on plan as part of the discharge of conditions, once the layout is agreed with the planning authority. The TPB should be erected prior to commencement of works, remain in its original form on-site for the duration of works and be removed only upon full completion of works.
 - 8.2.2 A TPB may no longer be required during soft landscaping work but a full arboricultural assessment must be performed prior to the undertaking of any excavations within the RPA of a tree. This will inform a decision about the requirement of protection measures. It is important that all TPBs have permanent, weatherproof notices denying access to the RPA. Extant areas of RPA that cannot be fenced off and therefore lie outside the CEZ must be protected with fit-for-purpose ground protection. The location and type of ground protection is shown in the Tree Protection Plan in the Appendices
 - 8.2.3 The use of heavy plant machinery for building demolition, removal of imported materials and grading of surfaces should take place in one operation. The necessary machinery should be located above the existing grade level and work away from any retained trees. This will ensure that any spoil is removed from the RPAs. It is vital that the original soil level is not lowered as this is likely to cause damage to the shallow root systems.
 - 8.2.4 Any pruning works must be in accordance with British Standard 3998:2010 Tree work [BS3998].
 - 8.2.5 Where sections of hard surfacing are proposed in close proximity to trees, it is recommended that "No-Dig" surfacing be employed in accordance with BS5837:2012 and 'The Principles of Arboricultural Practice: Note 1, Driveways Close to Trees, AAIS 1996 [APN1]'.
 - 8.2.6 If the RPA of a tree is encroached by underground service routes then BS5837:2012 and NJUG VOLUME 4 provisions should be employed. If it is deemed necessary, further arboricultural advice must be sought.
 - 8.2.7 Numerous site activities are potentially damaging to trees e.g. parking, material storage, the use of plant machinery and all other sources of soil compaction. In operating plant, particular care is required to ensure that the operational arcs of excavation and lifting machinery, including their loads, do not physically damage trees when in use.

Instructing party: Private Client c/o Benjemin Beth Projects Ltd, Samera House, 136 -138 High Street, Esher, Surrey KT10 9QJ Prepared by: David Gardner & Adam Hollis of Landmark Trees, Holden House, 4th Floor, 57 Rathbone Place, London W1T 4JU

- 8.2.8 To enable the successful integration of the proposal with the retained trees, the following points will need to be taken into account:
 - 1) Plan of underground services.
 - Schedule of tree protection measures, including the management of harmful substances.
 - Method statements for constructional variations regarding tree proximity (e.g. foundations, surfacing and scaffolding).
 - 4) Site logistics plan to include storage, plant parking/stationing and materials handling.
 - 5) Tree works: felling, required pruning and new planting. All works must be carried out by a competent arborist in accordance with BS3998.
 - Site supervision: the Site Agent must be nominated to be responsible for all dayto-day arboricultural matters on site. This person must:
 - be present on site for the majority of the time;
 - be aware of the arboricultural responsibilities;
 - have the authority to stop work causing, or may cause harm to any tree;
 - ensure all site operatives are aware of their responsibilities to the trees on site and the consequences of a failure to observe these responsibilities;
 - arrange with the retained arboricultural consultant an initial pre-start briefing to inspect tree protection measures and agree a schedule of monitoring thereof on an initial monthly basis to be reviewed over the duration of works.
 - give advance notice (ideally 2 weeks) to retained arboricultural consultant to arrange for supervision of any excavation (especially for services and foundations) within RPA
 - make immediate contact with the local authority and/or a retained arboricultural consultant in the event of any tree related problems occurring.
- 8.2.9 These points can be resolved and approved through consultation with the planning authority via their Arboricultural Officer.
- 8.2.10 The sequence of works should be as follows:
 - i) initial tree works: felling, stump grinding and pruning for working clearances;
 - ii) installation of TPB for demolition & construction;
 - iii) installation of underground services;
 - iv) installation of ground protection;
 - v) main construction;
 - vi) removal of TPB;
 - vii) soft landscaping.

Instructing party: Private Client c/o Benjemin Beth Projects Ltd, Samera House, 136 -138 High Street, Esher, Surrey KT10 9QJ Prepared by: David Gardner & Adam Hollis of Landmark Trees, Holden House, 4th Floor, 57 Rathbone Place, London W1T 4JU

9. COMPLIANCE: Trees and the Planning System

- 9.1 Under the UK planning system, local authorities have a statutory duty to consider the protection and planting of trees when granting planning permission for proposed development. The potential effect of development on trees, whether statutorily protected (e.g. by a tree preservation order or by their inclusion within a conservation area) or not, is a material consideration that is taken into account in dealing with planning applications. Where trees are statutorily protected, it is important to contact the local planning authority and follow the appropriate procedures before undertaking any works that might affect the protected trees.
- 9.2 The nature and level of detail of information required to enable a local planning authority to properly consider the implications and effects of development proposals varies between stages and in relation to what is proposed. Table B.1 provides advice to both developers and local authorities on an appropriate amount of information. The term "minimum detail" is intended to reflect information that local authorities are expected to seek, whilst the term "additional information" identifies further details that might reasonably be sought, especially where any construction is proposed within the RPA.
- 9.3 This report delivers information appropriate to a full planning application and to these specific proposals as per BS5837 Table B.1 below, providing both minimum details and further additional material in the form of general tree protection recommendations and constructional variation.

Stage of process	Minimum detail	Additional information		
Pre-application	Tree survey	Tree retention/removal plan (draft)		
Planning application	Tree survey (in the absence of pre-application discussions)	Existing and proposed finished levels		
	Tree retention/removal plan (finalized)	Tree protection plan		
	Retained trees and RPAs shown on proposed layout	Arboricultural method statement – heads of terms		
	Strategic hard and soft landscape design, including species and location of new tree planting	Details for all special engineering within the RPA and other releval construction details		
	Arboricultural impact assessment			
Reserved matters/ planning conditions	Alignment of utility apparatus (including drainage), where outside the RPA or	Arboricultural site monitoring schedule		
	where installed using a trenchless method	Tree and landscape management plan		
	Dimensioned tree protection plan	Post-construction remedial works		
	Arboricultural method statement – detailed	Landscape maintenance schedule		
	Schedule of works to retained trees, e.g. access facilitation pruning			
	Detailed hard and soft landscape design			

Table B.1 Delivery of tree-related information into the planning system

10.0 REFERENCES

- Barlow JF & Harrison G. 1999. Shade By Trees, Arboricultural Practice Note 5, AAIS, Farnham, Surrey.
- British Standards Institute. 2012. Trees in Relation to Design, Demolition and Construction Recommendations BS 5837: 2012 HMSO, London.
- Centre for Ecology & Hydrology. 2006. Tree Roots in the Built Environment, HMSO, London.
- Helliwell R (1980) Provision for New Trees; Landscape Design; July/August issue
- International Society of Arboriculture (ISA). 1994. The Landscape Below Ground. ISA, Champaign, Ilinois. USA.
- Lonsdale D 1999. Research for Amenity Trees No.7: Principles of Tree Hazard Assessment and Management, HMSO, London.
- Matheny, N; Clark, J. R.1998. Trees and Development: A Technical Guide to Preservation of Trees during Land Development. ISA, Champaign, Ilinois. USA.
- Mattheck C. & Breloer H. 1994. Research for Amenity Trees No.2: The Body Language of Trees, HMSO, London.
- Thomas P, 2000 & 2014. Trees: Their Natural History, Cambridge University Press, Cambridge.
- Trowbridge J & Bassuk N (2004) Trees in the Urban Landscape: Site Assessment, Design, and Installation; J Wiley & Sons inc.
 NJ USA



Caveats

This report is primarily an arboricultural report. Whilst comments relating to matters involving built structures or soil data may appear, any opinion thus expressed should be viewed as qualified, and confirmation from an appropriately qualified professional sought. Such points are usually clearly identified within the body of the report. It is not a full safety survey or subsidence risk assessment survey. These services can be provided but a further fee would be payable. Where matters of tree condition with a safety implication are noted during a survey they will of course appear in the report.

A tree survey is generally considered invalid in planning terms after 2 years, but changes in tree condition may occur at any time, particularly after acute (e.g. storm events) or prolonged (e.g. drought) environmental stresses or injuries (e.g. root severance). Routine surveys at different times of the year and within two - three years of each other (subject to the incidence of the above stresses) are recommended for the health and safety management of trees remote from highways or busy access routes. Annual surveys are recommended for the latter.

Tree works recommendations are found in the Appendices to this report. It is assumed, unless otherwise stated ("ASAP" or "Option to") that all husbandry recommendations will be carried out within 6 months of the report's first issue. Clearly, works required to facilitate development will not be required if the application is shelved or refused. However, necessary husbandry work should not be shelved with the application and should be brought to the attention of the person responsible, by the applicant, if different. Under the Occupiers Liability Act of 1957, the owner (or his agent) of a tree is charged with the due care of protecting persons and property from foreseeable damage and injury.' He is responsible for damage and/or nuisance arising from all parts of the tree, including roots and branches, regardless of the property on which they occur. He also has a duty under The Health and Safety at Work Act 1974 to provide a safe place of work, during construction. Tree works should only be carried out with local authority consent, where applicable.

Inherent in a tree survey is assessment of the risk associated with trees close to people and their property. Most human activities involve a degree of risk, such risks being commonly accepted if the associated benefits are perceived to be commensurate.

Risks associated with trees tend to increase with the age of the trees concerned, but so do many of the benefits. It will be appreciated, and deemed to be accepted by the client, that the formulation of recommendations for all management of trees will be guided by the cost-benefit analysis (in terms of amenity), of tree work that would remove all risk of tree related damage.

Prior to the commencement of any tree works, an ecological assessment of specific trees may be required to ascertain whether protected species (e.g. bats, badgers and invertebrates etc.) may be affected.



PART 2 – APPENDICES

APPENDIX 1

TREE SCHEDULE

Botanical Tree Names Ash, Common : Fraxinus excelsior

Notes for Guidance:

- 1. Height describes the approximate height of the tree measured in metres from ground level.
- 2. The Crown Spread refers to the crown radius in meters from the stem centre and is expressed as an average of NSEW aspect if symmetrical.
- 3. Ground Clearance is the height in metres of crown clearance above adjacent ground level.
- 4. Stem Diameter (Dm) is the diameter of the stem measured in millimetres at 1.5m from ground level for single stemmed trees. BS 5837:2012 formula (Section 4.6) used to calculate diameter of multi-stemmed trees. Stem Diameter may be estimated where access is restricted and denoted by '#'.
- 5. Protection Multiplier is 12 and is the number used to calculate the tree's protection radius and area
- 6. Protection Radius is a radial distance measured from the trunk centre.
- 7. Growth Vitality Normal growth, Moderate (below normal), Poor (sparse/weak), Dead (dead or dying tree).
- Structural Condition Good (no or only minor defects), Fair (remediable defects), Poor Major defects present.
- Landscape Contribution High (prominent landscape feature), Medium (visible in landscape), Low (secluded/among other trees).
- B.S. Cat refers to (British Standard 5837:2012 section 4.5) and refers to tree/group quality and value;
 'A' High, 'B' Moderate, 'C' Low, 'U' Unsuitable for retention. The following colouring has been used on the site plans:
 - High Quality (A) (Green),
 - Moderate Quality (B) (Blue),
 - Low Quality (C) (Grey),
 - Unsuitable for Retention (U) (Red)
- 11. Sub Cat refers to the retention criteria values where 1 is Arboricultural, 2 is Landscape and 3 is Cultural including Conservational, Historic and Commemorative.
- 12. Useful Life is the tree's estimated remaining contribution in years.

M	Si Da	Site:		5 Lawn Rd 7/03/2023			Appendix 1							Land 020	Landmark Trees Ltd 020 7851 4544		
Landmar	BS5837 Tree Constraints Survey Schedule					Surv Ref:	/eyor(s):	BBP_75LR_AIA									
Tree No.	English N	ame	÷	Height	Crown Spread	Ground Clearance	Stem Diamete	Age Class	Protection Radius	Growth Vitality	Structural Condition	B.S. Cat	Sub Cat	Useful Life	Co	omments	
Т3	Ash, Corr	imor	ו	16	7786	2.0	730	Mature	8.8	Normal	Fair	A	2	>40	Pollard (Old) Entry wounds on trunk Recently been pollarde growth.	k ed back to old	Pollard heads. 1 year re-

APPENDIX 2

RECOMMENDED TREE WORKS

Notes for Guidance:

Priority	1 - Urgent (ASAP), 2 - Standard (within 3 months), 3 - Non-urgent (2-3 years)
СВ	- Cut Back to boundary/clear from structure.
CL#	- Crown Lift to given height in meters.
CT#%	- Crown Thinning by identified %.
CR#%	 Crown Reduce by given maximum % (of outermost branch & twig length)
DWD	- Remove deadwood.
Fell	- Fell to ground level.
Flnv	 Further Investigation (generally with decay detection equipment).
Pol	- Pollard or re-pollard.
Mon	 Check / monitor progress of defect(s) at next consultant inspection which should be <18 months in frequented areas and <3 years in areas of more occasional use. Where clients retain their own ground staff, we recommend an annual in- house inspection and where practical, in the aftermath of extreme weather events.
• • •	

Svr Ivy / Clr Bs - Sever ivy / clear base and re-inspect base / stem for concealed defects.

Landm	Site: 75 Date: 07 ark Trees	5 Lawn Rd 7/03/2023	R	A ecomme	ppendix 2 ended Tree Works	Surveyor(s): Ref:	Conor Fitzpatrick BBP_75LR_AIA Hide irrelevant Show All Trees
Tree No.	English Name	B.S. H Cat	Height Ground Clearance	Crown Spread	Recommended Works	Comments/	Reasons
Т3	Ash, Common	A	16 2.0	7786	Maintain pollard regime	Pollard (Old) Entry wounds on Recently been po growth. Recommended h	trunk Ilarded back to old Pollard heads. 1 year re- usbandry 3



PART 3 – PLANS

PLAN 1

TREE CONSTRAINTS PLAN





5m

10m

NOTE:

This survey is of a preliminary nature. The trees were inspected from the ground only on the basis of the Visual Tree Assessment method. No samples were taken for analysis. No decay detection equipment was employed. The survey does not cover the arrangements that may be required in connection with the laying or removal of underground services.

Branch spread in metres is taken at the four cardinal points to derive an accurate representation of the crown.

Root Protection Areas (RPA) are derived from stem diameter measured at 1.5 m above adjacent ground level (taken on sloping ground on the upslope side of the tree base).



ARBORICULTURAL IMPACT ASSESSMENT PLAN (S)

i. Ground Floor

