


The Contractor is responsible for the design, installation and maintenance of all necessary temporary works to ensure the strength and stability of the building throughout the course of the works. All temporary works shown are indicative only.

When installing beams into an opening wider than 3m in an existing structure, allow for the use of folding wedges, Harjaks or other means to pre-deflect the beam to give a mid-span deflection of $\text{span}/400$ before transferring load from temporary works into the beam.

Use figured dimensions only: Do not scale from drawing.
All levels and dimensions are to be checked on site.
This drawing is to be read in conjunction with all relevant documents

 **KNAPP HICKS & PARTNERS LTD.** (DATE AS TITLE)

P1	18.05.22	PRELIMINARY ISSUE FOR COMMENT	JFM	JM
Rev	Date	Revision	By	Chk

Client

UNITED GRAND LODGE
OF ENGLAND

Project

35 GREAT QUEEN STREET
LONDON WC2B 5AA

Drawing Title

CONSTRUCTION NOTES
SHEET 2 of 2



Knapp Hicks
Consulting Structural, Civil
& Geotechnical Engineers

Prospect House, 1 Highpoint Business Village
Henwood, Ashford, Kent TN24 8DH

tel: 01233 502255 website: www.knapphicks.co.uk

SCALE	NA	DRAWN	JFM	A3
DATE	May 22	CHECK	JM	

37990 / S /SK12	P1
-----------------	----