



















-  Fire Alarm Panel
 -  Visual Alarm Device (White Flash)
 -  Smoke detector as 2 NO
 -  Smoke detector Sdr as 1 NO
 -  Heat Detector as 0 NO
 -  Sounder/Beacon as 1 NO
 -  Call Point
- FD30: 30 Mins Resistance Door
FD60: 60 Mins Resistance Door

The Ground Floor Fire Escape Proposed

- Notes:
1. All works to comply with the building regulations.
 2. New studwork partitions to be framed from 75X47 mm SW framing faced both sides with 12.5 mm plasterboard with skim coat of plaster finish.
 3. The floor to be leveling and covered with new anti slip vinyl flooring.
 4. Make good existing wall using gypsum plaster or similar approved.

-  Direction of escape
-  Foam Extinguisher
-  Shelving
-  H₂O Extinguisher
-  Wet Chemical Extinguisher
-  The Sink
-  CO₂ Extinguisher
-  Exiting Walls
-  Call Point
-  New Stud Walls
-  Fire Blanket

TITLE	Restaurant
CLIENT	Mr Xu
PROJECT ADDRESS	68-70 Sotumpton Row, London WC1B 4AR
DRAWING NUMBER	P-05
ISSUE&DATE	February 2023
SCALE	1:100 A4
DRAWING BY	-----

.....York Design Studio

.....York Design Studio
 2 Cromwell Road
 Feltham
 Middlesex
 Tel: 02087076687
 Mob:07988558919