

Caldwell



B0992 161 Drury Lane Development

Circular Economy and Whole Life Cycle Analysis Statement

Version: V1.0

Current Version Publish Date: 16/05/2023

Building Performance Prediction Ltd.
Caldwell Group
Unit 6 Forestgrove Business Park
Belfast
BT8 6AW
028 9069 9720



Contents

| | | |
|-------|---|----|
| 1 | Executive Summary..... | 3 |
| 1.1 | Brief description of development | 3 |
| 1.2 | Summary of the approach, key commitments, and targets..... | 4 |
| 2 | Introduction | 5 |
| 2.1 | Method statement (including key outcomes from workshops/meetings) | 6 |
| 2.2 | Circular economy aspirations..... | 6 |
| 3 | Whole Life Cycle Analysis..... | 7 |
| 4 | Circular economy goals and strategic approach | 8 |
| 4.1 | Strategic approach(es) | 8 |
| 4.1.1 | Circular economy approach for the refurbishment development | 8 |
| 4.1.2 | Circular economy approach for the existing site | 8 |
| 4.1.3 | Circular economy approach for municipal waste during operation | 8 |
| 4.2 | Explaining the strategic approach(es) | 8 |
| 4.3 | Draft Circular Economy Statements | 9 |
| 4.3.1 | Minimise the quantities of materials used. | 9 |
| 4.3.2 | Minimise the quantities of other resources used (energy, water, land) | 9 |
| 4.3.3 | Specify and sourcing materials and other resources responsibly and sustainably..... | 9 |
| 4.3.4 | Design for longevity, adaptability or flexibility and reusability or recoverability | 9 |
| 4.3.5 | Design out construction, demolition, excavation and municipal waste arising | 9 |
| 4.3.6 | Manage demolition waste | 9 |
| 4.3.7 | Manage excavation waste | 9 |
| 4.3.8 | Manage construction waste | 10 |
| 4.3.9 | Manage municipal waste..... | 10 |
| 5 | Circular economy commitments..... | 11 |
| 5.1 | Key commitments | 11 |
| 5.1.1 | Section A Conserve Resources | 11 |
| 5.1.2 | Section B: Design to Eliminate Waste (And for Ease of Maintenance) | 12 |
| 5.1.3 | Section C: Manage Waste | 13 |
| 5.2 | Reporting forms for numerical targets and commitments: | 15 |
| 5.2.1 | Bill of Materials | 15 |
| 5.2.2 | Recycling and Waste Reporting | 15 |
| 5.3 | Circular economy narrative – structured around nine circular economy principles..... | 16 |
| 5.4 | Plans for implementation:..... | 19 |



| | | |
|---|---|----|
| 5.4.1 | Specific plans for short- and medium-term targets..... | 19 |
| 5.4.2 | Programme/method for longer-term targets..... | 19 |
| 5.5 | End-of-life strategy..... | 19 |
| 6 | Reporting outcomes post-planning/completion..... | 21 |
| 6.1 | State whether each target or commitment was achieved and provide evidence and supporting documentation..... | 21 |
| 6.2 | Lessons learned..... | 21 |
| 7 | Appendices..... | 22 |
| Table 1 – Section A - Minimising the quantities of materials used | | 11 |
| Table 2 – Section A - Minimising the quantities of other resources used (energy, water, land)..... | | 11 |
| Table 3 – Section A - Specifying and sourcing materials responsible and sustainably | | 12 |
| Table 4 – Section B - Designing for reusability recoverability/ longevity/ adaptability/ flexibility..... | | 12 |
| Table 5 – Section B - Designing out construction, demolition, excavation and municipal waste arising..... | | 13 |
| Table 6 – Section C - Demolition waste (how waste from demolition of the layers will be managed) | | 13 |
| Table 7 – Section C - Excavation waste (how waste from excavation will be managed)..... | | 14 |
| Table 8 – Section C - Construction waste (how waste arising from construction of the layers will be reused or recycled) | | 14 |
| Table 9 – Section C - Municipal and industrial waste (how the design will support operational waste management) | | 14 |
| Table 10 - Bill of Materials | | 15 |
| Table 11 - Recycling and Waste Reporting | | 16 |

| Version | Date | Reason for issue | Prepared By | Checked By |
|---------|----------|----------------------------------|-------------|------------|
| 1.0 | May 2023 | Accompanying planning submission | HI/AG | AG |
| 2.0 | May 2023 | Minor Amendments | HI/AG | AG |

Building Performance Prediction Ltd disclaims any responsibility to the Client and others in respect of any matters outside the scope of this report. This report has been prepared with reasonable skill, care and diligence within the terms of the Contract with the Client and generally in accordance with the appropriate ACE Agreement and taking account of the manpower, resources, investigations and testing devoted to it by agreement with the Client. This report is confidential to the Client and Building Performance Prediction Ltd. accepts no responsibility of whatsoever nature to third parties to whom this report or any part thereof is made known. Any such party relies upon the report at their own risk.

©BPP Ltd 2023



1 Executive Summary

1.1 Brief description of development

This development comprises of:

“Demolition of existing fourth floor, replacement of fourth floor and erection of an additional storey to the building, ground floor alterations including new entrances, single storey extension to the rear, removal of existing external fire escape stair to the rear, reconfiguration of existing external plant equipment and introduction of additional plant at roof level, including associated works. Planning use class E throughout the building.”

A Whole Life Carbon Assessment has been undertaken in line with the London Plan 2021.

This document is split into a life cycle assessment and a circular economy analysis, which overall shows the benefits of reusing the external structure of the building regarding the carbon reduction as well as the benefits towards a circular economy.



1.2 Summary of the approach, key commitments, and targets

The design team's strategic approach for the proposed development is longevity and adaptability.

To achieve their objectives the design team is committed to monitor their waste arising from demolition, excavation and construction and promote reuse on site where possible. The materials used for the construction containing higher recycled rate will be prioritised. The majority of the building is to be retained.

The chart below shows that the decision to refurbish the building rather than knock down and replace has a direct impact on the lifetime equivalent carbon emission by 16% (including energy running costs). Figure 2 shows the comparison between the design proposal which has retained much of its material against if this had been an entirely new building.




FIGURE 1 – GLA BUILDING CIRCULARITY




FIGURE 2 – WHOLE LIFE CARBON ASSESSMENT



2 Introduction

This Circular Economy and Whole Life cycle Analysis has been prepared on behalf of McAleer & Rushe Contracts UK Ltd. in support of their full planning application for 161 Drury Lane.

The development comprises:

“Demolition of existing fourth floor, replacement of fourth floor and erection of an additional storey to the building, ground floor alterations including new entrances, single storey extension to the rear, removal of existing external fire escape stair to the rear, reconfiguration of existing external plant equipment and introduction of additional plant at roof level, including associated works. Planning use class E throughout the building.”

This report is to accompany planning application required by London Plan Policy SI7 ‘Reducing waste and supporting the Circular Economy’.

This report will demonstrate how the proposed development will incorporate Circular Economy measures.




FIGURE 3 – GENERAL LOCATION OF DEVELOPMENT



2.1 *Method statement (including key outcomes from workshops/meetings)*

A summary of the process followed up to the point of submission and how the team approached the application of circular economy principles and the production of the Statement.

Workshops have been held with the design teams to discuss and raise awareness of the circular economy.

2.2 *Circular economy aspirations*

The design team has engaged with the circular economy principles. The development had already in place Environmental Management Plan therefore attention was already made on recycling/reusing materials. With the help of circular economy statement all aspects and stages have been looked at to avoid creating waste not only during construction but also during occupancy and end of life of the development.

This shall minimise the waste associated with all stages and areas of the development from site selection to disposal and improve sustainable development outcomes.

The team has looked at the following aspects and strategies to address circular economy principles:

- Reuse as much of the building as possible to limit the extent of demolition.
- Materials arising from demolition and remediation works shall be reused or recycled where possible.
- The design proposal and construction shall reduce material demands and enable building materials, components and products to be disassembled and re-used at the end of their useful life.
- Identify opportunities for managing as much waste as possible on site.
- Provide adequate and easily accessible storage space and collection systems to support recycling and reuse.
- Predict how much waste the proposal is expected to generate and how and where the waste will be managed in accordance with the waste hierarchy.
- How performance will be monitored and reported.



3 Whole Life Cycle Analysis

A Whole Life Cycle Analysis (WLCA) assessment has been carried out using One Click LCA software which follows the BS EN 15978 and RICS PS scope. Refer to the accompanying GLA spreadsheet for details of the WLCA.

The below Figure 4 represents the total materials circularity both in use of materials for the project as well as end of life handling. It is calculated as the average of materials recovered and materials returned.




FIGURE 5 – ELEMENTS AND LIFE CYCLE STAGE WITH SERVICES FOR COMPARISON TO A NEW BUILDING




FIGURE 4 – ELEMENTS AND LIFE CYCLE STAGE WITHOUT SERVICES FOR COMPARISON TO A NEW BUILDING



4 Circular economy goals and strategic approach

4.1 Strategic approach(es)

The following sections provide a summary of the strategic approach:

4.1.1 Circular economy approach for the refurbishment development

| | | |
|-----------------------|--|--|
| PHASE/ BUILDING/ AREA | Frame | Facade |
| STEERING APPROACH | Reuse and refurbish | Reuse and refurbish |
| EXPLANATION | This includes roof and floors | |
| TARGET | 95% diversion from landfill at end of life | 95% diversion from landfill at end of life |
| SUPPORTING ANALYSIS | Life Cycle Assessment | Life Cycle Assessment |

4.1.2 Circular economy approach for the existing site

| | |
|-----------------------|---|
| PHASE/ BUILDING/ AREA | Partial remodelling of areas no major demolition. |
| STEERING APPROACH | Maximise reuse of the existing building |
| EXPLANATION | Waste classification of demolition works and construction works |
| TARGET | 95% diversion from landfill |
| SUPPORTING ANALYSIS | Pre-Demolition report / Site Waste Management Plan |

4.1.3 Circular economy approach for municipal waste during operation

| | |
|-----------------------|----------------------------------|
| PHASE/ BUILDING/ AREA | In use phase |
| STEERING APPROACH | Reusability |
| EXPLANATION | Segregation of operational waste |
| TARGET | 65% diversion from landfill |
| SUPPORTING ANALYSIS | Operational waste management |

4.2 Explaining the strategic approach(es)

An early workshop has been carried out with the design team on the 25th of April 2023 which identified the strategic approach to 'Longevity' and 'Durability' depending on the areas of the development.

The design should meet the long-term needs while being durable and resilient or able to cope with change with little modification, readiness for alternative technologies, different ways of living/working and a changing climate.

The design is considering the needs of the present but with consideration of how those needs might change in the future and designed for change in the forms of periodic remodelling including alterations or replacement on non-structural parts.



4.3 *Draft Circular Economy Statements*

The team has reached an agreement that the following targets and commitments shall be reported against at the full application stage. The following sections outline the potential targets and commitments based on the nine principles:

4.3.1 *Minimise the quantities of materials used.*

A Pre-demolition report will be carried out before any demolition is taking place on the site to maximise the reuse or recycling of the materials. Maximize use of existing building.

4.3.2 *Minimise the quantities of other resources used (energy, water, land)*

The site is located on a brownfield land and not using virgin land for the development. The reuse of the structure will lower demand on energy and water from construction. The energy statement introduces elements such as new double glazing and Heat Pump technology to minimise operational energy.

4.3.3 *Specify and sourcing materials and other resources responsibly and sustainably*

The development will be using the Sustainable Procurement Plan principles to ensure best practice in relation to procurement and resourcing procedures.

4.3.4 *Design for longevity, adaptability or flexibility and reusability or recoverability*

The refurbishment will extend the life and further small modifications could be made in the future to revert to other similar applications.

4.3.5 *Design out construction, demolition, excavation and municipal waste arising*

The Construction Environmental Waste Management will include the hierarchy of material disposal and shall be monitored on Smartwaste portal or similar.

4.3.6 *Manage demolition waste*

The Pre-demolition report shall include a demolition strategy and segregation of the materials to maximise reuse or recycling of the materials and divert them from landfill. This report is also used for Wst 01 credit for BREEAM assessment. The predicted and actual demolition waste shall be reported in the Site Waste Management Plan.

4.3.7 *Manage excavation waste*

Excavation waste is not anticipated for this project due to the extensive reuse of the building.



4.3.8 *Manage construction waste*

The construction waste shall be segregated and monitored on Smartwaste portal, and the predicted and actual waste shall be reported in the Site Waste Management Plan. This is part of the BREEAM assessment Wst 01 credit. Functional Adaptability studies shall be completed for construction waste occurred during operational phase due to maintenance, refurbishment and at the end of life.

4.3.9 *Manage municipal waste*

The development shall provide area for recycling waste and recycling bins within the occupied area to enhance recycling rates. Operational Waste Management Plan shall be developed.



5 Circular economy commitments

5.1 Key commitments

These are based on the 9 principles set out in the 'Circular Economy statement guidance' document. The 'layers' are described as follows:

- Site – The geographical setting, urban location and external works
- Substructure – Excavation, foundations, basements and ground floors
- Superstructure – Load-bearing elements above plinth including roof supporting structure
- Shell/skin – The layer keeping out water, wind, heat, cold, direct sunlight and noise
- Services – Installations to ensure comfort, practically
- Space – The layout, internal walls, ceilings, floors, finishes, doors, fitted furniture
- Stuff – Anything that could fall if the building was turned upside down
- Construction Stuff – Any temporary installations/ works/ materials, packaging and equipment
- Summary – Brief summary of how well the measures will work in contributing to achieve requirements, targets, aspirations
- Challenge – Any potentially conflicting measures re noted here
- Counter Actions – Addresses the challenges identified
- Plan to prove and quantify – How performance will be quantified and monitored

5.1.1 Section A Conserve Resources

TABLE 1 – SECTION A - MINIMISING THE QUANTITIES OF MATERIALS USED

| Layers | Comment |
|----------------------------|---|
| Site | Extensive reuse of the existing building |
| Substructure | Existing to be retained. |
| Superstructure | Existing be retained with some new elements for the new upper floors. |
| Shell/skin | Existing to be retained with new façade added to fourth and new fifth floor with a new roof and replacement of all glazing. |
| Services | Examination of service pipework location and cabling to reduce materials used in the construction. Services have been upgraded. |
| Space | The existing spaces have been remodelling efficiently to meet the requirements of an office block and fire requirements. |
| Stuff | Furniture layouts have been examined to improve efficiency of the manufacturing process and maximise functionality. |
| Construction Stuff | Limited construction site area |
| Summary | Extensive reuse of existing building, minimising material use where possible through design and layout. |
| Challenge | To retain as much of the existing building as possible. |
| Counter Actions | Detailed specification, efficient communications |
| Plan to prove and quantify | Whole Life Cycle Assessment / Functional Adaptability / Material Efficiency / Pre-demolition report |

TABLE 2 – SECTION A - MINIMISING THE QUANTITIES OF OTHER RESOURCES USED (ENERGY, WATER, LAND)

| Layers | Comment |
|--------------|--|
| Site | Existing site being reused to avoid any damage to the site that may need remedial action. |
| Substructure | Existing foundations being reused avoid any damage to the foundations that may need remedial action. |



| Layers | Comment |
|----------------------------|--|
| Superstructure | Existing superstructure being reused avoid any damage to this when remodelling to avoid unexpected works. |
| Shell/skin | The majority of the shell will be maintained, with a new façade on the top two floors, and new double glazed windows to improve energy efficiency. |
| Services | Energy efficient heating and cooling systems / energy efficient lighting and zoning / water flow restrictions |
| Space | Designing for fit for purpose |
| Stuff | Refer to Table 2 |
| Construction Stuff | Local work force/ use reclaimed water for the construction |
| Summary | Minimising energy, water and land use |
| Challenge | Higher initial capital costs associated with specific manufacturers or technology. Use in keeping with the historic nature of the building |
| Counter Actions | Ensure the decisions are not solely driven by lowest capital cost |
| Plan to prove and quantify | Monitoring construction waste & transport (BREEAM Wst 01). Life cycle analysis |

TABLE 3 – SECTION A - SPECIFYING AND SOURCING MATERIALS RESPONSIBLE AND SUSTAINABLY

| Layers | Comment |
|----------------------------|---|
| Site | No site boundary required |
| Substructure | Minimal as reuse of existing. |
| Superstructure | Minimal as reuse of existing new element will try and source locally. |
| Shell/skin | Minimal as reuse of existing new element will try and source locally. |
| Services | Refer to Table 3 |
| Space | Refer to Table 3 |
| Stuff | Locally produced furniture when included in the scope. |
| Construction Stuff | Minimal as reuse of existing. |
| Summary | Locally sourced materials and work force |
| Challenge | Gathering all documentations and aware of all of the local material providers |
| Counter Actions | Extensive research of the local area |
| Plan to prove and quantify | EPD certificates, Manufacturer's specification |

5.1.2 Section B: Design to Eliminate Waste (And for Ease of Maintenance)

TABLE 4 – SECTION B - DESIGNING FOR REUSABILITY RECOVERABILITY/ LONGEVITY/ ADAPTABILITY/ FLEXIBILITY

| Layers | Comment |
|--------------------|---|
| Site | No site modification anticipated. |
| Substructure | Refer to Table 2 |
| Superstructure | Protection measures at exposed areas |
| Shell/skin | Cleaning maintenance strategy |
| Services | Regular maintenance to increase life expectancy |
| Space | Ceiling is washable, durable and easy clean floor finishes |
| Stuff | Furniture that meets the need of the building users |
| Construction Stuff | Organise skips to minimise road trips |
| Summary | Design and maintain the development in such way that material waste is minimised through increasing life span of the materials and services |
| Challenge | Identifying vulnerable and exposed parts of materials |
| Counter Actions | Research and studies |



| Layers | Comment |
|----------------------------|---|
| Plan to prove and quantify | Designing for durability and resilience (BREEAM Mat 05); Operational manual |

TABLE 5 – SECTION B - DESIGNING OUT CONSTRUCTION, DEMOLITION, EXCAVATION AND MUNICIPAL WASTE ARISING

| Layers | Comment |
|----------------------------|---|
| Site | Attention to techniques that clean and enable reuse of excavation materials if any |
| Substructure | As above |
| Superstructure | Optimising the load bearing structure mass |
| Shell/skin | Just in time delivery and secure on-site storage avoiding damage to the materials thus replacement |
| Services | The services are designed as per best practise and standards to minimise energy usage during building operation |
| Space | Easy replacement of damaged materials and fitted furniture |
| Stuff | Minimisation of packaging, off cuts and damage |
| Construction Stuff | Secure on-site storage is limited which will encourage usage of Just in Time (JIT) for construction equipment to avoid damage |
| Summary | Maintenance and lean design |
| Challenge | Lack of research and innovation |
| Counter Actions | Undertake precedent searches, modelling etc. |
| Plan to prove and quantify | Lean design option appraisal, Construction Environmental Waste Management, |

5.1.3 Section C: Manage Waste

TABLE 6 – SECTION C - DEMOLITION WASTE (HOW WASTE FROM DEMOLITION OF THE LAYERS WILL BE MANAGED)

| Layers | Comment |
|----------------------------|--|
| Site | Independent pre-demolition audit, implementing demolition strategies, segregation of materials, monitoring waste flows to maximise reuse/recycling |
| Substructure | Refer to Table 8 |
| Superstructure | As 'Site' comments |
| Shell/skin | As 'Site' comments |
| Services | As 'Site' comments |
| Space | As 'Site' comments |
| Stuff | As 'Site' comments |
| Construction Stuff | Any demolished materials for potential temporary construction road works (crushed stones) |
| Summary | An independent third-party pre-demolition report is required |
| Challenge | Noise, vibration, dust, vehicle movements or congestion |
| Counter Actions | Different working hours, screens covers |
| Plan to prove and quantify | Pre-demolition audit, Site waste management plan (BREEAM Wst 01) |



TABLE 7 – SECTION C - EXCAVATION WASTE (HOW WASTE FROM EXCAVATION WILL BE MANAGED)

| Layers | Comment |
|----------------------------|--|
| Site | Using excavation waste as a resource within the construction site or other local construction projects before sending it to the landfill |
| Substructure | As above |
| Superstructure | As above |
| Shell/skin | As above |
| Services | As above |
| Space | As above |
| Stuff | As above |
| Construction Stuff | As above |
| Summary | Prioritise reuse of excavation waste over sending it to landfill |
| Challenge | Logistical/ space constraints/ supply delay |
| Counter Actions | Identify vacant sites |
| Plan to prove and quantify | Site Waste Management Plan (BREEAM Wst 01) |

TABLE 8 – SECTION C - CONSTRUCTION WASTE (HOW WASTE ARISING FROM CONSTRUCTION OF THE LAYERS WILL BE REUSED OR RECYCLED)

| Layers | Comment |
|----------------------------|--|
| Site | Construction waste measures go above and beyond standards. |
| Substructure | As above |
| Superstructure | As above |
| Shell/skin | Construction waste can occur after the construction phase during operational phase due to maintenance, refurbishment and at the end of life |
| Services | As above |
| Space | As above |
| Stuff | As above |
| Construction Stuff | Construction waste measures go above and beyond standards. |
| Summary | Monitoring and managing construction waste |
| Challenge | Health & Safety concerns, attitude |
| Counter Actions | Increase awareness of the brief, tool box talks |
| Plan to prove and quantify | Site Waste Management Plan, (BREEAM Wst 01) Site sustainability manager, Functional adaptability studies (BREEAM Wst 06) Considerate Construction Scheme |

TABLE 9 – SECTION C - MUNICIPAL AND INDUSTRIAL WASTE (HOW THE DESIGN WILL SUPPORT OPERATIONAL WASTE MANAGEMENT)

| Layers | Comment |
|--------------------|--|
| Site | Provide sufficient space for waste collection lorries for manoeuvring and collection. Advocate space for recycling bins in refuse area |
| Substructure | As above |
| Superstructure | As Above |
| Shell/skin | As above |
| Services | As above |
| Space | Provide recycling bins in every kitchen and studio |
| Stuff | As above |
| Construction Stuff | As above |
| Summary | Segregation of operational waste throughout the building |
| Challenge | Social behaviour |



| | |
|----------------------------|---|
| Counter Actions | Leaflets of appropriate recycling materials |
| Plan to prove and quantify | Operational Waste Management Plan (BREEAM Wst 03) |

5.2 Reporting forms for numerical targets and commitments:

5.2.1 Bill of Materials

Refer to table below:

TABLE 10 - BILL OF MATERIALS

| Section | Result category | Material quantity kg | Material intensity kg/m2 Gross Internal Area | Recycled content by value % | Reused content by value % | Estimated recyclable materials kg/m2 |
|---------|---|----------------------|--|-----------------------------|---------------------------|--------------------------------------|
| 1 | 1 Substructure | 2171.1 | 1.36 | 86.57 | 100 | 1.36 |
| 21 | 2.1 Superstructure: Frame | 273864.44 | 171.53 | 49.87 | 58.48 | 171.53 |
| 2.2 | 2.2 Superstructure: Upper Floors | 177433.5 | 111.13 | 29.46 | 97.78 | 34.37 |
| 2.3 | 2.3 Superstructure: Roof | 2843.01 | 1.78 | 14.67 | 0 | 0.2 |
| 2.4 | 2.4 Superstructure: Stairs and Ramps | 1110.36 | 0.7 | 90 | 0 | 0.7 |
| 2.5 | 2.5 Superstructure: External Walls | 774968 | 485.4 | 0.5 | 74.58 | 479.98 |
| 2.6 | 2.6 Superstructure: Windows and External doors | 13641.31 | 8.54 | 0 | 0 | 8.54 |
| 2.7 | 2.7 Superstructure: Internal Walls and Partitions | 52007.99 | 32.58 | 3.21 | 69.79 | 31.93 |
| 2.8 | 2.8 Superstructure: Internal doors | 3545.67 | 2.22 | 0 | 0 | |
| 3 | 3 Finishes | 57482.48 | 36 | 0 | 39.83 | 33.48 |
| 4 | 4 Fittings, furnishings & equipment | 10010 | 6.27 | 0 | 0 | |
| 5 | 5 Services (MEP) | 23819.03 | 14.92 | 0 | 0 | 12.12 |
| Total | Total | 1392896.89 | 872.44 | 5.78 | 34.67 | 774.21 |

5.2.2 Recycling and Waste Reporting

Refer to table 11.



TABLE 11 - RECYCLING AND WASTE REPORTING

| CATEGORY | TOTAL ESTIMATE | OF WHICH | | | | SOURCE OF INFORMATION |
|--------------------|----------------|-----------------------------|--|--------------------------------|--------------------------------------|--|
| | t/m2 (GIA) | % reused or recycled onsite | % reused or recycled offsite | % not reused/ recycled (max5%) | | |
| | | | | % to landfill | % to other management (incineration) | |
| Excavation Waste | | 10% | 85% | 5% | - | Site Waste Management Plan |
| Demolition Waste | | 5% | 90% | 5% | - | Demolition report |
| Construction Waste | 3.5t/100m2 | - | 95% | 5% | - | BREEAM RFO 2014 V2 Wst 01 (1 credit) Site Waste Management Plan |
| | t/annum | % reused on or off site | % recycled or composted on or off site | % not reused or recycled | | |
| | | | | % to landfill | % to other management (incineration) | |
| Municipal Waste | | - | 65% | 35% | - | Operational Waste Management |

5.3 Circular economy narrative – structured around nine circular economy principles

This part includes clear, strong commitments and targets, a more detailed description of how the targets will be achieved presented in table 11 and 12, the Bill of Materials and Recycling and Waste Reporting Form.

1. Minimise the quantities of materials used

- Summary of the proposed approach: Minimising material use through design and layout.
- Itemised metrics and targets: 20% Recycled aggregates where possible.
- Commitments and measures that will be adopted: Offsite manufacturing where possible.
Modular design, keep the materials as light as possible to avoid additional structural load.



- Anticipated challenges and counter-actions: Maintain quality of the offsite manufacturing process to avoid modifications on site. This can be achieved by detailed specification and efficient communication.

2. Minimise the quantities of other resources used

- Summary of the proposed approach: Minimising energy, water and land use.
- Itemised metrics and targets: Predicted yearly energy and water consumption,
- Commitments and measures that will be adopted: Building Management System, Life Cycle Assessment.
- Anticipated challenges and counter-actions: Higher capital costs associated with manufacturers or technology. Carrying out a life cycle cost analysis can make a difference at the early stages.

3. Specify and resource materials and other resource responsibly and sustainably

- Summary of the proposed approach: Sourcing materials locally where possible with manufacturers having responsible sourced certificates. Use local work force for construction to reduce travel thus carbon.
- Itemised metrics and targets: At least 80% of the materials shall come from local manufacturers.
- Commitments and measures that will be adopted: Monitoring material resources.
- Anticipated challenges and counter-actions: To have all the correct certifications, not out of date. A list of local manufacturers and their products shall be created.

4. Design for longevity, adaptability or flexibility and reusability or recoverability

- Summary of the proposed approach: Design and maintain the development in such way that material waste is minimised through increasing life span of the materials and services.
- Itemised metrics and targets: At least 20% reused at the end of life.
- Commitments and measures that will be adopted: Designing for durability and resilience report providing recommendations for protection measures.
- Anticipated challenges and counter-actions: Identifying all vulnerable and exposed materials, areas through carrying out research and studies.



5. Design out construction, demolition, excavation and municipal waste arising

- Summary of the proposed approach: Lean design of the development with practical maintenance.
- Itemised metrics and targets: Most practical and lowest carbon technologies to be implemented.
- Commitments and measures that will be adopted: Modelling and lean design option appraisal.
- Anticipated challenges and counter-actions: Undertake precedent searches, modelling etc. to missing out on implementing solutions at early stage.

6. Manage demolition waste

- Summary of the proposed approach: An independent pre-demolition report is carried out.
- Itemised metrics and targets: 95% diverted from landfill.
- Commitments and measures that will be adopted: Report predicted and actual waste arising from demolition works. Report the quantities reused or recycled from the waste.
- Anticipated challenges and counter-actions: To avoid noise and vehicle movements or congestions on site, different working hours can be proposed or using screen covers etc.

7. Manage construction waste

- Summary of the proposed approach: Monitoring and managing construction waste.
- Itemised metrics and targets: Minimise construction waste, segregation.
- Commitments and measures that will be adopted: Reporting predicted and actual waste arising from construction site works. Signing up for Considerate Construction Scheme.
- Anticipated challenges and counter-actions: Increase awareness of the brief between site workers through tool box talks etc.

8. Manage municipal waste

- Summary of the proposed approach: Segregation of operational waste throughout of the building.
- Itemised metrics and targets: At least 65% of the operational waste shall be recycled.



- Commitments and measures that will be adopted: Accessible refuse area, providing recycling bins for the building users.
- Anticipated challenges and counter-actions: Display recycling information in each kitchen, studio and common areas to inform the building user of recycling schemes.

5.4 *Plans for implementation:*

This section explains how short-, medium- and long-term targets or commitments will be implemented, monitored and reported. Actual performance against these targets shall be submitted at practical completion.

5.4.1 *Specific plans for short- and medium-term targets*

Who: Sustainability Site Manager

What: Monitor energy and water consumption and material transport to and from site.

When: Energy and water monthly. Transport as applicable

How: Taking notes from the energy and water meters. Material deliveries and skips are monitored and noted at the site entrance.

Who: Site Manager

What: Monitor construction waste

When: At every skip collection

How: Smart waste portal reporting in Site Waste Management Plan

5.4.2 *Programme/method for longer-term targets*

For longer-term targets, this section describes the methods that will be used to ensure they are met and a programme of key milestones provided (completion, monitoring intervals etc.)

BREEAM Man 05.1 Aftercare Support – monitoring of water and energy use for 12 months after the building is occupied

5.5 *End-of-life strategy*

This section describes the strategy for how the proposal's design and construction will reduce material demands and enable building materials, components and products to be disassembled and reused at the end of their useful life.



The information shall be applied in reports such as Functional adaptability, Plant replacement strategy, Building User Guide, Operational Manual etc.



6 Reporting outcomes post-planning/completion

(placeholder for post completion stage)

6.1 *State whether each target or commitment was achieved and provide evidence and supporting documentation.*

(placeholder for post completion stage)

6.2 *Lessons learned.*

(placeholder for post completion stage)



7 Appendices

Refer to excel file B0992 WCLA Drury Lane.xlsx for the breakdown of the input information into the OneClick LCA tool.

Below are some of the headline chart outputs.



FIGURE 6 – LCA CHART OUTPUTS