Loading Schedule - CDY

Project:CDY - GatewayReference:0203Client:ArgentDoc No.0203-LCS1Date:11/05/2023Revision:A



Note:

Channel	Fitting Ref	Qty	Area	w	v	Lamp Source	Control
1	L1	158	Kissing roof	12	24	LED	DMX
2			Kissing roof	12	24	LED	DMX
3	L1	115	Kissing roof	12	24	LED	DMX
4			Kissing roof	12	24	LED	DMX
5	L1	121	Kissing roof	12	24	LED	DMX
6			Kissing roof	12	24	LED	DMX
7	L1	132	Kissing roof	12	24	LED	DMX
8			Kissing roof	12	24	LED	DMX
9	UL1	28	Uplighters both sides of doorways	19,8	24	LED	DMX
10	L2	10	Wall grazer	55	230	LED	DMX
12	FL1	73	Glazing	38	230	LED	DMX

1. Please read in conjunction with Studio 29's drawings and luminaire schedule.

2. Quantities given in this document as guidance, all quantities to be taken from drawings or site measurements when indicated by the electrical contractor prior to 3. Lighting channels given as control groupings only and do not indicate how the fittings should be wired. Please refer to the electrical engineers drawings for wiring