

Marcus Foster

Arboricultural Design & Consultancy

BA (Hons) | NDArb | AATechCert | MSGD | MArborA



TREE WORKS SCHEDULE

Site:

44 Ferncroft Avenue
London
NW3

Prepared by:

Marcus Foster

Tree Works Schedule:

No. 44 Ferncroft Avenue

T1: Leyland Cypress - Fell to ground level and grind out stump
T2: Hazel - Fell to ground level and grind out stump
T3: Cherry - Fell to ground level and grind out stump
T4: Magnolia - Fell to ground level and grind out stump
G4: Camellia / Fatsia - Fell to ground level and grind out stump
G5: Mixed Shrubs - Fell to ground level and grind out stump
T8: Apple - Fell to ground level and grind out stump


No. 42 Ferncroft Avenue

T6: Pittosporum - Prune overhanging growth to within 500mm of boundary; prune to retain even and flowing canopy outline

No. 18 Heath Drive

T7: Holly - Prune overhanging growth to within 500mm of boundary; prune to retain even and flowing canopy outline
T9: Horse Chestnut - Prune overhanging growth by branch lengths of 2-3m to reduce over-extended form, retaining even and flowing canopy outline

Marcus Foster Ltd



Marcus Foster
Arboricultural Design & Consultancy

BA (Hons) | NDARB | AATechCert | MSGD | MArborA

TREE WORKS SCHEDULE

Tree Works Site Plan

