

ter	Description					
	New private surface water drain					
	New private surface water inspection chamber (typ. 450mmØ) upto 3000mm deep					
	New private surface water rodding eye					
	Existing combined sewer					
	Existing combined sewer manhole					
	Description					
	Finished Floor Level (FFL)					
	Proposed Level					
	Existing Level					
	Proposed Fall Gradient					
	Road Gully					
	Linear Drainage Channel					
	Pad Foundations (Refer to Structa drawing 6570-SK003 for details)					
	Kerb line					
	Resurfaced Fire Tender Access					
	Indicates vehicle deterrent road markings					
!	5 10 15					

HEALTH, SAFETY & ENVIRONMENT

It is the responsibility of the client to ensure that those undertaking the works are competent and experienced in the type of work to be undertaken.

In addition to the hazards usually associated with the types of work detailed on this drawing, the following specific hazards have been identified through design risk assessment. The planning and execution of the works should take into account all usual and specific hazards.

Hazards should also be taken into account in the maintenance, operation, decommissioning and demolition of the works.

Unknown contamination may be present

NOTES

- 1. All dimensions are in millimetres (mm) and levels in metres Above Ordnance Datum (mAOD) unless noted otherwise.
- 2. Do not scale from this drawing.
- 3. The copyright in this drawing belongs to Structa LLP; the designs and details may not be used on any project other than that indicated in the titleblock.
- Where CAD or BIM files of the drawing are issued, they are 4. provided for the convenience of others, and shall not be used for construction purposes or relied upon for accuracy or completeness.
- 5. Drainage connection types/points taken from Portakabins layout ref:HUKF:205, and are to be confirmed on site prior to the start of any drainage works.
- This drawing is based on Portakabin "Proposed Site Plan" ref:TSLPP235-PL02 RevC and Site Vision Surveys Limited Topographical & Utility Drawing ref:1219-PKL-12963.

General Drainage Specification

7

- All private drains shall be constructed and commissioned in accordance with the relevant sections of the Building Regulations Approved Documents and relevant British Standards.
- Private surface water drains shall be laid at a minimum gradient 2. of 1 in 100 or to the gradients and invert levels shown.
- 3. Private foul water drains shall be laid at a minimum gradient of 1 in 80 or to the gradients and invert levels shown
- 4. Foul pipework connections to first access point shall be laid at a minimum gradient of 1 in 40 or to the levels shown.
- 5. All connections to be made soffit to soffit unless noted otherwise.
- 6. Pipe bedding to be class 'S' bedding (100 mm granular bed and surround).
- Where cover to soffit of pipe is less than 600 mm in private areas, the following shall apply:-
- a) Vitrified clay pipes provide a 100 mm min. thick concrete bed and surround (instead of class 'S' bedding) and a 13 mm thick compressible filler at each joint.
- b) uPVC pipes provide a concrete bridging (in addition to class 'S' bedding) in accordance with appendix A15, Building Regulations part 'H'.
- All concrete indicated in the construction of drainage 8. infrastructure (pipe bedding, bridging, manholes etc) shall be standardised prescribed concrete ST2 and is to conform to BS EN 206-1 and BS 8500-2. The maximum aggregate size shall be 20mm.
- Foundations adjacent to pipe runs or manholes are to have their 9. formation level set above the invert level no higher than the equivalent of the horizontal distance between the pipe/excavation trench and the foundation, minus 500mm.
- 10. Excavations for manholes, pipe runs etc located within a 45 degree load distribution splay from any adjoining existing foundations, are to be adequately supported for the duration of the works and pipe runs protected as note 8 above.
- 11. Where excavations for pipe runs are parallel and in close proximity to each other and/or other service trenches, The Contractor shall ensure that adequate safety measures, including temporary shoring, are provided in line with current health & safety legislation and good practice. Particular attention is to be paid to adjacent trenches of differing invert levels.
- 12. All existing drainage found on site during the works shall be investigated, its operational status confirmed and the following applied:-
- a) Inoperative drainage shall be cut back and pipe runs filled with concrete grout.
- b) 'Live' drainage shall be advised to the engineer.

P2	08.08.23	VIEWPORTS ADDED, DROP KERB NOTE ADDED	JL	DAM	GWW
P1	02.08.23	FIRST ISSUE	JL	DAM	GWW
Rev.	Date	Description	Drawn	Checked	Approved
•					

## FOR APPROVAL

## PORTAKABIN, ESCP SCHOOL

## DRAINAGE GENERAL ARRANGEMENT

Structural Civil

Geo-environmental



Drawing No: 6570-1005

Revision: P2