HARRINGTON SQUARE PLANTING SCHEDULE

Trees

Number	Abbreviation	Species	Height	Girth	Specification
1	A ca 'S'	Acer campestre 'Streetwise'	500-550cm	25-30cm	Semi-Mature: 4x: RB: Clear Stem min. 200cm
6	A can	Amelanchier canadensis	425-600cm	18-20cm	Extra Heavy Standard: 3x: RB: Clear Stem 175-200cm
4	B pe 'F'	Betula pendula 'Fastigiata'	450-500cm	18-20cm	Extra Heavy Standard: 3x: RB: Clear Stem min. 200cm
1	P pad	Prunus padus	500-550cm	20-25cm	Semi-Mature: 3x: RB: Clear Stem min. 200cm

Specimen Shrubs

Number	Abbreviation	Species	Height	Pot Size	Specification
1	H a 'A'	Hydrangea arborescens 'Annabelle'	40-60cm	5L	Branched: 5 brks: C
1	P ten 'T T'	Pittosporum tenuifolium 'Tom Thumb'	30-40cm	10L	Bushy: 7 brks: C

Hedgerows

Number	Abbreviation	Species	Height	Pot Size	Specification	Density	Length
384	Li vu	Ligustrum vulgare	100-125cm	10L	Individual plant (100-110 high) cut back to 900x50cm to form instant hedge. Single row.	5/m	77m

Shrubs

Number	Abbreviation	Species	Height	Pot Size	Specification	Density
31	Pa te	Pachysandra terminalis		3L	Several Shoots: 9 brks: C	7/m²

Herbaceous

Number	Abbreviation	Species	Pot Size	Specification	Density
12	Aj re	Ajuga reptans	3L	Full Pot: Sept to April planting: British Native-origin: C	9/m²
36	Al mo	Alchemilla mollis	3L	Full Pot: C	9/m²
40	A sco	Asplenium scolopendrium	3L	Full Pot: C	9/m²
38	Ca gl Ca	Campanula glomerata 'Caroline'	3L	Full Pot: C	9/m²
42	Ec pa	Echinacea pallida	3L	Full Pot: C	9/m²
14	Eu ar	Euphorbia amygdaloides robbiae	7.5L	Full Pot: C	3/m²
10	Ir si	Iris sibirica	3L	Full Pot: C	9/m²
12	Pe bi	Persicaria bistorta	3L	Full Pot: Sept to April planting: British Native-origin: C	9/m²
41	Ru sg	Rudbeckia fulgida sullivantii 'Goldsturm'	3L	Full Pot: C	9/m²
36	Se al	Sedum album	3L	Full Pot: C	9/m²
38	Th se	Thymus serpyllum	3L	Full Pot: C	9/m²
10	Ve bo	Verbena bonariensis	3L	Full Pot: C	9/m²

Grasses

Number	Abbreviation	Species	Pot Size	Specification	Density
6	CAR EVE	Carex oshimensis 'Everest'	5L	Full Pot: C	5/m²
24	Ha ma 2	Hakonechloa macra	5L	Full Pot: C	5/m²
38	Li mu	Liriope muscari	3L	Full Pot: C	9/m²
6	Mi yd	Miscanthus sinensis 'Yakushima Dwarf'	5L	Full Pot: C	5/m²
21	Pe vi	Pennisetum villosum	5L	Full Pot: C	5/m²

Seed Mix

Seed Mix Name	Seed Mix Supplier	Density	Area
Flora 3 Seed Mix	Bauder Green	100g/m²	135.28m²

Revisions:
(see rev clouds and notes for additional explanation of change)

Rev.	Description	Dwn.	Chk.	Date
P01	WIP	BX	VS	04.08.2023

Scale Bar

North

outerspace

Urban + Landscape Design
The Boathouse, 27 Ferry Road
Teddington, TW11 9NN

t. 00 44 (0)20 8973 0070 e. info@outerspaceuk.com

Project
Harrington Square

Client
Salboy Ltd.

Dwg No
L-4004

Status
PLANNING

Drawing Title
PLANTING SCHEDULE

Outerspace Project No
LN00700

Date	Scale	Rev	Dwn by:	Chk by:
04.08.2023		P01	BX	VS

Drawing Information
© Copyright Outerspace (Urban Design) Ltd. All Right Reserved

Please note:
Figured dimensions take precedence over scale. Do Not Scale from Drawings.
Outerspace to be informed of discrepancies prior to commencement of works.
All dimensions to be checked on site.