

CONTRACTOR TO SUPPLY AND INSTALL ALL MATERIALS AS IDENTIFIED ON ALL DRAWINGS UNLESS STATED OTHER

FOR EXAMPLE "CLIENT TO SUPPLY"

Flat roof inserted complete and prepared by the contracter TBC by client finish. Roof membrane or equal approved, 18mm WBP plywood with vapour control layer, firrings fall from middle to side walls, 200mm SW joists @ 400cts, 40mm Celotex CW4000 insulation, Visqueen, or equal approved, VCL with taped joints, 40+12.5mm insulated plasterboard skim & decoration.

New 300 cavity wall, 1100mm dense concrete 3.5-7-N/mm2 blocwork. 100mm cavity with insulation and stainless steel wall ties. 100mm dense concrete 3.5-7-N/mm2 blocwork, 13mm two coat palaster work.

The new FD30 Two panels doors installed by the contractor and the client supply.

All new foundations to be minimum 450mm wide trench fill foundations to extend to existing foundations with FND2 concrete mix or other approved by engineer, Formation level to be min 1000mm below GL and agreed on site with the engineer and building control agreement.

			Date:	September 2023	ARCH.
	Loc:	Flat 1 226 Camden Road London NW1 9HG	Esc:	1/50	
			Ref ^a :		11
	Act:	Paulo do Nascimento Pinheiro Afonso Architect			14