



6No. Cross Stitching/Pinning of Cracks to each pier: Mark out and agree with engineer positions of X pinning dependent upon expected depth of ties. Drill 18mm Staggered holes approx. 300 mm crs apart. Drill 18mm holes approx. 1250mm deep. Insert 10mm stainless steel tie and fully back-grout. Leave tie below the finished surface ready for striking off and plugging with clear resin mixed with brick dust polished flush to brick face.

Notes:

1. This drawing to be read in conjunction with all architects and engineers drawings sketches and the specifications.
2. Do Not Scale.
3. All dims in millimeters.
4. If in doubt ask.

Gate 2 Elevation (view from main road)

St Stephens Church & Hampstead Hill School Boundary Wall  
 J9034 - SK. 03 Rev. 00 date: 14.03.2022  
 N.T.S

**BYRNELOOBY**  
 AN **avesa** COMPANY

FOR INFORMATION