#### Tree Data Schedule


Reference G = Group H = Hedge	Age & Species	Height (m)	Crown Ht(m)	<b>Diameter</b> (cm)	Crown Spread (m) N W E S	Scaled Tree Diagram (m)	Notes	Recommendations (Independent of any development proposals)			Amenity Value
										Physiological Condition	Life Expectancy (yrs)
								Priority	Inspect Freg (yrs)	Structural Condition	
T1	Semi-Mature				<b>7</b>	<u>!</u> 5	Position: Situated on third party land. Form: Multi-stemmed at ground level with a compact crown.			Moderate	Low
	Bay Laurel 8	4.5	34	3 3		History: Maintained by pruning.  Defects: No significant defects observed.	No action required.		Good	40+	
					3		Other: Limited inspection. Recorded stem diameter is equivalent for 8 stems at 12cm diameter.	n/a 3	Good	C	
T2	Early-Mature			35	6.5 5 6		Position: Situated on third party land.  Form: Twin-stemmed at 6m with a balanced crown.  History: No evidence of significant pruning.  Defects: No significant defects.  Other: Limited inspection, dimensions estimated.	n/a 3  No action required.		Moderate	Moderate
	Robinia pseudoacacia.	13	8							Good	40+
								I-	T _	Good	В
	Semi-Mature				av	[25]		n/a	3		
G3	Cotoneaster	aster av	av		4 5 1 3 each		Position: Situated on third party land.  Form: Single stemmed and leaning with a slightly unbalanced crown.  History: Occasional pruning wounds due to crown lifting.  Defects: No significant defects observed.  Other: Limited inspection, dimensions estimated.	No action required.		Moderate	Low
			3.5							Good	40+
	Cotoneaster sp.							n/a	3	Fair	C

### **Statutory Protection**

We were informed by Rav Curry of London Borough of Camden via email on the 10<sup>th</sup> October 2023 that:

- The site lies within the **Primrose Hill Conservation Area**.
- There are no tree preservation orders affecting trees within the site.
- There are no tree preservation orders immediately adjacent to the site; a Corkscrew Willow in Fitzroy Yard, outside the rear of 6 Primrose Hill Studios, is the nearest TPO tree.


#### **Photographs**




























Trees unsuitable for retention due to their very poor condition.







## Excerpts from the Arboricultural Impact Assessment



It is proposed to construct a new basement, rear extension and undertake landscaping works in the rear garden as indicated on the drawings in Appendix 6. The existing layout is indicated in black, the proposed basement in shown in blue, and the footprint of the proposed ground floor extension and landscaping works The table below summarises the potential impact on trees due to various activities. Trees Potentially Affected Tree Removal Two 3m tall Portuguese Laurel Tree Pruning RPA: Basement Foundation RPA: Other Foundations

RPA: Soil Compaction Other potentially damaging activities often associated with construction sites include demolition or the careless use of plant machinery, hazardous materials, or fires. All of the above potential impacts are considered in detail throughout this Section.

Tree Removal

RPA: New Hard Surface RPA: Replace Existing Surface


RPA: Change of Ground Levels

All trees to be removed are indicated on the Impact Assessment Plan and are listed below:

**Retention Category A:** Our survey did not identify any Retention Category A trees.

**Retention Category B:** It is proposed to retain all Retention Category B trees.

These are small trees (height 3m) located within a rear garden and are not visible from public vantage points. Their removal shall have little to no impact on the visual amenity of the locality, so they are not considered to be a material Retention Category U: Our survey did not identify any Retention Category U



**Mitigation Planting** The rear garden offers opportunity to plant replacement vegetation as part of a post-development

landscaping scheme. **Impact on Tree Canopies** 

The retained tree canopies are sufficiently far from proposed building works and access routes such that they

Impact on Tree Roots **Basement Foundations:** 

The proposed basement shall encroach into approximately 6% of the theoretical Root Protection Area of Ti. Whilst an incursion of 6% is considered to be relatively minor, T1 grows beyond a boundary wall on third-party land; the foundations of this boundary wall are likely to have an influence on Tr's root proliferation within the garden of No: 27. Consequently, the portion of T1's RPA affected by the proposed basement is likely to be

Nevertheless, is it recommended to install the basement in a manner that does not disturb the soils beyond its proposed footprint. This may be done via contiguous piling, sheet piling, pinning or any similar method which limits excavation for the basement footprint in the direction of RPAs. Excavating a temporary batter slope within the RPA should be avoided.

considerably less than 6%.

The foundations for the new rear extension do not encroach within the Root Protection Area of any retained tree. Consequently, no restrictions on foundation design or implementation are considered necessary from an arboricultural perspective.

Other Foundations:

No other foundations are proposed within Root Protection Areas. **New Surfaces:** 

No new hard surfaces are proposed within Root Protection Areas. Replacement of Existing Surfaces:

replaced with a new paved surface and/or turf. To ensure little to no impact, excavation should be limited to the removal of the existing surfaces and their sub-base using hand tools. No detrimental impact should occur

**Underground Services:** 

Wherever possible, any new underground services should be located outside of RPAs. Where this is not possible, the project arborist should be consulted prior to any excavation. Trenching for underground services is one of the most damaging activities on construction sites, and NJUG guidelines<sup>8</sup> should be in accordance with a site-specific Arboricultural Method Statement.

Changes in Ground Levels: It is proposed to lower the existing ground levels at the very rear of the dwelling. However, no ground level

Two Portuguese Laurel are to be removed to facilitate the proposal. These are small trees and are hidden from public vantage points. The impact of tree removal on local amenity levels shall be minimal.

No pruning works are required to enable the proposal.

Basement foundations are proposed within the theoretical RPA of T1. However, the potential impact is likely to be minor due to the lack of rooting activity anticipated within the site.

Existing paving and gravel surfaces are to be replaced with new paving and turf. Little to no impact on trees

No new hard surfacing is proposed in Root Protection Areas.

No ground level changes are proposed over Root Protection Areas.

Adequate space has been allowed between the proposal and all trees such that no future pressure to overlyprune or remove trees shall occur as a consequence of the proposal.

**Arboricultural Method Statement** 

BS 5837 recommends that a detailed methodology is agreed in the form of an Arboricultural Method all tree protection measures and limitations on construction activity. All of the issues raised within this Impact Assessment should be covered by the Method Statement.

> See Section 7 for a more


detailed assessment



# Existing Layout (Black)

Proposed Basement (Dashed Blue)

Proposed Extension & Garden Layout (Pink)



Drawing No: | CCL 11666 Impact Assessment Plan

CROWN

Category A tree


Category C tree Category U tree

Tree Retention Categories Stems & canopies shown Category B tree

Trees unsuitable for retention due to their very poor condition.

Trees of high quality with an estimated life expectancy of 40+ years. Usually large trees with significant presence or smaller trees with excellent form. Retention of these trees is highly desirable. Trees of moderate quality with a life expectancy of 20+ years.
Usually maturing trees, or younger trees with good form. Retentior of these trees is desirable though less than Category A trees Unremarkable trees of low quality and merit. Individual specimens





MN = Measured North: Tree to be removed to defined by site features. Tree to be removed where rows of trees are not due to its low quality aligned N-S or E-W. Proposed pruning

