

Existing Plan

Window 2 to be reinstated

Electric cables / gas / water pipes in this corner

Window 1 to remain blocked



WALL A

WALL B



WINDOW 1

WINDOW 2

Wall A was observed to be a non loadbearing 75mm thick light weight block. This wall is an infill wall and not structural.

Wall B was observed to be timber stud wall. This wall is also non loadbearing and was installed to cover up the service cables and pipes entering the building from street level.

Note this space is beneath the original staircase to enter the building.




CABLES AND PIPES ENTERING THE BUILDING



Proposed window 2 potential clash with zinc DPC

Desirable to connect this RWP direct to gully

Rev	Date	By	Description	Check
 Arun Associates Chartered Surveyors & Property Consultants				
Project Flat D 13 Wedderburn Road NW3 5QS				
Title Proposed alteration				
Scale	File reference	Drawing Number		
nts		165-22 /sk-01		