





REVISION	DATE	REASON
PR1	30.06.23	REVIEW
PR2	06.10.23	PLANNING ISSUE
PR3	23.10.23	PLANNING ISSUE




Amended Items in Yellow




638 - 28 CHALCOT SQUARE





SH-03 Proposed Door Schedule





NOTE: CLIENT TO REVIEW AND APPROVE ALL FINISHES






PROPOSED DOORS								
Ref	Descrip.	Proposal	Visual	Leaf Size	Fire Rating	Ironmon.	Architraves	Notes
<p>NOTE:</p> <p>1. Building control to review all new doors to determine required fire integrity etc.</p> <p>2. All alterations pending planning approval</p>								
LOWER GROUND FLOOR								
DLG.01	External door to storage at front	Existing door to be made good and repainted as per schedule						N/A
DLG.04	External double doorset to rear garden from bedroom	Existing external doors to be removed to accommodate new layout - ref. plan and elevations New door to be fabricated with double glazing and multi-point locking system as per elevations						
DLG.07	New door to utility room / bathroom	Masonite 2 Panel Smooth New architraves required as per proposed decorative mouldings schedule New ironmongery as per schedule, ref. type		Existing structural opening (TBC)	FD 30 S (TBC)			AR.01
DLG.08	New door to kitchenette	Masonite 2 Panel Smooth New architraves required as per proposed decorative mouldings schedule New ironmongery as per schedule, ref. type		W: 826mm H:2040mm	FD 30 S (TBC)			AR.01

Ref	Descrip.	Proposal	Visual	Leaf Size	Fire Rating	Ironmon.	Architraves	Notes
DLG.09	New door to utility room	Masonite 2 Panel Smooth New architraves required as per proposed decorative mouldings schedule New ironmongery as per schedule, ref. type		W: 826mm H:2040mm	FD 30 S (TBC)		AR.01	
DLG.10	New door to bathroom	Masonite 2 Panel Smooth New architraves required as per proposed decorative mouldings schedule New ironmongery as per schedule, ref. type		W: 826mm H:2040mm	FD 30 S (TBC)		AR.01	
DLG.11	New door to bedroom from lobby	Masonite 2 Panel Smooth New architraves required as per proposed decorative mouldings schedule New ironmongery as per schedule, ref. type		W: 826mm H:2040mm	FD 30 S (TBC)		AR.01	Structural engineer to provide design for structural opening
DLG.12	New external entrance door from front lightwell	New external entrance door in place of existing window opening New door to be fabricated with double glazing and multi-point locking system as per elevations		TBC	TBC			Structural engineer to provide design for structural opening

Ref	Descrip.	Proposal	Visual	Leaf Size	Fire Rating	Ironmon.	Architraves	Notes
GROUND FLOOR								
DG.01	Main entrance door	Existing door to be re-hung, made good and painted as per schedule Client to confirm security requirements New ironmongery as per schedule, ref. type						
DG.02	Door from entrance hallway to dining room	Existing door and architraves to be retained, made good and repainted as per schedule New ironmongery as per schedule, ref. type						Existing to be retained
DG.03	Doorset from dining room to kitchen	Existing doors and architraves to be retained, made good and repainted as per schedule New ironmongery as per schedule, ref. type (existing hinges to be retained)						Existing to be retained

Ref	Descrip.	Proposal	Visual	Leaf Size	Fire Rating	Ironmon.	Architraves	Notes
DG.04	Door from entrance hallway to kitchen	<p>Existing door to be fixed shut and ironmongery removed.</p> <p>On kitchen side, wall is to be built out behind the cupboards to preserve door and mouldings while accomodating new layout</p> <p>Architraves and door to be made good and repainted on hallway side</p>					Existing to be retained	
DG.07	Door from hallway to WC	<p>Masonite 2 Panel Smooth</p> <p>New architraves required as per proposed decorative mouldings schedule</p> <p>New ironmongery as per schedule, ref. type</p>		Existing structural opening (TBC)	FD 30 S (TBC)		AR.01	Glazed panel overhead to be infilled
DG.08	Door from hallway to utility room	<p>Masonite Half Light Smooth Clear Glazed</p> <p>New architraves required as per proposed decorative mouldings schedule</p> <p>New ironmongery as per schedule, ref. type</p>		Existing structural opening (TBC)	FD 30 S (TBC)		AR.01	If FD 30 is required then alternate spec. may be required - BC to confirm Glazed panel overhead to be infilled
DG.10	External door from utility room to rear garden	<p>Existing door & upper glazed panel to be replaced - to match existing ref. elevations</p> <p>New door to be fabricated with double glazing and multi-point locking system</p> <p>New ironmongery as per schedule, ref. type</p>						

Ref	Descrip.	Proposal	Visual	Leaf Size	Fire Rating	Ironmon.	Architraves	Notes
FIRST FLOOR								
D1.01	Door from stairwell to living room	Existing door and architraves to be retained, made good and repainted as per schedule New ironmongery as per schedule, ref. type						Existing to be retained
D1.02	Door from living room to study	Existing door and architraves to be retained, made good and repainted as per schedule New ironmongery as per schedule, ref. type						Existing to be retained
SECOND FLOOR								
D2.01	Door from stairwell to bedroom	Masonite 2 Panel Smooth New architraves required as per proposed decorative mouldings schedule New ironmongery as per schedule, ref. type		Existing structural opening (TBC)	FD 30 S (TBC)			AR.01
D2.02	Door from stairwell to storage	Masonite 2 Panel Smooth New architraves required as per proposed decorative mouldings schedule New ironmongery as per schedule, ref. type		Existing structural opening (TBC)	FD 30 S (TBC)			AR.01

Ref	Descrip.	Proposal	Visual	Leaf Size	Fire Rating	Ironmon.	Architraves	Notes
D2.04	Door from bathroom to bedroom	Masonite 2 Panel Smooth New architraves required as per proposed decorative mouldings schedule New ironmongery as per schedule, ref. type		Existing structural opening (TBC)	(TBC)		AR.01	
THIRD FLOOR								
D3.02	Door from landing to single bedroom at front	Masonite 2 Panel Smooth New architraves required as per proposed decorative mouldings schedule New ironmongery as per schedule, ref. type		Existing structural opening (TBC)	FD 30 S (TBC)		AR.01	
D3.03	Door from landing to bathroom	Masonite 2 Panel Smooth New architraves required as per proposed decorative mouldings schedule New ironmongery as per schedule, ref. type		Existing structural opening (TBC)	FD 30 S (TBC)		AR.01	
D3.05	Door to double bedroom at front	Masonite 2 Panel Smooth New architraves required as per proposed decorative mouldings schedule New ironmongery as per schedule, ref. type		Existing structural opening (TBC)	FD 30 S (TBC)		AR.01	
D3.06	Door from landing to single bedroom at rear	Masonite 2 Panel Smooth New architraves required as per proposed decorative mouldings schedule New ironmongery as per schedule, ref. type		Existing structural opening (TBC)	FD 30 S (TBC)		AR.01	