COLOURS CODES

NAVY: rgb(27,49,57)
RED: rgb(255,54,33)
WHITE : rgb(255,255,255)
GREY : rgb(48,63,71)
BLACK : rgb(0,0,0)

databricks

14

11

PREPARATION AND BRIEF

14 WINDMILL STREET

11-13 WINDMILL STREET

A WINDMILL STREET - FRONT ELEVATION
Scale: 1:100

FASCIA SIGNAGE:
OVER MAIN ENTRANCE.
INDIVIDUAL 25MM THICK
LETTERING AND LOGO IN
POWDER COATED ALUMINIUM.
PEGGED 25MM FROM FASCIA.
SUBJECT TO PLANNING.

AWNING:
CHANGING FABRIC ON
EXISTING FRAME TO "NAVY".

PROJECTING SIGN
EACH SIDE:
EXTRUDED
ALUMINIUM SIGN.
BAR IN "BLACK".
SUBJECT TO PLANNING.

CLIENT
DATABRICKS

PROJECT
DATABRICKS, 11-14 WINDMILL STREET, W1

DRAWING TITLE
WINDMILL STREET
FRONT ELEVATION

STATUS	DRAWN	CHECKED
INFORMATION	SA	AC/PR

SCALE	DATE
1:50@A1 / 1:100@A3	08/12/2023

DRWG NO.
2309_570

REVISION