

PLANT SCHEDULE

Client:	University College London Hospitals Charity	Date Created:	26/10/2018
Project:	BEDFORD PASSAGE DEVELOPMENT	Created by:	HLM
Location:	London	Schedule no.:	BPD-HLM-XX-XX-SH-L-45000
Schedule name:	BEDFORD PASSAGE DEVELOPMENT - Planting Schedule		
Drawing ref.:	BPD-HLM-00-00-DR-L-45001		
Revision:	C08 - Stage 5 Issue	Date Issued:	24/01/2023

NOTE: Stage 5 Issue for North House and Workhouse only.

NOTE: All Native plant material must be sourced from Flora Locale Code of Practice suppliers.

LEVEL 00 - WORKHOUSE FRONTAGE

Trees

Abbrev.	Name	Girth/Dia. cm	Height cm	Root Zone	Specification	Planting Layout	Ultimate Spread m ²	Ultimate Height m	Ctr m	No./m ²	Qty
T00-5	Ginkgo biloba	16-18	400-450	RB	3x Heavy Standard, cs min 200cm; 5 brks	Refer to detail landscape plan	8-10	15-20			2
											2

H00 - Hedge Type 1

Abbrev.	Name	Girth/Dia. cm	Height cm	Root Zone	Specification	Planting Layout	Mix %	Lin. M	No. rows	No. / lin. m	Qty
Hedge	Carpinus betulus		80-100	2L	Bushy; 6 brks	single row, 250mm apart.	100	18.7	1	4	75
Herbaceous	Allium sphaerocephalon		40-60	2L	1+1; Transplant - seed raised	Groups of 1-3, evenly between buxus sempervirens	100	18.7	1	9	168
											168

