Do not scale this drawing.

NOTES
Cross refer to Drg No 400.001 for new brick string course detail.

Render retained. Allow for up to 10% render repair/replacement in small areas.
New render for repair: 1 part Portland Cement mixed 4 parts yellow-brown quartz and flint sand <5mm.

Paint retained but allow for 5% removal where failing. Prepare and redecorate all painted surfaces including window cills at basement level with Keim Soldalit. Colour: To match existing.

No 8S looking north.

No 8S looking south.

KEY

Area of render known to require replacement.

Timber repair

0 1 2 3 4 5 metres

Rev A - 17.03.24 Additional notes added.

Scale 1:50	Job LONDON, Lincoln's Inn New Square	CCA
Drg No 0400/008/A	Title Elevation of No8 South	
Date 21.02.2024	This document is copyright and the property of Chantrey Conservation Architects Ltd. Any copies of this drawing made by any method must also include a copy of this legend. ©Chantrey Conservation Architects Ltd	