

**NOTES**  
 Cross refer to Drg No 400.001 for new brick string course detail.

Render retained. Allow for up to 5% render repair/replacement in small areas.  
 New render for repair: 1 part Portland Cement mixed 4 parts yellow-brown quartz and flint sand <5mm.

Paint retained but allow for 5% removal where failing. Prepare and redecorate all painted surfaces including window cills at basement level with Keim Soldalit. Colour: To match existing.



Cement mortar and decayed bricks removed with new brick string course introduced. Allow for 50% slate replacement with new lead cover flashing.

Surface mounted cables retained.

Lightly overhaul windows and redecorate outer face only.

Build-up of paint stripped from vent to improve ventilation. Vent repainted.

New French drain introduced to base of wall beneath the existing paving. (Phase 2)

Mortar repairs to plinth.




No 8N looking north.



No 8N looking south.


**KEY**

 Area of render known to require replacement.

 Timber repair



Rev A - 17.03.24 Additional notes added.

Scale 1:50	Job LONDON, Lincoln's Inn New Square	
Drg No 0400/009/A	Title Elevation of No8 North	
Date 21.02.2024	This document is copyright and the property of Chantrey Conservation Architects Ltd. Any copies of this drawing made by any method must also include a copy of this legend. ©Chantrey Conservation Architects Ltd	