

Do Not Scale.
 All Figured Dimensions To Be Checked On Site Prior To Construction.
 All Copyright Reserved.



- GENERAL NOTES:**
1. ALL SERVICES/ROUTES THROUGHOUT BUILDING TO BE FULLY COORDINATED ON SITE.
 2. DRAWING TO BE READ IN CONJUNCTION WITH THE INSTALLATION SPECIFICATION AND ALL OTHER RELEVANT DRAWINGS.
 3. UNLESS OTHERWISE STATED: ALL SOILS AND WASTES PIPEWORK TO BE COPPER.
 4. ACCESS POINT TO BE PROVIDED AT ALL CHANGES OF DIRECTIONS FOR MAINTENANCE.
 5. ALL SANITARY APPLIANCES TO BE FITTED WITH ANTI-SIPHON TRAPS WITH 75mm SEAL TRAPS ON WHBS TO BE CHROME PLATED.
 6. ALL PENETRATION THROUGH FIRE COMPARTMENTS TO BE FIRE STOPPED. SEE ARCHITECTS DRAWING FOR LOCATION. ALL PENETRATIONS THROUGH FLOORS TO BE FIRE STOPPED.
 7. ACCESS/RODDING POINTS IN STACK TO BE INSTALLED AT ALL LEVELS.
 8. ALL WC OVERFLOW SHALL BE INTERNAL OVERFLOW.
 9. CONDENSATE WASTE FOR ALL FAN COILS TO BE ROUTED TO NEAREST SVP & CONNECTED VIA A HEP20 AIR SEAL TRAP.

- NOTES:**
- 1 1000 COMMON WASTE DROPS TO HIGH LEVEL BELOW
 - 2 1000 COMMON WASTE RUNS AT HIGH LEVEL BELOW
 - 3 1000 COMMON WASTE CONNECTS TO EXISTING WASTE STACK IN THIS AREA. FINAL LOCATION TO BE CONFIRMED ON SITE
 - 4 DURGOO AIR ADMITTANCE VALVE
 - 5 1000 WASTE FROM WC TO 1000 COMMON
 - 6 350 TRAPPED WASTE FROM WHB TO 500 COMMON

Revision				
Rev	Description	By	App By	Date
T01	TENDER ISSUE	JH		11/03/2024
T02	AMENDED TO GA 26/03/2024	DG		26/03/2024

CLIENT: **UNISON**

PROJECT: **UNISON HQ**

DRAWING TITLE: **FIRST FLOOR - PROPOSED SOILS & WASTE**

DRAWN BY: J.HARPER	STATUS: STAGE 3	DATE: FEB'24
PROJECT No.: L2604	REV: T02	SCALE: 1:100

DRAWING No.: **UNI-LSD-XX-01-DR-M-0400**



LEHNDING SERVICES DESIGN LTD
 Unit 10, 10 Redlands Crescent, Larne, Co. Antrim, N Ireland, BT40 1FF.
 28 Manor Green Road, Epsom, London, KT19 8RA.
 Tel: +44(0) 2828 277 123 Web: www.lehding.co.uk Email: info@lehding.co.uk