

Do Not Scale.  
All Figured Dimensions To Be Checked On Site Prior To Construction.  
All Copyright Reserved.



- GENERAL NOTES:**
1. ALL SERVICES/ROUTES THROUGHOUT BUILDING TO BE FULLY CO-ORDINATED ON SITE.
  2. DRAWING TO BE READ IN CONJUNCTION WITH THE INSTALLATION SPECIFICATION AND ALL OTHER RELEVANT DRAWINGS.
  3. ALL PIPEWORK TO BE INSULATED TO BS EN ISO 12241, USING CLASS O INSULATION, MINIMAL THICKNESS AS PER INSULATION SCHEDULE.
  4. ALL WATER SERVICES SHALL BE PRESSURE TESTED AND DISINFECTED AFTER INSTALLATION.
  5. ALL PLUMBING PIPEWORK TO BE COPPER. EXPOSED PIPEWORK TO BE CHROME PLATED AS COPPER, TABLE X, IN ACCORDANCE WITH BS2871, CAPILLARY JOINTED WITH LEAD FREE SOLDER.
  6. ALL SANITARY WARE TO BE FITTED WITH REGULATING / ISOLATING VALVES ON MWS AND HWS PIPEWORK.
  7. ALL CONCEALED PIPEWORK TO BE REASONABLY ACCESSIBLE THROUGHOUT ITS LENGTH IN ACCORDANCE WITH BUILDING REGULATIONS. ACCESS PANELS TO BE PROVIDED ADJACENT TO ALL VALVES WHEREVER THE SAME MIGHT OTHERWISE BE CONCEALED.

- NOTES:**
- 1 220 MMS & 150 MMS DROPS FROM LOW LEVEL TO BELOW
  - 2 150 MMS & HWS SERVING WHB
  - 3 220 MMS & 150 HWS RUNS AT HIGH LEVEL BELOW. FINAL ROUTE TO BE CO-ORDINATED ON SITE
  - 4 220 MMS & 150 HWS RISES FROM BELOW TO HIGH LEVEL
  - 5 150 MMS SERVING WC

**TRACE HEATING**

ALL HOT WATER SUPPLY PIPEWORK TO BE INSTALLED WITH TRACE HEATING

Revision				
Rev	Description	By	App By	Date
T01	TENDER ISSUE	JH		11/03/2024
T02	AMENDED GA DATED 26/03/2024	DG		26/03/2024

CLIENT: **UNISON**

PROJECT: **UNISON HQ**

DRAWING TITLE: **FIRST FLOOR - PROPOSED PLUMBING**

DRAWN BY: <b>J.HARPER</b>	STATUS: <b>STAGE 3</b>	DATE: <b>FEB'24</b>
PROJECT No.: <b>L2604</b>	REV: <b>T02</b>	SCALE: <b>1:100</b>

DRAWING No.: **UNI-LS-D-XX-01-DR-M-0300**



**LEHNDING SERVICES DESIGN LTD**  
Unit 10, 10 Redlands Crescent, Larne, Co. Antrim, N. Ireland. BT40 1FF.  
28 Manor Green Road, Epsom, London, KT19 8RA.  
Tel: +44(0) 2828 277 123 Web: www.lehding.co.uk Email: info@lehding.co.uk