Rev C02 Proposed works to doors revised in line with comments from Conservation Officer



1:50 @ A1 3004

Demolition Scope of Works

5. Existing doors removed for acoustic upgrades off-site.

- 7. Minor alterations to stair arrangement of newly formed gallery platform
- 8. Alterations to historic ceiling to allow for AV/Lighting rigging installation. 600x600mm openings formed for installing structural supports into L03 slab and services infrastructure - ceiling reinstated to match existing with 150mm diameter flush finished cover plates introduced

- with new ceiling installed
- 18. Consented but not built raised handrail design to be revised

5 m

15. Decorative soffit mouldings to be taken down and reinstated below new lowered bulkhead introduced for supply air distribution slot grille 16. Section of ceiling to be taken down for installation of ventilation ductwork

20. New door opening from lobby G.44 into Stair A to match opening into Stair B 21. Non-original door removed and opening in non-original partition enlarged

Notes:

Drawings are based on survey data and may not accurately represent what is physically present.

Do not scale from this drawing. All dimensions are to be verified on site before proceeding with the work.

All dimensions are in millimetres unless noted otherwise.

Purcell shall be notified in writing of any discrepancies.

