




The existing structural information shown on these drawings is based on visual inspection of the building, limited opening up works and relevant archive information. All details of the existing construction are subject to confirmation by the Contractor during the works on site. No materials are to be ordered until the relevant details and conditions are confirmed by the Contractor on site. Should the contractor discover any discrepancies between the assumed existing structure and what is found on site they should notify the engineer immediately, and await further instruction

1. This drawing is to be read in conjunction with all relevant architects, engineers and specialists drawings and specifications.
2. Do not scale from this drawing in either paper or digital form. Use written dimensions only. To check drawing has been printed to the intended scale the above bar should be 100mm.
3. Any setting out dimensions shown in red are to be confirmed by the architect. All dimensions are to be checked by the contractor against site dimensions prior to fabrication /commencement of work on site. Beams and columns are to be centred on grid unless noted otherwise. Setting out of steelwork is shown to the centre of symmetric sections and to the back face of PFCs and RSAs.
4. Investigations required as per HTS sketches SK002 and SK006 to determine extent of load bearing structure. Proposed works shown on these drawings are therefore indicative only and subject to strip out works and investigations
5. Access not available to visually inspect and investigation ground and basement areas due to existing tenants

Proposed Steel Cols		Proposed Steel Beams	
Ref	Type	Ref	Type
C2	SHS100x100x10	B1	UC203x203x71
C3	UC254x254x107	B2	UB203x133x30
C4	SHS150x150x10	B3	UC254x254x107
C5	RHS400x200x12.5	B5	UC152x152x23
C6	RHS300x200x12.5	B6	UC203x203x46
		B7	UB254x146x43
		B8	PFC150x75x18
		B9	UB203x133x25
		B10	UC305x305x198

Proposed Floors	
Ref	Description
1	200thk RC slab
2	200x50wd C24 joists at 400c.c. 22mm OSB board screwed to top face of joists
3	30thk steel mesh grating rated for 5kN/m2 for max span 1500mm
4	130thk profiled NWC slab on TATA Comflor 60 0.9mm gauge deck with A142 mesh top and 1no. H16 bar per trough

Legend	
	Proposed RC structure
	Proposed Steel Framing
	Red dimension TBC by architect
	PS1 - 430lg x 215wd x 150dp MC padstone
	Moment connection
	Crank



Rev	Date	By	Eng	Amendment
P3	03.05.24	HS	DP	Revised Stage 2 Issue
P2	26.04.24	HS	DP	Revised Stage 2 Issue
P1	09.12.21	MC	GW	Stage 2 Issue

HEYNE TILLET STEEL STRUCTURAL & CIVIL ENGINEERS
<http://hts.uk.com/>

Job Name
Southampton Row, 31,
 Holborn, London
 WC1B 5HA
 Drawing Title
Proposed
First Floor Plan

Purpose of Issue Preliminary Scale at A1 1 : 100

Drg No **2459-HTS-00-01-DR-S-2110**

HTS Job No Suitability S1 Rev **P3**




The existing structural information shown on these drawings is based on visual inspection of the building, limited opening up works and relevant archive information. All details of the existing construction are subject to confirmation by the Contractor during the works on site. No materials are to be ordered until the relevant details and conditions are confirmed by the Contractor on site. Should the contractor discover any discrepancies between the assumed existing structure and what is found on site they should notify the engineer immediately, and await further instruction

- This drawing is to be read in conjunction with all relevant architects, engineers and specialists drawings and specifications.
- Do not scale from this drawing in either paper or digital form. Use written dimensions only. To check drawing has been printed to the intended scale the above bar should be 100mm.
- Any setting out dimensions shown in red are to be confirmed by the architect. All dimensions are to be checked by the contractor against site dimensions prior to fabrication /commencement of work on site. Beams and columns are to be centred on grid unless noted otherwise. Setting out of steelwork is shown to the centre of symmetric sections and to the back face of PFCs and RSAs.
- Investigations required as per HTS sketches SK002 and SK006 to determine extent of load bearing structure. Proposed works shown on these drawings are therefore indicative only and subject to strip out works and investigations
- Access not available to visually inspect and investigation ground and basement areas due to existing tenants

Contractor to allow for localised remedial works to soffit including reinstating cover to filler joists and any areas where there has been loss of full depth of clinker concrete

Existing floor structure demolished to form void for crange. Floor adjacent to be propped to suit. Structural approach to be confirmed once structural investigations are completed.



Columns to be confirmed through structural investigations

Steel moment frames from level 1 to level 4. Allow for moment connections between all B3 beams and C3 columns

Support for stair unknown, trimmers to be added once stair support is confirmed through investigations

New lintels on smaller demo openings

Localised areas of water damage have been observed on site. Allow for removing clinker locally to expose and brush back corrosion of filler joists. Remedial extent TBC following site investigations

Proposed Steel Cols		Proposed Steel Beams	
Ref	Type	Ref	Type
C2	SHS100x100x10	B1	UC203x203x71
C3	UC254x254x107	B2	UB203x133x30
C4	SHS150x150x10	B3	UC254x254x107
C5	RHS400x200x12.5	B5	UC152x152x23
C6	RHS300x200x12.5	B6	UC203x203x46
		B7	UB254x146x43
		B8	PFC150x75x18
		B9	UB203x133x25
		B10	UC305x305x198

Proposed Floors	
Ref	Description
1	200thk RC slab
2	200x50wd C24 joists at 400c.c. 22mm OSB board screwed to top face of joists
3	30thk steel mesh grating rated for 5kN/m2 for max span 1500mm
4	130thk profiled NWC slab on TATA Comflor 60 0.9mm gauge deck with A142 mesh top and 1no. H16 bar per trough

Legend	
	Proposed RC structure
	Proposed Steel Framing
	Red dimension TBC by architect
	PS1 - 430lg x 215wd x 150dp MC padstone
	Moment connection
	Crank

P3	03.05.24	HS	DP	Revised Stage 2 Issue
P2	26.04.24	HS	DP	Revised Stage 2 Issue
P1	09.12.21	MC	GW	Stage 2 Issue
Rev	Date	By	Eng	Amendment

HEYNE TILLET STEEL STRUCTURAL & CIVIL ENGINEERS
<http://hts.uk.com/>

Job Name
Southampton Row, 31,
 Holborn, London
 WC1B 5HA
 Drawing Title
Proposed
Second Floor Plan

Purpose of Issue Preliminary Scale at A1 1 : 100


Drg No 2459-HTS-00-02-DR-S-2120

HTS Job No Suitability S1 Rev **P3**



The existing structural information shown on these drawings is based on visual inspection of the building, limited opening up works and relevant archive information. All details of the existing construction are subject to confirmation by the Contractor during the works on site. No materials are to be ordered until the relevant details and conditions are confirmed by the Contractor on site. Should the contractor discover any discrepancies between the assumed existing structure and what is found on site they should notify the engineer immediately, and await further instruction

1. This drawing is to be read in conjunction with all relevant architects, engineers and specialists drawings and specifications.
2. Do not scale from this drawing in either paper or digital form. Use written dimensions only. To check drawing has been printed to the intended scale the above bar should be 100mm.
3. Any setting out dimensions shown in red are to be confirmed by the architect. All dimensions are to be checked by the contractor against site dimensions prior to fabrication /commencement of work on site. Beams and columns are to be centred on grid unless noted otherwise. Setting out of steelwork is shown to the centre of symmetric sections and to the back face of PFCs and RSAs.
4. Investigations required as per HTS sketches SK002 and SK006 to determine extent of load bearing structure. Proposed works shown on these drawings are therefore indicative only and subject to strip out works and investigations
5. Access not available to visually inspect and investigation ground and basement areas due to existing tenants



Proposed Steel Cols **Proposed Steel Beams**

Ref	Type	Ref	Type
C2	SHS100x100x10	B1	UC203x203x71
C3	UC254x254x107	B2	UB203x133x30
C4	SHS150x150x10	B3	UC254x254x107
C5	RHS400x200x12.5	B5	UC152x152x23
C6	RHS300x200x12.5	B6	UC203x203x46
		B7	UB254x146x43
		B8	PFC150x75x18
		B9	UB203x133x25
		B10	UC305x305x198

Proposed Floors

Ref	Description
1	200thk RC slab
2	200x50wd C24 joists at 400c.c. 22mm OSB board screwed to top face of joists
3	30thk steel mesh grating rated for 5kN/m2 for max span 1500mm
4	130thk profiled NWC slab on TATA Comflor 60 0.9mm gauge deck with A142 mesh top and 1no. H16 bar per trough

Legend

	Proposed RC structure
	Proposed Steel Framing
	Red dimension TBC by architect
	PS1 - 430lg x 215wd x 150dp MC padstone
	Moment connection
	Crank

P3	03.05.24	HS	DP	Revised Stage 2 Issue
P2	26.04.24	HS	DP	Revised Stage 2 Issue
P1	09.12.21	MC	GW	Stage 2 Issue
Rev	Date	By	Eng	Amendment

HEYNE TILLET STEEL **STRUCTURAL & CIVIL ENGINEERS**
<http://hts.uk.com/>

Job Name
Southampton Row, 31,
 Holborn, London
 WC1B 5HA
 Drawing Title
Proposed
Third Floor Plan

Purpose of Issue Preliminary Scale at A1 1 : 100


Drg No **2459-HTS-00-03-DR-S-2130**

HTS Job No Suitability S1 Rev **P3**



The existing structural information shown on these drawings is based on visual inspection of the building, limited opening up works and relevant archive information. All details of the existing construction are subject to confirmation by the Contractor during the works on site. No materials are to be ordered until the relevant details and conditions are confirmed by the Contractor on site. Should the contractor discover any discrepancies between the assumed existing structure and what is found on site they should notify the engineer immediately, and await further instruction

1. This drawing is to be read in conjunction with all relevant architects, engineers and specialists drawings and specifications.
2. Do not scale from this drawing in either paper or digital form. Use written dimensions only. To check drawing has been printed to the intended scale the above bar should be 100mm.
3. Any setting out dimensions shown in red are to be confirmed by the architect. All dimensions are to be checked by the contractor against site dimensions prior to fabrication /commencement of work on site. Beams and columns are to be centred on grid unless noted otherwise. Setting out of steelwork is shown to the centre of symmetric sections and to the back face of PFCs and RSAs.
4. Investigations required as per HTS sketches SK002 and SK006 to determine extent of load bearing structure. Proposed works shown on these drawings are therefore indicative only and subject to strip out works and investigations
5. Access not available to visually inspect and investigation ground and basement areas due to existing tenants



Proposed Steel Cols		Proposed Steel Beams	
Ref	Type	Ref	Type
C2	SHS100x100x10	B1	UC203x203x71
C3	UC254x254x107	B2	UB203x133x30
C4	SHS150x150x10	B3	UC254x254x107
C5	RHS400x200x12.5	B5	UC152x152x23
C6	RHS300x200x12.5	B6	UC203x203x46
		B7	UB254x146x43
		B8	PFC150x75x18
		B9	UB203x133x25
		B10	UC305x305x198

Proposed Floors	
Ref	Description
1	200thk RC slab
2	200x50wd C24 joists at 400c.c. 22mm OSB board screwed to top face of joists
3	30thk steel mesh grating rated for 5kN/m2 for max span 1500mm
4	130thk profiled NWC slab on TATA Comflor 60 0.9mm gauge deck with A142 mesh top and 1no. H16 bar per trough

Legend	
	Proposed RC structure
	Proposed Steel Framing
	Red dimension TBC by architect
	PS1 - 430lg x 215wd x 150dp MC padstone
	Moment connection
	Crank

Rev	Date	By	Eng	Amendment
P3	03.05.24	HS	DP	Revised Stage 2 Issue
P2	26.04.24	HS	DP	Revised Stage 2 Issue
P1	09.12.21	MC	GW	Stage 2 Issue

HEYNE TILLET STEEL STRUCTURAL & CIVIL ENGINEERS
<http://hts.uk.com/>

Job Name
Southampton Row, 31,
 Holborn, London
 WC1B 5HA
 Drawing Title
Proposed Fourth Floor Plan

Purpose of Issue Preliminary Scale at A1 1 : 100


Drg No **2459-HTS-00-04-DR-S-2140**

HTS Job No Suitability S1 Rev **P3**



The existing structural information shown on these drawings is based on visual inspection of the building, limited opening up works and relevant archive information. All details of the existing construction are subject to confirmation by the Contractor during the works on site. No materials are to be ordered until the relevant details and conditions are confirmed by the Contractor on site. Should the contractor discover any discrepancies between the assumed existing structure and what is found on site they should notify the engineer immediately, and await further instruction

- This drawing is to be read in conjunction with all relevant architects, engineers and specialists drawings and specifications.
- Do not scale from this drawing in either paper or digital form. Use written dimensions only. To check drawing has been printed to the intended scale the above bar should be 100mm.
- Any setting out dimensions shown in red are to be confirmed by the architect. All dimensions are to be checked by the contractor against site dimensions prior to fabrication /commencement of work on site. Beams and columns are to be centred on grid unless noted otherwise. Setting out of steelwork is shown to the centre of symmetric sections and to the back face of PFCs and RSAs.
- Investigations required as per HTS sketches SK002 and SK006 to determine extent of load bearing structure. Proposed works shown on these drawings are therefore indicative only and subject to strip out works and investigations
- Access not available to visually inspect and investigation ground and basement areas due to existing tenants



Proposed Steel Cols		Proposed Steel Beams	
Ref	Type	Ref	Type
C2	SHS100x100x10	B1	UC203x203x71
C3	UC254x254x107	B2	UB203x133x30
C4	SHS150x150x10	B3	UC254x254x107
C5	RHS400x200x12.5	B5	UC152x152x23
C6	RHS300x200x12.5	B6	UC203x203x46
		B7	UB254x146x43
		B8	PFC150x75x18
		B9	UB203x133x25
		B10	UC305x305x198

Proposed Floors	
Ref	Description
1	200thk RC slab
2	200x50wd C24 joists at 400c.c. 22mm OSB board screwed to top face of joists
3	30thk steel mesh grating rated for 5kN/m2 for max span 1500mm
4	130thk profiled NWC slab on TATA Comflor 60 0.9mm gauge deck with A142 mesh top and 1no. H16 bar per trough

Legend	
	Proposed RC structure
	Proposed Steel Framing
	Red dimension TBC by architect
	PS1 - 430lg x 215wd x 150dp MC padstone
	Moment connection
	Crank

Ref	Date	By	Eng	Amendment
P3	03.05.24	HS	DP	Revised Stage 2 Issue
P2	26.04.24	HS	DP	Revised Stage 2 Issue
P1	09.12.21	MC	GW	Stage 2 Issue

HEYNE TILLET STEEL STRUCTURAL & CIVIL ENGINEERS
<http://hts.uk.com/>

Job Name
Southampton Row, 31,
 Holborn, London
 WC1B 5HA
 Drawing Title
Proposed
Fifth Floor Plan

Purpose of Issue Preliminary Scale at A1 1 : 100

Drg No **2459-HTS-00-05-DR-S-2150**

HTS Job No Suitability S1 Rev **P3**




The existing structural information shown on these drawings is based on visual inspection of the building, limited opening up works and relevant archive information. All details of the existing construction are subject to confirmation by the Contractor during the works on site. No materials are to be ordered until the relevant details and conditions are confirmed by the Contractor on site. Should the contractor discover any discrepancies between the assumed existing structure and what is found on site they should notify the engineer immediately, and await further instruction

- This drawing is to be read in conjunction with all relevant architects, engineers and specialists drawings and specifications.
- Do not scale from this drawing in either paper or digital form. Use written dimensions only. To check drawing has been printed to the intended scale the above bar should be 100mm.
- Any setting out dimensions shown in red are to be confirmed by the architect. All dimensions are to be checked by the contractor against site dimensions prior to fabrication /commencement of work on site. Beams and columns are to be centred on grid unless noted otherwise. Setting out of steelwork is shown to the centre of symmetric sections and to the back face of PFCs and RSAs.
- Investigations required as per HTS sketches SK002 and SK006 to determine extent of load bearing structure. Proposed works shown on these drawings are therefore indicative only and subject to strip out works and investigations
- Access not available to visually inspect and investigation ground and basement areas due to existing tenants

Proposed Steel Cols		Proposed Steel Beams	
Ref	Type	Ref	Type
C2	SHS100x100x10	B1	UC203x203x71
C3	UC254x254x107	B2	UB203x133x30
C4	SHS150x150x10	B3	UC254x254x107
C5	RHS400x200x12.5	B5	UC152x152x23
C6	RHS300x200x12.5	B6	UC203x203x46
		B7	UB254x146x43
		B8	PFC150x75x18
		B9	UB203x133x25
		B10	UC305x305x198

Proposed Floors	
Ref	Description
1	200thk RC slab
2	200x50wd C24 joists at 400c.c. 22mm OSB board screwed to top face of joists
3	30thk steel mesh grating rated for 5kN/m2 for max span 1500mm
4	130thk profiled NWC slab on TATA Comflor 60 0.9mm gauge deck with A142 mesh top and 1no. H16 bar per trough

Legend	
	Proposed RC structure
	Proposed Steel Framing
	Red dimension TBC by architect
	PS1 - 430lg x 215wd x 150dp MC padstone
	Moment connection
	Crank



Rev	Date	By	Eng	Amendment
P3	03.05.24	HS	DP	Revised Stage 2 Issue
P2	26.04.24	HS	DP	Revised Stage 2 Issue
P1	09.12.21	MC	GW	Stage 2 Issue

HEYNE TILLET STEEL STRUCTURAL & CIVIL ENGINEERS
<http://hts.uk.com/>

Job Name
Southampton Row, 31,
 Holborn, London
 WC1B 5HA
 Drawing Title
Proposed
Roof Floor Plan

Purpose of Issue Preliminary Scale at A1 1:100

Drg No **2459-HTS-00-06-DR-S-2160**

HTS Job No Suitability S1 Rev **P3**



The existing structural information shown on these drawings is based on visual inspection of the building, limited opening up works and relevant archive information. All details of the existing construction are subject to confirmation by the Contractor during the works on site. No materials are to be ordered until the relevant details and conditions are confirmed by the Contractor on site. Should the contractor discover any discrepancies between the assumed existing structure and what is found on site they should notify the engineer immediately, and await further instruction

1. This drawing is to be read in conjunction with all relevant architects, engineers and specialists drawings and specifications.
2. Do not scale from this drawing in either paper or digital form. Use written dimensions only. To check drawing has been printed to the intended scale the above bar should be 100mm.
3. Any setting out dimensions shown in red are to be confirmed by the architect. All dimensions are to be checked by the contractor against site dimensions prior to fabrication /commencement of work on site. Beams and columns are to be centred on grid unless noted otherwise. Setting out of steelwork is shown to the centre of symmetric sections and to the back face of PFCs and RSAs.
4. Investigations required as per HTS sketches SK002 and SK006 to determine extent of load bearing structure. Proposed works shown on these drawings are therefore indicative only and subject to strip out works and investigations
5. Access not available to visually inspect and investigation ground and basement areas due to existing tenants

Proposed Steel Cols		Proposed Steel Beams	
Ref	Type	Ref	Type
C2	SHS100x100x10	B1	UC203x203x71
C3	UC254x254x107	B2	UB203x133x30
C4	SHS150x150x10	B3	UC254x254x107
C5	RHS400x200x12.5	B5	UC152x152x23
C6	RHS300x200x12.5	B6	UC203x203x46
		B7	UB254x146x43
		B8	PFC150x75x18
		B9	UB203x133x25
		B10	UC305x305x198

Proposed Floors	
Ref	Description
1	200thk RC slab
2	200x50wd C24 joists at 400c.c. 22mm OSB board screwed to top face of joists
3	30thk steel mesh grating rated for 5kN/m2 for max span 1500mm
4	130thk profiled NWC slab on TATA Comflor 60 0.9mm gauge deck with A142 mesh top and 1no. H16 bar per trough

Legend	
	Proposed RC structure
	Proposed Steel Framing
	Red dimension TBC by architect
	PS1 - 430lg x 215wd x 150dp MC padstone
	Moment connection
	Crank



Rev	Date	By	Eng	Amendment
P2	03.05.24	HS	DP	Revised Stage 2 Issue
P1	26.04.24	HS	DP	Revised Stage 2 Issue

HEYNE TILLET STEEL STRUCTURAL & CIVIL ENGINEERS
<http://hts.uk.com/>

Job Name
Southampton Row, 31,
 Holborn, London
 WC1B 5HA
 Drawing Title
Proposed
Roof Plant Deck

Purpose of Issue Preliminary Scale at A1 1 : 100

Drg No **2459-HTS-00-06-DR-S-2165**

HTS Job No Suitability Rev **P2**

New roof plant deck to be constructed on top of existing roof. To be supported on posts connected into the structure beneath. New structure to be designed once framing if roof structure is confirmed. Extent of plant support currently unknown

New steel moment frames from first floor to fourth floor to resupport existing slabs and provide stability

New steel moment frames from first floor to fourth floor to resupport existing slabs and provide stability

New stairs from basement to ground assumed to be steel. To architects specification

1. This drawing is to be read in conjunction with all relevant architects, engineers and specialists drawings and specifications.
2. Do not scale from this drawing in either paper or digital form. Use written dimensions only. To check drawing has been printed to the intended scale the above bar should be 100mm.
3. Any setting out dimensions shown in red are to be confirmed by the architect. All dimensions are to be checked by the contractor against site dimensions prior to fabrication /commencement of work on site. Beams and columns are to be centred on grid unless noted otherwise. Setting out of steelwork is shown to the centre of symmetric sections and to the back face of PFCs and RSAs.
4. Investigations required as per HTS sketches SK002 and SK006 to determine extent of load bearing structure. Proposed works shown on these drawings are therefore indicative only and subject to strip out works and investigations
5. Access not available to visually inspect and investigation ground and basement areas due to existing tenants

Proposed Steel Cols		Proposed Steel Beams	
Ref	Type	Ref	Type
C2	SHS100x100x10	B1	UC203x203x71
C3	UC254x254x107	B2	UB203x133x30
C4	SHS150x150x10	B3	UC254x254x107
C5	RHS400x200x12.5	B5	UC152x152x23
C6	RHS300x200x12.5	B6	UC203x203x46
		B7	UB254x146x43
		B8	PFC150x75x18
		B9	UB203x133x25
		B10	UC305x305x198

Proposed Floors	
Ref	Description
1	200thk RC slab
2	200x50wd C24 joists at 400c.c. 22mm OSB board screwed to top face of joists
3	30thk steel mesh grating rated for 5kN/m2 for max span 1500mm
4	130thk profiled NWC slab on TATA Comflor 60 0.9mm gauge deck with A142 mesh top and 1no. H16 bar per trough

Legend	
	Proposed RC structure
	Proposed Steel Framing
	Red dimension TBC by architect
	PS1 - 430lg x 215wd x 150dp MC padstone
	Moment connection
	C Crank

The existing structural information shown on these drawings is based on visual inspection of the building, limited opening up works and relevant archive information. All details of the existing construction are subject to confirmation by the Contractor during the works on site. No materials are to be ordered until the relevant details and conditions are confirmed by the Contractor on site. Should the contractor discover any discrepancies between the assumed existing structure and what is found on site they should notify the engineer immediately, and await further instruction

Rev	Date	By	Eng	Amendment
P3	03.05.24	HS	DP	Revised Stage 2 Issue
P2	26.04.24	HS	DP	Revised Stage 2 Issue
P1	09.12.21	MC	GW	Stage 2 Issue

HEYNE TILLET STEEL STRUCTURAL & CIVIL ENGINEERS
<http://hts.uk.com/>

Job Name
Southampton Row, 31,
 Holborn, London
 WC1B 5HA

Drawing Title
Proposed Section A-A

Purpose of Issue Preliminary Scale at A1

Drg No **2459-HTS-00-XX-DR-S-2200**

HTS Job No Suitability S1 Rev **P3**

Appendix B


Structural Investigations Scope

Notation

1. Concrete cover to be removed from column/beam to determine if in-situ RC or concrete encased steelwork. If in-situ RC, vertical bars (incl. shear links) are to be exposed. If encased steelwork, beam to be exposed to allow for breadth/width to be measured. Allow for minimum 500x500 opening.
2. Concrete cover to be removed from column/beam to determine if in-situ RC or concrete encased steelwork. If in-situ RC, vertical bars (incl. shear links) are to be exposed. If encased steelwork, beam to be exposed to allow for breadth/width to be measured. Allow for minimum 500x500 opening. End bearing of beam to be exposed.
3. Drill through masonry to determine thickness and if embedded steelwork is present.
4. Screed to be locally removed using non-percussive methods. Care to be taken not to damage filler joist slabs


Notes

- Investigations are to be carried out on the structure above, ie this level looking up
- Prior approval may be required where existing tenants are in place
- Some locations shown have flexibility and may be moved to suit obstructions. TBC with HTS.
- All structural investigation locations to be confirmed with HTS on site prior to opening-up works.
- HTS to inspect opening-up works prior to finishes being reinstated (if requested from the client).
- Fire proofing to be reinstated as per existing condition.
- No existing rebar/steelwork is to be cut on site during investigations
- Works to be completed in accordance with Historic England requirements
- Phase 2 investigations may be required subject to findings on site




Ceiling finishes to be exposed to determine roof structure. Minimum two joists to be exposed. Allow for 500mm x 500mm opening

1



Structure between fifth floor and roof currently unknown and to be confirmed once access/survey available.

To be completed as part of stage 2 works. Remaining investigations to be carried out during stage 3



FIFTH FLOOR PLAN
(Only common areas)

Job	31 Southampton Place	Date	08/02/2024
Title	Site Investigations	Eng.	GT/DP
Job No.	2459	Sheet	SK06.1
		Rev.	P2



Rev.	Description	Date

ASES
Advanced Site Engineering Surveys
Registered at 1 Park Road, Hampton Wick, Kingston Upon Thames, Surrey, KT1 4AS
Tel: 0203 7000 654
E: contact@aseskd.com
Web: www.aseskd.com

Client: EDMOND DE ROTHSCHILD REIM (UK) LTD
Project: HOLBORN LINKS, 31 SOUTHAMPTON ROW - PROJECT 7
Title: FLOOR PLANS, FIFTH

Drawn	VS	Surveyed	AP	Checked	JP	Date	23/06/2022
Project No.	A1177	Scale @ A1	1:100	Reason			
Drawing No.	A1177-F5						


CHAS

Notation

- Concrete cover to be removed from column/beam to determine if in-situ RC or concrete encased steelwork. If in-situ RC, vertical bars (incl. shear links) are to be exposed. If encased steelwork, beam to be exposed to allow for breadth/width to be measured. Allow for minimum 500x500 opening.
- Concrete cover to be removed from column/beam to determine if in-situ RC or concrete encased steelwork. If in-situ RC, vertical bars (incl. shear links) are to be exposed. If encased steelwork, beam to be exposed to allow for breadth/width to be measured. Allow for minimum 500x500 opening. End bearing of beam to be exposed.
- Drill through masonry to determine thickness and if embedded steelwork is present.
- Screed to be locally removed using non-percussive methods. Care to be taken not to damage filler joist slabs

Notes


- Investigations are to be carried out on the structure above, ie this level looking up
- Prior approval may be required where existing tenants are in place
- Some locations shown have flexibility and may be moved to suit obstructions. TBC with HTS.
- All structural investigation locations to be confirmed with HTS on site prior to opening-up works.
- HTS to inspect opening-up works prior to finishes being reinstated (if requested from the client).
- Fire proofing to be reinstated as per existing condition.
- No existing rebar/steelwork is to be cut on site during investigations
- Works to be completed in accordance with Historic England requirements
- Phase 2 investigations may be required subject to findings on site



To be completed as part of stage 2 works.
 Remaining investigations to be carried out during stage 3

FOURTH FLOOR PLAN

Job	31 Southampton Place	Date	08/02/2024
Title	Site Investigations	Eng.	GT/DP
Job No.	2459	Sheet	SK06.2
		Rev.	P2



Rev.	Description	Date

ASES
 Advanced Site Engineering Surveys
 Registered at 1 Park Road, Hampton
 Wick, Kingston Upon Thames,
 Surrey, KT1 4AS
 Tel: 0203 7000 654
 E: contact@aseskd.com
 Web: www.aseskd.com

Client: EDMOND DE ROTHSCHILD REIM (UK) LTD
 Project: HOLBORN LINKS, 31 SOUTHAMPTON ROW - PROJECT 7
 Title: FLOOR PLANS, FOURTH


Drawn	VS	Surveyed	AP	Checked	JP	Date	23/06/2022
Project No.	A1177	Scale @ A1	1:100	Reason			
Drawing No.	A1177-F4						

Notation

1. Concrete cover to be removed from column/beam to determine if in-situ RC or concrete encased steelwork. If in-situ RC, vertical bars (incl. shear links) are to be exposed. If encased steelwork, beam to be exposed to allow for breadth/width to be measured. Allow for minimum 500x500 opening.
2. Concrete cover to be removed from column/beam to determine if in-situ RC or concrete encased steelwork. If in-situ RC, vertical bars (incl. shear links) are to be exposed. If encased steelwork, beam to be exposed to allow for breadth/width to be measured. Allow for minimum 500x500 opening. End bearing of beam to be exposed.
3. Drill through masonry to determine thickness and if embedded steelwork is present.
4. Screed to be locally removed using non-percussive methods. Care to be taken not to damage filler joist slabs

Notes

- Investigations are to be carried out on the structure above, ie this level looking up
- Prior approval may be required where existing tenants are in place
- Some locations shown have flexibility and may be moved to suit obstructions. TBC with HTS.
- All structural investigation locations to be confirmed with HTS on site prior to opening-up works.
- HTS to inspect opening-up works prior to finishes being reinstated (if requested from the client).
- Fire proofing to be reinstated as per existing condition.
- No existing rebar/steelwork is to be cut on site during investigations
- Works to be completed in accordance with Historic England requirements
- Phase 2 investigations may be required subject to findings on site



To be completed as part of stage 2 works.
 Remaining investigations to be carried out during stage 3

THIRD FLOOR PLAN

Job	31 Southampton Place	Date	08/02/2024
Title	Site Investigations	Eng.	GT/DP
Job No.	2459	Sheet	SK06.3
		Rev.	P2



Rev.	Description	Date

<p>Advanced Site Engineering Surveys</p>	
Registered at 1 Park Road, Hampton Wick, Kingston Upon Thames, Surrey, KT1 4AS Tel: 0203 7000 654 E: contact@aseskd.com Web: www.aseskd.com	
Client:	EDMOND DE ROTHSCHILD REIM (UK) LTD
Project:	HOLBORN LINKS, 31 SOUTHAMPTON ROW - PROJECT 7
Title:	FLOOR PLANS, THIRD


Drawn	VS	Surveyed	AP	Checked	JP	Date	23/06/2022
Project No.	A1177	Scale @ A1	1:100	Reason			
Drawing No.	A1177-F3						

Notation


1. Concrete cover to be removed from column/beam to determine if in-situ RC or concrete encased steelwork. If in-situ RC, vertical bars (incl. shear links) are to be exposed. If encased steelwork, beam to be exposed to allow for breadth/width to be measured. Allow for minimum 500x500 opening.
2. Concrete cover to be removed from column/beam to determine if in-situ RC or concrete encased steelwork. If in-situ RC, vertical bars (incl. shear links) are to be exposed. If encased steelwork, beam to be exposed to allow for breadth/width to be measured. Allow for minimum 500x500 opening. End bearing of beam to be exposed.
3. Drill through masonry to determine thickness and if embedded steelwork is present.
4. Screed to be locally removed using non-percussive methods. Care to be taken not to damage filler joist slabs

Notes

- Investigations are to be carried out on the structure above, ie this level looking up
- Prior approval may be required where existing tenants are in place
- Some locations shown have flexibility and may be moved to suit obstructions. TBC with HTS.
- All structural investigation locations to be confirmed with HTS on site prior to opening-up works.
- HTS to inspect opening-up works prior to finishes being reinstated (if requested from the client).
- Fire proofing to be reinstated as per existing condition.
- No existing rebar/steelwork is to be cut on site during investigations
- Works to be completed in accordance with Historic England requirements
- Phase 2 investigations may be required subject to findings on site



To be completed as part of stage 2 works.
 Remaining investigations to be carried out during stage 3



SECOND FLOOR PLAN

Job	31 Southampton Place	Date	08/02/2024
Title	Site Investigations	Eng.	GT/DP
Job No.	2459	Sheet	SK06.4
		Rev.	P2



Rev.	Description	Date

ASES
 Advanced Site Engineering Surveys
 Registered at 1 Park Road, Hampton Wick, Kingston Upon Thames, Surrey, KT1 4AS
 Tel: 0203 7000 654
 E: contact@aseskd.com
 Web: www.aseskd.com

Client: EDMOND DE ROTHSCHILD REIM (UK) LTD
 Project: HOLBORN LINKS, 31 SOUTHAMPTON ROW - PROJECT 7
 Title: FLOOR PLANS, SECOND


Drawn	VS	Surveyed	AP	Checked	JP	Date	23/06/2022
Project No.	A1177	Scale	@ A1	1:100	Reason		
Drawing No.	A1177-F2						

Notation

1. Concrete cover to be removed from column/beam to determine if in-situ RC or concrete encased steelwork. If in-situ RC, vertical bars (incl. shear links) are to be exposed. If encased steelwork, beam to be exposed to allow for breadth/width to be measured. Allow for minimum 500x500 opening.
2. Concrete cover to be removed from column/beam to determine if in-situ RC or concrete encased steelwork. If in-situ RC, vertical bars (incl. shear links) are to be exposed. If encased steelwork, beam to be exposed to allow for breadth/width to be measured. Allow for minimum 500x500 opening. End bearing of beam to be exposed.
3. Drill through masonry to determine thickness and if embedded steelwork is present.
4. Screed to be locally removed using non-percussive methods. Care to be taken not to damage filler joist slabs

Notes

- Investigations are to be carried out on the structure above, ie this level looking up
- Prior approval may be required where existing tenants are in place
- Some locations shown have flexibility and may be moved to suit obstructions. TBC with HTS.
- All structural investigation locations to be confirmed with HTS on site prior to opening-up works.
- HTS to inspect opening-up works prior to finishes being reinstated (if requested from the client).
- Fire proofing to be reinstated as per existing condition.
- No existing rebar/steelwork is to be cut on site during investigations
- Works to be completed in accordance with Historic England requirements
- Phase 2 investigations may be required subject to findings on site



FIRST FLOOR PLAN

To be completed as part of stage 2 works.
 Remaining investigations to be carried out during stage 3

Job	31 Southampton Place	Date	08/02/2024
Title	Site Investigations	Eng.	GT/DP
Job No.	2459	Sheet	SK06.5
		Rev.	P2



Rev.	Description	Date

ASES
 Advanced Site Engineering Surveys
 Registered at 1 Park Road, Hampton Wick, Kingston Upon Thames, Surrey, KT1 4AS
 Tel: 0203 7000 654
 E: contact@aseskd.com
 Web: www.aseskd.com

Client: EDMOND DE ROTHSCHILD REIM (UK) LTD
 Project: HOLBORN LINKS, 31 SOUTHAMPTON ROW - PROJECT 7
 Title: FLOOR PLANS, FIRST

Drawn	VS	Surveyed	AP	Checked	JP	Date	23/06/2022
Project No.	A1177	Scale	@ A1	1:100	Reason		
Drawing No.	A1177-F1						


Key

- 1 - Remove finishes and expose steel beam within vaults along full length and bearing. Engineer to inspect investigation to assess condition of beam. Contractor to allow for reinstating any brickwork following inspection.
- 2 - Remove existing ceiling and any finishes at head of wall along a length of 1m and width of 500mm to expose underside of slab and connection into existing wall. If beam found allow for breaking out at beam bearing end to view connection.
- 3 - Remove existing ceiling and any finishes over area of 2m x 2m to expose underside of slab and supporting beams. Allow for drilling through slab to determine depth.
- 4 - Remove existing ceiling and any finishes at head of column over area of 1m x 1m to expose underside of slab and any supporting beams that connect into columns.
- 5 - Remove ceiling and finishes from around RC beam along length of 500mm at end bearing to expose connection into masonry wall.

Structural Investigation Notes

- All investigations to be carried out at high level on floor which they are marked on
- Contractor to allow for reinstating all finishes including any fire protection removed in order to measure elements
- Engineer to inspect all investigations prior to reinstating any finishes

Colour Key

 Remove finishes locally to expose structure beneath - no breaking out required




Key


- 1 - Remove finishes and expose steel beam within vaults along full length and bearing. Engineer to inspect investigation to assess condition of beam. Contractor to allow for reinstating any brickwork following inspection.
- 2 - Remove existing ceiling and any finishes at head of wall along a length of 1m and width of 500mm to expose underside of slab and connection into existing wall. If beam found allow for breaking out at beam bearing end to view connection.
- 3 - Remove existing ceiling and any finishes over area of 2m x 2m to expose underside of slab and supporting beams. Allow for drilling through slab to determine depth.
- 4 - Remove existing ceiling and any finishes at head of column over area of 1m x 1m to expose underside of slab and any supporting beams that connect into columns.
- 5 - Remove ceiling and finishes from around RC beam along length of 500mm at end bearing to expose connection into masonry wall.

Structural Investigation Notes

- All investigations to be carried out at high level on floor which they are marked on
- Contractor to allow for reinstating all finishes including any fire protection removed in order to measure elements
- Engineer to inspect all investigations prior to reinstating any finishes

Colour Key


 Remove finishes locally to expose structure beneath - no breaking out required



Appendix C

Archive Drawings

SOUTHAMPTON ROW & VERNON PLACE



PLAN OF BASEMENT FLOOR




Robert J. Worley
Architect
Albany Chambers
170 Strand W.C.

Approved in accordance with
building proposal dated the 20th day of
February 1906

Bedford Office 1908

SOUTHAMPTON ROW & VERNON PLACE



SOUTHAMPTON ROW
PLAN OF GROUND FLOOR




Robert J. Worley
 Architect
 Alwyck Chambers
 170 Strand W.C.

Approved in accordance with
 building proposal dated the 20th day of
 February 1906

Bedford Office 1908

SOUTHAMPTON ROW & VERNON PLACE



PLAN OF FIRST FLOOR



Robert J. Worley
 Architect
 Aldwych Chambers
 170 Strand W.C.

Approved in accordance with
 building proposal dated the 20th day of
 February 1906

Bedford Office 1908