Window Schedule - Existing

Element ID	FAN-001	SKYL-001	SKYL-002	W-001	W-002	W-003	W-004
Floor	Ground Floor (20.40)	Roof	Roof	Basement (18.00)	Ground Floor (20.40)	Ground Floor (20.40)	Ground Floor (20.40)
W x H Size	2,660×700	---	---	800×660	1,160×950	795×550	795×550
Window sill height	2,382	---	---	-1,265	2,220	2,480	2,480
Window head height	3,081	---	---	-605	3,170	3,030	3,030
Renovation Status	To Be Demolished	To Be Demolished	To Be Demolished	Existing	Existing	Existing	Existing
3D Front View	2,660 / 700	REPLACE WITH NEW DOUBLE GLAZED HERITAGE ROOF LIGHT TO MATCH. SEE PROPOSED WINDOW SCHEDULE — 1,550 / 2,300	REPLACE WITH NEW DOUBLE GLAZED HERITAGE ROOF LIGHT TO MATCH. SEE PROPOSED WINDOW SCHEDULE — 1,550 / 2,300	800 / 660 REPLACE WITH NEW DOUBLE GLAZED SASH TO MATCH.	1,160 / 950 REPLACE WITH NEW DOUBLE GLAZED SASH TO MATCH.	795 / 550 REPLACE WITH NEW DOUBLE GLAZED SASH TO MATCH.	795 / 550 REPLACE WITH NEW DOUBLE GLAZED SASH TO MATCH.
Quantity	1	1	1	1	1	1	1

W-005	W-006	W-007	W-008	W-009	W-010	W-011	W-012	W-013
Ground Floor (20.40)	Ground Floor (20.40)	Ground Floor (20.40)	Ground Floor (20.40)	Ground Floor (20.40)	First Floor (23.85)	First Floor (23.85)	First Floor (23.85)	First Floor (23.85)
795×550	880×1,350	900×1,350	1,020×1,169	900×825	1,280×1,600	1,015×1,600	926×1,600	770×1,180
2,480	1,270	1,270	1,281	1,565	780	780	780	835
3,030	2,620	2,620	2,450	2,390	2,380	2,380	2,380	2,015
Existing	Existing	To Be Demolished	To Be Demolished	To Be Demolished	Existing	Existing	Existing	To Be Demolished
795 / 550 REPLACE WITH NEW DOUBLE GLAZED SASH TO MATCH.	880 / 1,350 REPLACE WITH NEW DOUBLE GLAZED SASH TO MATCH.	900 / 1,350	1,020 / 1,169	900 / 825	1,280 / 1,600 REPLACE WITH NEW DOUBLE GLAZED SASH TO MATCH.	1,015 / 1,600 REPLACE WITH NEW DOUBLE GLAZED SASH TO MATCH.	926 / 1,600 REPLACE WITH NEW DOUBLE GLAZED SASH TO MATCH.	770 / 1,180
1	1	1	1	1	1	1	1	1