

# **16 Lyndhurst Gardens – Planning Application Queries**

## **East Elevation – Soil and Rainwater Pipe Coordination**

### **STAGE 1 – REMOVAL OF EXISTING HOPPER / DOWNPIPE**



## 16 Lyndhurst Gardens – Planning Application Queries

### East Elevation – Soil and Rainwater Pipe Coordination

#### STAGE 2 – CONNECT TO ROOF DOWNPIPE, RUN IN REDUCED 3"

New soil vent pipe indicated in red – we will offset the rainwater pipe using 115mm offset and run this into new hopper – and complete the rainwater vertical run in 3 inch – currently 4" on top floor so reducing to 3" will reduce the impact currently on the elevation

