



Sign to be illuminated by Chiplite LEDs mounted to internal returns of sign carcass, 12v feed into sign through solid panel into building. 12v cable connected to transformer in access hatch which is to be provided by the main contractor within 1000mm of each sign position and to have fused switched spur on dedicated sign circuit from MDB. Electrical contractor to run all mains cabling, installed fused switched spurs and make final connections.

