

St Christopher's School schedule of works subject of s73 application

1. New ramp and steps arrangement in link area.
 - Ramp amended to comply with Part M of Building Regulations.
 - Remove existing steps to accommodate new width of ramp.
 - New raised planter to replace steps.
(Approved by Building Control).
 - Re-fit existing fabric awning and canopy structure.

2. New PPC aluminium frame glazed canopy in place of pyramidal roof.

3. New screen gates to bins / deliveries entrance area.

4. New timber fence enclosing playground.

5. South Elevation changes

6.
 - PPC aluminium glazed double doors on west side of extension.
 - Omit double doors.
 - Doors on both sides of external WCs. Single door to external WC, timber clad to match elevation.

7. Roof (extension)
 - New northlight rooflights over new bays. Omit and replace with flat rooflights.
 - New circular rooflights over entrance and WCs. - Omit rooflights over entrance.
 - Flat rooflight in external WCs.

July 2024