





Date Rev By Issue Notes 21.06.24 P2 YF Stage 3 Issue

19.07.24 P3 CP Planning Issue

Glass within existing painted single glazed timber sash windows to be carefully removed and replaced with Histoglass Mono RT+ glass to improve thermal performance. Contractor to allow for rubbing down, filling any defects, making good and installing new glass with putty detail to match existing profiles and redecorating windows internally and externally with new paint to match existing finish.

NO DIMENSIONS ARE TO BE SCALED FROM THIS DRAWING. THE CONTRACTOR/MANUFACTURER IS RESPONSIBLE FOR CHECKING ALL DIMENSIONS AND QUERYING ANY DISCREPANCIES. THIS DRAWING IS THE PROPERTY OF BURWELL ARCHITECTS LTD. COPYRIGHT IS RESERVED BY THEM AND THE DRAWING IS ISSUED ON CONDITION THAT IT IS NOT COPIED, REPRODUCED, RETAINED OR DISCLOSED TO ANY UNAUTHORISED PERSON, EITHER WHOLLY OR IN PART, WITHOUT WRITTEN CONSENT.



Unit 0.01 California Building Deals Gateway London SE13 7SB 020 8305 6010

info@burwellarchitects.com www.burwellarchitects.com

UCL

Wilkins Building

Wilkins South Wing - West Elevation Proposed

980-G-1100-Elevations.vwx

CP 980 MM 1:100 @ A1

16/05/2024 980_G_1122

P3