



--- Duct work running high level
--- Tray work running high level
--- Fresh air supply ductwork high level

LIGHTING / CEILING KEY

- DL Down Light
- P Pendant Light
- Ceiling recessed light panel
- EXIT Emergency Exit Sign
- S Smoke Detector
- S/S Smoke Detector with Sounder
- PIR Passive Infrared Sensor

NOTES

- Drawings to be read together with Design Intent information and technical drawings
- All drawings shall be read in conjunction with the fire strategy
- All layouts are subject to compliance review by Building Control
- Drawings are based on survey data and review survey data for further details.
- Do not scale from this drawing. All dimensions are to be verified on site before proceeding with the work.
- Architect shall be notified in writing of any discrepancies.

WALL FINISHES KEY

WF-01A EXPOSED EXISTING WALL FINISHES (Brickwork) CLEAN GRIT BLASTING	WF-01B EXISTING BRICK WALL CLEAN BRICKWORK (STEAM / WATER)
WF-02 RENDER (Waterproofing)	WF-03B CEMENTITIOUS WALL COATING - RED (NEW TOILET WALLS)
WF-03A CEMENTITIOUS WALL COATING - GRAY (NEW TOILET WALLS)	WF-04B LAMINATE
WF-04A TIMBER VENEER	WF-05B PAINT FINISH - GRAY
WF-05A PAINT FINISH - WHITE	WF-07 New insulated walls to perimeter walls in annex. KOOETHERM K118 42.5mm
WF-06 NEW METAL FINISH	

FLOOR FINISHES KEY

FF-01
TIMBER FLOORING

FF-02
OPTION 1: VINYL FLOORING (SLIP RESISTANT)
OPTION 2: CERAMIC LARGE TILES (SLIP RESISTANT)

FF-03
TILE FLOORING

CEILING FINISHES KEY

CF-01 EXPOSED EXISTING CEILING FINISHES (Brickwork)	CF-06 Repainted existing metal work
CF-02 EXPOSED EXISTING CEILING FINISHES (Concrete)	
CF-03 EXPOSED EXISTING CEILING FINISHES (Structural Steel)	
CF-04 NEW PLASTERBOARD	
CF-05 EXISTING PLASTERBOARD REPAIRED & REPAINTED	

CFL : +2.8m

CFL : +2.2m (ceiling low, ceiling height to be maximized where possible)

3	Additional key for M&E services - indicated secondary glazing	MT	OG	09.08.2024
2	Issued for Planning	DF	OG	24.07.2024
1	Issued as Stage 3 Design	DF	OG	15.01.2024
DR	Issued for Review	DF	OG	11.12.2023
Rev	Description	By	Check	Date

01m2m5m

STUDIO GHAZAL

Contractor

QOB

QOB Interiors
3 Marshalsea Road
London
SE1 1EP

Client

RAILPEN

Project

Camden Works, The Rotunda
42-43 Gloucester Crescent, Camden Town, NW1 7PE

Drawing

Level 3 RCP

Scale	Date	Drawn	Approved
1:50 @ A1	09.08.2024	MT	OG
Drawing No.			Revision
CDW-SGH-PR-03-DR-A-160			03