



All work shall be completed in line with BS3998:2010 -Recommendations for Tree Work where appropriate  
 Artemis Tree Services Ltd will check all TPO and Conservation Area clearance if not already in place

## WORK ORDER

<b>Client:</b> Tom Critchley Nurture Landscapes Coursers Farm, Coursers Road, St Albans, Herts, AL4 0PD		<b>Site address:</b> Kings Cross Central, N1C	
<b>Our Ref:</b>	31094	<b>Date:</b>	4th July 2024
		<b>Purchase Order No:</b>	229298

### Details of Work Required/Recommended

Priority A works as per survey 27872 recommendations

Tree numbers - 19 Sorbus alternifolia - Remove as close to trees current ground level as possible, leaving the stump in the ground.

49 Sorbus aucuparia Asplenifolia - Remove as close to trees current ground level as possible, leaving the stump in the ground.

78 Prunus avium Plena - Remove dead branch at 2m to NE.

83 (0030) Quercus palustris - Remove dead branch at 3m to SE.

89 Sorbus aucuparia Asplenifolia - Remove as close to trees current ground level as possible, leaving the stump in the ground.

Priority B works as per survey 27872 recommendations

Tree numbers - 2 Platanus x hispanica - Crown lift to 2.5m from ground level, targeting secondary growth where possible.. Prune to give 0.5m clearance from lamp, targeting secondary growth where possible.

3 Platanus x hispanica - Thorough deadwood removal.

4 Platanus x hispanica - Crown lift to give 2.5m ground clearance, targeting secondary growth where possible. Thorough deadwood removal.

12 Quercus palustris - Crown lift to 2.5m from ground level, targeting secondary growth where possible. Thorough deadwood removal.

14 Prunus subhirtella Autumnalis - Prune N side of crown (footpath sides back by around 0.5m to give clearance to footpath.

15 Prunus subhirtella Autumnalis - Lift crown over footpath to give around 2m ground clearance.

16 Prunus subhirtella Autumnalis - Lift crown to give around 2m clearance over footpath.

37 Prunus subhirtella Autumnalis - Prune branches back to 0.5m behind rail.

38 Prunus subhirtella Autumnalis - Prune branches back to 0.5m behind rail.

39 Prunus subhirtella Autumnalis - Prune branches back to 0.5m behind rail.

44 Prunus subhirtella Autumnalis - Lift crown over footpath to give 2.5m ground clearance, targeting secondary growth where possible. Prune growth to N to give 1m clearance from lamp column, pruning to suitable growth points.

45 Prunus subhirtella Autumnalis - Lift crown to give 2.to ground clearance to W over bench/footpath, targeting secondary growth where possible. Prune to give 0.5m clearance from lamp column, pruning to suitable growth points.

46 Prunus subhirtella Autumnalis - Prune to give 0.5m clearance from building to E, pruning to suitable growth points. Lift crown over bike racks to W to give around 2.5m ground clearance, targeting secondary growth where possible.

47 Prunus subhirtella Autumnalis - Prune to clear lamp column by around 0.25m, pruning to suitable growth points.



**Artemis Tree Services Ltd**

West Hyde Nursery  
 Old Uxbridge Road  
 West Hyde  
 Rickmansworth  
 Herts WD3 9XY

**T:** 01895 821 623

**E:** office@artemistreeservices.com

**W:** www.artemistreeservices.com



All work shall be completed in line with BS3998:2010 -Recommendations for Tree Work where appropriate  
 Artemis Tree Services Ltd will check all TPO and Conservation Area clearance if not already in place

(Continued) Priority B works as per survey 27872 recommendations

- Tree numbers - 58 Prunus avium Plena - Lift crown over footpaths to give 2.5m ground clearance, targeting secondary growth where possible.  
 59 Cercidiphyllum japonicum - Lift crown over footpaths to give around 2.5m ground clearance, targeting secondary growth. Reduce lateral growth to N by around 1m to reduce end weight of leggy branches, pruning to suitable growth points.  
 60 Prunus avium Plena - Remove 1x stem that overhangs stairs and crown lift remaining secondary growth to 2.5m from ground level.  
 62 Platanus x hispanica - Prune branches away from streetlight to provide 1m clearance.  
 70 Platanus x hispanica - Prune branches away from streetlight to provide 0.5m clearance.  
 51 (0045) Prunus avium Plena - Crown lift to 2.5m from ground level, targeting secondary growth where possible. Thorough deadwood removal.  
 54 (0040) Prunus avium Plena - Crown lift to 2.5m from ground level, targeting secondary growth.  
 55 (0041) Liquidamber styraciflua - Crown lift to 2.5m from ground level, targeting secondary growth.  
 66 (0012) Platanus x hispanica - Prune branches away from streetlight to provide 1m clearance.  
 73 Platanus x hispanica - Prune branches away from streetlight to provide 1m clearance.  
 75 Platanus x hispanica - Crown lift to 2.5m from ground level, targeting secondary growth.  
 82 Quercus palustris - Prune branches away from streetlight to provide 1m clearance, pruning to suitable growth points.  
 86 Prunus subhirtella Autumnalis - Crown lift to 2.5m from ground level, targeting secondary growth.  
 88 Prunus subhirtella Autumnalis - Crown lift to 2.5m from ground level, targeting secondary growth where possible.  
 97 Platanus x hispanica - Prune branches away from streetlight to provide 0.5m clearance.

Priority C works as per survey 27872 recommendations

- Tree numbers - 1 Platanus x hispanica - Crown lift to 2.5m from ground level. Remove shoes from crown.  
 6 Platanus x hispanica - Crown lift to 2.5m from ground level, targeting secondary growth where possible. Prune branches away from sign to provide 0.5m clearance, pruning to suitable growth points.  
 7 Platanus x hispanica - Crown lift to 2.5m from ground level, targeting secondary growth where possible. Prune to give 0.5m clearance from structure adjacent, pruning to suitable growth points.  
 9 Platanus x hispanica - Crown lift to 2.5m from ground level, targeting secondary growth where possible.  
 10 Platanus x hispanica - Crown lift to 2.5m from ground level, including removal of low branch (90mm diameter) on east side of crown.  
 11 Platanus x hispanica - Crown lift to 2.5m from ground level targeting secondary growth where possible.  
 21 Prunus subhirtella Autumnalis x3 - Lift crown of tree to W to give 2.5m ground clearance over footpath, targeting secondary growth.  
 22 Cercidiphyllum japonicum - Lift crown over footpath to give around 2.5m ground clearance, targeting secondary growth.  
 23 Prunus subhirtella Autumnalis - Lift crown to give 2.5m ground clearance over footpath, targeting secondary growth.  
 29 Liquidamber styraciflua - Lift crown over footpath to give 2.5m ground clearance, targeting secondary growth where possible.  
 30 Prunus avium Plena - Crown lift to 2.5m from ground level, targeting secondary growth.  
 32 Sorbus alternifolia - Crown lift to 2.5m from ground level over footpaths to E and W, targeting secondary growth where possible.  
 33 Cercidiphyllum japonicum - Lift crown to give 2.5m ground clearance over footpaths, targeting secondary growth.  
 36 Prunus avium Plena - Lift crown to give 2.5m ground clearance over footpath, targeting secondary growth.  
 41 Prunus subhirtella Autumnalis - Prune to give 0.25m clearance from lamp column.

(Continued) Priority C works as per survey 27872 recommendations

- Tree numbers - 48 Prunus subhirtella Autumnalis - Lift crown to give 2.5m ground clearance over bike rack to W, targeting secondary growth where possible.  
 56 Quercus palustris - Crown lift to 2.5m from ground level, targeting secondary growth. Prune branches away from



Registered Office in England: Brandon House, First Floor, 90 The Broadway, Chesham, Buckinghamshire, HP5 1EG  
 Company No. 579 1625 | VAT No. 888 0779 56 @20%

**Artemis Tree Services Ltd**

West Hyde Nursery  
Old Uxbridge Road  
West Hyde  
Rickmansworth  
Herts WD3 9XY

**T:** 01895 821 623

**E:** office@artemistreeservices.com

**W:** www.artemistreeservices.com



All work shall be completed in line with BS3998:2010 -Recommendations for Tree Work where appropriate  
Artemis Tree Services Ltd will check all TPO and Conservation Area clearance if not already in place

umbrellas to provide 0.25m clearance.

52 (0043) Prunus avium Plena - Crown lift to 2.5m from ground level, targeting secondary growth.

Tree Number - 273 and 274

Tree Type - Plane (Platanus x hispanica)

Approx. Diameter at 1.5m - 270-290mm

Approx. Height - 17m

Approx. Crown Spread Diameter - 11m

Location - Handyside street, see maps.

Service - Crown Reduction

Work Required - Reduce Northern side (road side) of crown by up to 2.5m and remaining lateral spread on all sides by up to 1.5m. Reduce height by upto 2m, pruning to suitable growth points/branch fork junctions.

Reason - Branches in contact with adjacent building to South. Growth to North becoming leggy and over extended. To give clearance to building while maintaining reasonable form and balance.

PN - Client to allow parking on site for Artemis Vehicles and Machinery

PN - Client to liase with TFL about rental bike racks under T273 and T274 as area will need to be temporarily restricted from public access while works are undertaken.

All resulting brushwood and logs will be transported to our recycling depot awaiting transfer to Thetford Power Station to be used as bio-fuel (**unless otherwise stated in work description above**).

**Priorities**

U – Within 2 weeks (If necessary fencing off the hazard until work can be carried out)

A – Within 3 months    B – Within 6 months    C – Within 12 months    ON - Owner's discretion

Tree Preservation Order/Conservation area status: **In progress.**



Registered Office in England: **Brandon House, First Floor, 90 The Broadway, Chesham, Buckinghamshire, HP5 1EG**  
Company No. 579 1625 | VAT No. 888 0779 56 @20%