



DEM-GF-01 (ALTERATION) Doors to be unhung and replaced and hinged in the opposite way. The current doors are not original.

DEM-GF-02 (REINSTATED) Existing downlights to be removed. Pendant lighting to be reinstated throughout.

DEM-GF-03 (DEMO) Non-original door to be removed and opening to closet wing created.

DEM-GF-04 (DEMO) Non-orignal balcony to be removed and replaced with closet wing extension.

DEM-GF-05 (DEMO) Section of garden wall to be removed and replaced with closet wing extension.

Proposed Ground Floor Plan PR 1:100

PRO-GF-01 (REINSTATED) Pendant lighting.

PRO-GF-02 (REINSTATED) Celing rose.

PRO-GF-03 (REINSTATED) Cornicing to match original.

PRO-GF-04 (PROPOSED) Moulded Panel Bi-fold doors to match original visually.

PRO-GF-05 (PROPOSED) Proposed kitchen furniture units.

PRO-GF-06 (PROPOSED) Proposed kitchen furniture island. Extractor to be electric recirculating downdraft to minimse impact on existing fabric.

PRO-GF-07 (PROPOSED) Opening in wall to proposed closet wing extensio

PRO-GF-08 (PROPOSED) Closet wing extension.

PRO-GF-09 (PROPOSED) Metal staircase to garden level.

PRO-GF-10 (PROPOSED) Conservation half-glazed door to suit fenestration of adjacent window

PRO-GF-11 (PROPOSED) Add case

PRO-GF-12 (PROPOSED) Omit roof light.

© This drawing is the property of Miltiadou Cook Mitzman architects. No disclosure or copy of it may be made without the written permission of Miltiadou Cook Mitzman architects.

For construction purposes:


- Do not scale this drawing. - All dimensions and levels to be checked on site.

- Discrepancies to be reported to Miltiadou Cook
- Mitzman architects before proceeding. - If in any doubt about information on this drawing

contact Miltiadou Cook Mitzman architects

REVISION

REVISION			
NUMBER	DATE	BY	NOTES
P1	01/08/2023	OR	Issued for Planning
P2	02/10/2024	CG	Variation of Condition



Existing Elements

Demolition

Floor Demolition

Proposed Works


Cornecing / Ceiling Roses

- **Ø**_P Existing Pendant Light
- 💭 M Existing Wall Light
- Existing Recessed Downlight
- Existing Track Lighting
- Proposed Pendant Light

Rain Below Ground Drainage

Foul Below Fround Drainage

Combined Below Ground Drainage





ЛСМа

MILTIADOU соок

MITZMAN architects

020 7722 8525 office@mcma.design www.mcma.design

Unit 1 Primrose Mews Sharpleshall Street London NW1 8YW

CLIENT Mrs and Mr Brown

PROJECT 1 Rothwell Street, NW1 8YH



SHEET TITLE Ground Floor Plan

SCALE 1:100 @ A3

DATE CREATED

FILE REFERENCE

DRAWING NUMBER

394-DWG-1003

REVISION