

Tree Work Specifications
For
St Anne's Church
106, Highgate West Hill
London
N6 6AP

- T1. Ash** - Crown reduce height and spread back to previous reduction points leaving soft furnishing growth (approx. 5m height and 3.5m spread)
Remove major dead wood
- T2. Elm** - Crown reduce height by 5.0m
Crown reduce spread to balance and shape (approx. 3m)
Crown reduce low limb over road back in line with brick wall
- T3. Ash** - Crown reduce height and spread back to previous reduction points leaving soft furnishing growth (approx. 5m height and 3.5m spread)
Remove major dead wood
- T4. Ash** - Dismantle crown using rigging
Section fell trunk
Cut entire tree to ground level
- T5. Ash** - Dismantle crown using rigging
Section fell trunk
Cut entire tree to ground level
- T8. Ash** - Reduce crown spread towards church by 4.0m
- T9. Holly** - Crown reduce spread growing towards church back to stem
Crown reduce remainder of Holly back to previous reducing points (approx. 4m height and 1m spread)
- G1. Mixed Saplings** - These trees have been previously reduced very lightly
Reduce group of saplings by an additional 40% - 50%
Respectively (approx. 4m height and 2m spread)