

Notes

**GENERALLY:** 

Remove all recessed LED strip light

Remove alcove infills where required and make good.

Replace existing internal doors to hallway with panelled doors as per drawing (31)05. Finished doors to retain existing fire rating.

Replace contemporary skirting boards and architraves with new joinery of traditional design as per drawings (31)10 and (43)01.

Replacement sashes as per drawing (31)01.

Staircase details as per drawings (24)01 and (24)02.

Built in cupboards added Annotations updated Annotations updated

Kelley House 18-20 Royal College Street

Revisions

Proposed Third Floor Plan

ROGER MEARS ARCHITECTSLLP

Union Chapel, Compton Avenue

tel 020 7359 8222

16/12/2024

18/11/2024

01/08/2024

rma@rmears.co.uk www.rmears.co.uk © Roger Mears Architects LLP 1:50@A3 Sep 2024

Job No. Dwg No. 2245 (02)14 C