



Any discrepancies between information shown on this drawing and any other contract information
manufacturers/suppliers recommendations is to be brought to the attention of the Architect.

L-2	07/02/2025	Revised as per agreements

of Works Key:	06	03.445.06 - Existing kerbstone and concrete floor finishes to be removed
conjunction with schedule 383(SL) Listed Building Consent Schedule of Works, heet 445	07	03.445.07 - Existing tarmac surface to be removed
.01 - Existing ground floor single glazed timber sash window to be removed	08	03.445.08 - Existing ground floor slab to be cut back to create new level threshold
.02 - Existing high level single glazed timber basement window to be removed	09	03.445.09 - Existing trimming steel to be removed
.03 - Existing solid masonry wall to be removed carefully below window and bricks retained for future use	10	03.445.10 - Existing electrical conduit + lighting to be removed
.04 - Existing concrete lintel to be removed at head of basement window	11	03.445.11 - Existing low level redundant external pipework and fixings to be removed, holes in brickwork to filled
.05 - Existing chamfered brick cill to be removed	31	03.445.31 - New full height PPC aluminium curtain walling in existing structural opening, colour: dark grey





Hale Brown Architects Ltd. Unit 1.04, Edinburgh House, 170 Kennington Lane, London, SE11 5DPT: 020 3735 7442E: mail@halebrown.comW: www.halebrown.com