


Typical Section Through Tree Pit Within Areas Of Soft Landscape - Where a Geo-Textile Membrane Is Used To Seperate The Existing Ground Condition From New Imported Soils



Typical Plan View Of Tree Pit Within Areas Of Soft Landscape Scale: 1:20 at A1

All dimensions in millimetres unless otherwise shown.
 All levels in metres above Ordinance Datum (mAOD) unless otherwise shown.

3. All dimensions to be checked on site and any discrepancies reported to Employer before pricing / work starts.

4. Any ambiguities or discrepancies within this drawing and any other information given elsewhere must be reported to Camlins and the Employer for clarification before pricing work proceeds.

5. All drawings to be read in conjunction with other Camlins drawings and specification information as appropriate. Refer to relevant Engineer's and Architect's information as appropriate for confirmation of all engineering and architectural details.

7. All works to be carried out in accordance with the latest British Standards and appropriate codes

TREE PLANTING, TREE SELECTION & APPROVAL

- TREES TO BE SELECTED AND APPROVED BY THE EMPLOYER AT THE NURSERY FROM A GROUP OF AT LEAST 200% OF THE REQUIRED QUANTITY. - Cost of trees to include for travel expenses for Nursery visits as necessary for the Landscape

Architect to approve the trees. Representative photos of the trees to be provided prior to any Nursery visit.

For tree species & stock sizes refer to Tree Planting Plan Drg. No. TRI-CLA-ZZ-00-DR-L-0061.

Trees to be well balanced in root and crown and to be good examples of the species.

Trees of the same species and stock size to be a matching set unless directed otherwise by

Evidence to be provided of transplanting in last 4 years. Trees to have been undercut a minimum of 12 and a maximum of 24 months before planting.

- Trees to be containerised in air pot system during last winter season before planting.

# Trees to be installed within constructed tree pit so that growing / nursery line is located at the top

of the tree pit (top of root ball at top of topsoil layer). IMPORTED TOPSOIL & SUBSOIL

# - 300mm depth of topsoil and 500mm depth of subsoil for areas of tree planting.

Topsoil must never be installed to a greater depth than 300mm. Topsoil to comply with BS 3882.
Topsoil to be a well structured sandy-loam and free from stones or any other contaminants.

Topsoil must never be contaminated with other material, including hardcore. Topsoil must never be laid over standing water or sodden ground.

Topsoil must never be overcompacted

Iopsoil must never be overcompacted.
Subsoil to comply with BS 8601.
Subsoil Organic Matter Content to be no more than 1%.
Manufactured topsoil to comply with BS 3882.
Manufactured topsoil Organic Matter Content to be a maximum of 30%.
Manufactured topsoil to have a maximum aggregate size of 25mm.
All imported topsoil and subsoil to be sourced from a reputable source and to be friable,

free-draining and uncompacted.

Representative sample of all imported topsoils and subsoils to be provided to Employer for approval a minimum of 4 weeks in advance of bulk delivery to site.

## Possible Supplier

Bourne Amenity
The Wharf, Rye Road, Kent, TN18 5QG

Tel.: 01797 252 299 Web.: https://bourneamenity.co.uk/

**EXISTING AREAS OF TOPSOIL & SUBSOIL** 

## - Ground Investigation Report to assess existing soil conditions. Contractor to allow for the appointment of a Soil Specialist to independently asses the condition

of all retained topsoil and subsoil Soil Specialist to provide detailed Method Statement for the handling of retained topsoil and subsoil to ensure it is fit for future planting proposals. This Method Statement will confirm any additional compost requirements, remediation measures and methods of stripping and temporary storage to ensure that existing topsoils are friable, free-draining and uncompacted.

does occur must be rectified by the Contractor to the approval of the Landscape Architect.

- Strictly no compaction to occur of all existing topsoil areas to be retained. Any compaction that

Contractor to allow for the appointment of a Soil Specialist to independently asses the condition of all imported topsoil and subsoil. Contractor must not rely on the suppliers documentation.

Possible Supplier Soil Analysis
Tim O-Hare Associates Soil & Landscape Consultancy
Howbery Park, Wallingford, Oxfordshire, OX10 8BA Tel.: 01491 822 653

http://www.timohare-associates.com/contact.php
For confirmation of soil areas refer to Drg. No. TRI-CLA-ZZ-00-DR-L-0041 GA - Growing Medium

All planting beds to be mulched with 40-60mm depth ornamental grade, composted bark fines

Mulch to be screen to 0-10mm particle size, ph 4.5-5.5. UK Origin. FSC chain of custody certified. To have been composted for a minimum of 9-10 weeks, no urea added, minimum three turns. Suggested product: https://www.cpa-horticulture.co.uk/composted-bark-fines Sample to be issued to client / Landscape Architect for approval.

## TREE ANCHORING SYSTEM

To be GreenBlue Urban ArborGuy AnchorPlate Kit or similar as approved. Each tree to be secured with underground Tree Anchoring System consisting of adjustable canvas straps that are to be securly located to the shoulder of the root ball, with three high strength galvanised steel wires connected to 3no ArborGuy AnchorPlates placed at bottom of pit. Protective matt to be utilised to ensure guying system does not cut into root ball. All ratchets to be

# IRRIGATION / AERATION SYSTEM

Irrigation/aeration system to be 60mmø pvc perforated pipe installed around shoulder of root ball within growing medium. Aeration pipe connected to surface with vertical pipe of same specification and tee sections as required.

Possible Supplier - Tree Anchor, Irrigation/Aeration System & Root Barrier GreenBlue Urban, Haywood Way, Hastings, East Sussex TN35 4PL Tel.: 01424 717 797

**EXISTING GROUND IN ROOT PROTECTION AREAS** Installation of soft landscaping (As per AIA)

- Within the root protection areas of trees to be retained, the preparation of soil for planting and turfing will be carried out by hand. - Cultivation will be kept to a minimum and new topsoil must not exceed 100mm in depth within 1m of the stem.

- Top soil and other materials will be transported by wheelbarrow on running boards when working near trees.

P01 2025-02-13 Notes reviewed and updated, Section updated to include sand free draining layer



Tribeca, London

**Drawing Number** 

New Zealand House, Abbey Foregate, Shrewsbury, Shropshire, SY2 6FD 01743 290 779

Revised by Checked by

Reef Group Typical Tree Planting Detail Within Soft Landscape

Planning Condition Discharge

P01 1:20@A1 TRI-CLA-ZZ-ZZ-DR-L-0702

09.08.2024