



Bottom of gutter detail outside Theatre Office window

As Proposed Option 2

1:5

NOTE

Dimensions shown and height of clerestorey windows to be confirmed following opening up works

All dimensions are TBC subject to site opening up works

KEY TO MATERIALS

- 1 Existing timber clerestorey window to Store
- 2 Existing brickwork
- 3 New GRP gutter to clause R10 with lead flashing to clause H71
- 4 New timber furring and boards below new GRP gutter to clause K20 (detail in abeyance until further opening up).
- 5 New timber joists to clause G20 below timber boards (detail in abeyance until further opening up)
- 6 Existing facing stonework
- 7 Assumed line of existing lead gutter and timber deck

P01 Issue for Planning		28:01:25 ck	
rev.	description	date	drawn chkd

client :

UCL

project :

The Slade School of Fine Art
Gower St London WC1E 6BT
External Repairs

drawing title :

Gutter Detail 2
Bottom of gutter outside Theatre Office
As Proposed Option 2

FulkersBaileyRussell

London | Basingstoke | Brighton | Bristol | Cardiff | Kings Hill | Manchester

info@fulkers.co.uk // www.fulkers.co.uk // 020 3735 5792

proj no :	24 4682	scale:	1: 5 @A3
-----------	---------	--------	----------

identifier :	4682-FBR-A1-XX-DR-A-SK06
--------------	--------------------------

status:	S2 (For Information)	rev no:	P.01
---------	----------------------	---------	------

1:5

