

PLANNING

STAGE:

KEY					
FIRE					
	Fire resistant construction (30 mins)				
	Fire resistant construction (60 mins)				
Η	Heat Detector				
S	Smoke Detector				
¢	Carbon Monoxide Detector				
FD30S	30 min fire door with smoke seal				
SC	Self closing				
S	Smoke Vent				
X	Rooflight Vent				
٢	Fire Mist System				

NOTES

(i) Installation of a single unified automatic fire detection and alarm system (Type LD1 - minimum Grade D1) to BS 5839-6:2019+A1:2020 throughout all parts of the flat with simultaneous evacuation of all floors on occurrence of alarm i.e. detection to be provided in all habitable rooms/circulation spaces, interlinked and mains powered.(ii) Internal protected hallway to be provided adjacent to the flat entrance to ensure compliance with clause8.5NOTE 3 of BS 9991:2024. i.e. 30 minute fire-resisting construction with FD30 doorset, no self-closer required. (iii) Enclosure between the

kitchen/dining/bedrooms/stores and stair/hallway at the lower ground floor level to be provided with 30 minutes fire-resisting construction with FD30 doorsets, no self-closer required.

(iv) Enclosure between the rear bedrooms and stair/hallway/open plan areas at the ground floor level to be provided with 30 minutes fire-resisting construction with FD30 doorsets, no self-closer required.

(v) Window/door suitable for escape to be provided from all habitable rooms at the ground floor level and lower groundfloor level with the exception of the spare bedroom at the lower ground floor level, open plan lego room at ground floor level and office at the gallery floor level. (vi) Independent means of escape to be provided

(vii) Flat to be compartmented from the adjacent flats/units by a minimum of 60 minutes fire-resisting construction assumed existing.

	10m	20m	1:1250	20m 30	0m 40m 50m		
Y:	DATE:		HOLLOWAY+HOLLOW	٩Y			
		HH	DONNINGTON HOUSE COLLEGE AVENUE MAIDENHEAD, BERKSHIRE, SL6 6AP				
		Client	JON TIPPELL				
		Address	REGENTS PARK ROAD				
		TITLE	FIRE PLANS				
		DRAWING	151				
		REV.	-	SCALE	AS STATED		
		STATUS	PLANNING	DRAWN	VH		
		DATE	MARCH 25	CHECKED	-		