




FOUNDATION SCHEDULE	
REF.	SIZE
PD1	450 DEEP MASS CONCRETE RAFT
PD2	2000x2000x1000(Dp) MC PAD FOOTING
PD3	3000x1500x1000(Dp) MC PAD FOOTING
PD4	1200x1200x600(Dp) MC PAD FOOTING
PD5	1500x1500x1000(Dp) MC PAD FOOTING
PD6	1500x1500x1000(Dp) MC PAD FOOTING
SF1	1000x1000x1000(Dp) MC PAD FOOTING
SF2	750x750x600(Dp) MC PAD FOOTING
SF3	600(W)x350(Dp) MC STRIP FOOTING
SF4	450(W)x450(Dp) MC STRIP FOOTING
SF5	900(W)x600(Dp) MC STRIP FOOTING
SF6	1000(W)x350(Dp) MC STRIP FOOTING
SF7	600(W)x600(Dp) MC STRIP FOOTING

LINTEL SCHEDULE	
REF.	TYPE / SIZE
L1	100mm (W) x 140mm (DP) PRECAST CONCRETE
L2	140mm (W) x 140mm (DP) PRECAST CONCRETE
L3	215mm (W) x 140mm (DP) PRECAST CONCRETE
L4	CATNIC CH110/125 CAVITY WALL LINTEL
L5	CATNIC CX EXTRA HEAVY DUTY CAVITY WALL LINTEL (EXISTING CAVITY TO BE MEASURED)
BEARING FOR ALL LINTELS TO BE 150mm MINIMUM.	

This drawing is to be read in conjunction with all relevant architects, engineers and specialists drawings and specifications.

LEGEND	
	EXISTING STRUCTURE TO BE RETAINED
	NEW REINFORCED CONCRETE
	NEW REINFORCED WATER RESISTANT CONCRETE
	NEW LOAD BEARING STUDWORK
	NEW MASS CONCRETE
	NEW LOAD BEARING BLOCKWORK
	NEW LOAD BEARING BRICKWORK
	PADSTONES
	LOAD BEARING STRUCTURE BELOW
	NEW STEEL BEAMS
	NEW LINTELS OVER OPENINGS
	MOMENT CONNECTION
	THERMAL BREAK

STEELWORK COLUMN SCHEDULE	
COLUMN REF.	COLUMN SIZE
SC1	SHS140x140x5
SC2	UC152x152x23
SC3	SHS100x100x5
SC6	RHS200x100x10

STEELWORK BEAM SCHEDULE	
BEAM REF.	BEAM SIZE
SB1	UB203x102x23
SB2	UB203x133x30
SB3	UC203x203x46
SB4	UC203x203x60
SB5	UC203x203x71
SB7	UC152x152x23
SB8	UC152x152x37
SB9	50x12mm PLATE (S275)
SB10	SHS140x140x5
SB13	UC203x203x66
SB14	RHS300x200x12.5
SB15	RHS200x150x12.5

WALL SCHEDULE	
WALL REF.	WALL SIZE
W1	150mm THK RC WALL
W2	250mm THK WRC WALL
W3	100mm THK, 7.3N BLOCKWORK WALL
W4	140mm THK, 7.3N BLOCKWORK WALL
W5	140mm 7.3N LOAD BEARING BLOCWORK INNER LEAF, CAVITY/INSULATION TO ARCHITECTS DETAIL WITH 100MM FACING BRICK OUTER LEAF TO ARCHITECTS DETAILS
W6	100mm 7.3N LOAD BEARING BLOCWORK INNER LEAF, CAVITY/INSULATION TO ARCHITECTS DETAIL WITH 100MM FACING BRICK OUTER LEAF TO ARCHITECTS DETAILS
W7	225mm CLASS B ENGINEERING BRICK WALL

C5	30.09.24	NL	AS	Revised as clouded
C4	02.09.24	NL	DB	Issued for Construction
C3	20.08.24	MC	DB	Revised as clouded
C2	16.08.24	NL	DB	Revised as clouded
C1	02.08.24	PW	DB	Issued for Construction
P2	08.02.24	MC	IG	Updated as clouded
P1	26.01.24	MC	IG	Draft Contract Issue for Review
rev	date	by	chk	description

elliottwood engineering a better society


Elliott Wood Partnership Ltd
Central London • Wimbledon • Nottingham
Consulting Structural and Civil Engineers
(020) 7499 5888 • elliottwood.co.uk

Project
12 Pilgrim's Lane
Hampstead, London


Drawing title
Proposed Lower Ground Floor

Scale (s)	Date	Drawn
1:50@ A1;	August 2023	MC
Drawing status	Status	Revision
Construction	A5	C5
Project no.	Originator Zone	Level Type Role
2210419-EWP-ZZ-LG-DR-S-0900		


1. PRIOR TO ROOF DEMOLITION, CONTRACTOR TO ALLOW FOR INSTALLATION OF TEMPORARY WORKS TO RESTRAIN CHIMNEYS UNTIL PERMANENT ROOF STRUCTURE AND RESTRAINT IS PROVIDED
2. REPLACEMENT OF EXISTING FLOORS TO BE SEQUENCED INTO BAYS TO MAINTAIN RESTRAINT TO WALLS AND MAINTAIN DIAPHRAGM ACTION FOR OVERALL BUILDING STABILITY. ALTERNATIVELY PROVIDED TEMPORARY WORKS PROPOSALS FOR LARGER AREAS OF REMOVAL.
3. GROUND LEVEL TO NO.14 PILGRIM'S LANE TO BE ESTABLISHED PRIOR TO ANY WORKS COMMENCING. CONTRACTOR TO ALLOW FOR TEMPORARY TRENCH SHEETINGS/SHIELD PILING TO FORM LGF AND STAIRCASE WITH FINAL DESIGN TO BE PROVIDED BY TEMPORARY WORKS DESIGNER ONCE LEVELS ARE ESTABLISHED
4. CONTRACTOR TO ENSURE THE STABILITY OF THE BUILDING IS MAINTAINED AT ALL TIMES AND NO AREAS/ELEMENTS ARE LEFT UNSUPPORTED
5. CONTRACTOR TO PROVIDED TEMPORARY WORKS/GROUND WORKS PROPOSALS FOR FORMING REINFORCED UNDERPINNING BENEATH EXISTING BUILDING




DRG SC1 BASEPLATE
1: 10@A1



DRG SC2 BASEPLATE
1: 10@A1



DRG SC3 BASEPLATE
1: 10@A1



GENERAL KEY	
RS	INDICATES RESTRAINT STRAPS. 1200x30x2.5 RESTRAINT STRAPS TO BE INSTALLED AT Max 1200mm CTRS (STRONG BACKS) TO BE PROVIDED TO METAL WEB JOISTS AT RESTRAINT STRAP LOCATIONS. WHERE RESTRAINT STRAPS ARE INTO EXISTING WALLS, STRAPS TO BE CAST INTO 330x100x150mm MASS CONCRETE POCKETS
XC	DENOTES STEELWORK TO BE CRANKED. PROVIDE FULL STRENGTH, FULL PENETRATION BUTT WELD AT CRANK LOCATION

LINTEL SCHEDULE			
REF.	TYPE / SIZE		
L1	100mm (W) x 140mm (DP) PRECAST CONCRETE		
L2	140mm (W) x 140mm (DP) PRECAST CONCRETE		
L3	215mm (W) x 140mm (DP) PRECAST CONCRETE		
L4	CATNIC CH110/125 CAVITY WALL LINTEL		
L5	CATNIC CX EXTRA HEAVY DUTY CAVITY WALL LINTEL (EXISTING CAVITY TO BE MEASURED)		
BEARING FOR ALL LINTELS TO BE 150mm MINIMUM.			
PADSTONE SCHEDULE			
REF.	LENGTH	DEPTH	HEIGHT
P1	440 mm	215 mm	225 mm
P2	450 mm	100 mm	225 mm
P3	650 mm	225 mm	225 mm
P4	450 mm	140 mm	225 mm

This drawing is to be read in conjunction with all relevant architects, engineers and specialists drawings and specifications.	
Do not scale from this drawing.	
LEGEND	
	EXISTING STRUCTURE TO BE RETAINED
	NEW REINFORCED CONCRETE
	NEW REINFORCED WATER RESISTANT CONCRETE
	NEW LOAD BEARING STUDWORK
	NEW MASS CONCRETE
	NEW LOAD BEARING BLOCKWORK
	NEW LOAD BEARING BRICKWORK
	PADSTONES
	LOAD BEARING STRUCTURE BELOW
	NEW STEEL BEAMS
	NEW LINTELS OVER OPENINGS
	MOMENT CONNECTION
	THERMAL BREAK

STEELWORK COLUMN SCHEDULE	
COLUMN REF.	COLUMN SIZE
SC1	SHS140x140x5
SC2	UC152x152x23
SC3	SHS100x100x5
SC6	RHS200x100x10

STEELWORK BEAM SCHEDULE	
BEAM REF.	BEAM SIZE
SB1	UB203x102x23
SB2	UB203x133x30
SB3	UC203x203x46
SB4	UC203x203x60
SB5	UC203x203x71
SB7	UC152x152x23
SB8	UC152x152x37
SB9	50x12mm PLATE (S275)
SB10	SHS140x140x5
SB13	UC203x203x66
SB14	RHS300x200x12.5
SB15	RHS200x150x12.5

WALL SCHEDULE	
WALL REF.	WALL SIZE
W1	150mm THK RC WALL
W2	250mm THK WRC WALL
W3	100mm THK, 7.3N BLOCKWORK WALL
W4	140mm THK, 7.3N BLOCKWORK WALL
W5	140mm 7.3N LOAD BEARING BLOCWORK INNER LEAF, CAVITY/INSULATION TO ARCHITECTS DETAIL WITH 100MM FACING BRICK OUTER LEAF TO ARCHITECTS DETAILS
W6	100mm 7.3N LOAD BEARING BLOCWORK INNER LEAF, CAVITY/INSULATION TO ARCHITECTS DETAIL WITH 100MM FACING BRICK OUTER LEAF TO ARCHITECTS DETAILS
W7	225mm CLASS B ENGINEERING BRICK WALL

C2	02.09.24	NL	DB	Issued for Construction
C1	02.08.24	PW	DB	Issued for Construction
P5	08.02.24	MC	IG	Updated as clouded
P4	26.01.24	MC	IG	Draft Contract Issue for Review
P3	14.09.23	PW	IG	Revised as clouded
P2	01.09.23	PW	IG	Tender Issue
P1	24.08.23	PW	IG	Tender Issue
rev	date	by	chk	description

elliottwood engineering a better society

Elliott Wood Partnership Ltd
Central London • Wimbledon • Nottingham
Consulting Structural and Civil Engineers
(020) 7499 5888 • elliottwood.co.uk

Project
12 Pilgrim's Lane
Hampstead, London

Drawing title
Proposed First Floor Plan

Scale (s)
1:500 @ A1:

Date
August 2023

Drawn
MC

Drawing status
Construction

Status
A5

Revision
C2

Project no.
2210419-EWP-ZZ-01-DR-S-1010

Originator Zone
Level Type Role
drg no.

FLOOR / ROOF SCHEDULE	
	PS10 POSI-JOISTS (253mm DEEP) @ 400 c/c SHEATHED IN 18mm PLY
	PS8 POSI-JOISTS (202mm DEEP) @ 400 c/c SHEATHED IN 18mm PLY
	50x200mm C24 ROOF JOISTS / RAFTERS @ 300mm c/c SHEATHED IN 18mm PLY
ALLOW FOR ALL FLOOR JOISTS TO BE DOUBLED UP BENEATH ANY PARTITIONS RUNNING PARALLEL TO THE JOIST SPAN AND BLOCKING TO BE PROVIDED ALONG PARTITIONS ALIGNING PERPENDICULAR TO THE JOIST SPAN	
FINAL DESIGN OF POSI JOISTS BY MANUFACTURER BASED ON THE FOLLOWING SLS (UNFACTORED LOADINGS): - SUPERIMPOSED DL (EXCL SELFWEIGHT OF JOISTS) = 1.25kN/m² - SUPERIMPOSED LL = 2.00kN/m²	


1. PRIOR TO ROOF DEMOLITION, CONTRACTOR TO ALLOW FOR INSTALLATION OF TEMPORARY WORKS TO RESTRAIN CHIMNEYS UNTIL PERMANT ROOF STRUCTURE AND RESTRAINT IS PROVIDED
2. REPLACEMENT OF EXISTING FLOORS TO BE SEQUENCED INTO BAYS TO MAINTAIN RESTRAINT TO WALLS AND MAINTAIN DIAPHRAGM ACTION FOR OVERALL BUILDING STABILITY. ALTERNATIVELY PROVIDED TEMPORARY WORKS PROPOSALS FOR LARGER AREAS OF REMOVAL
3. GROUND LEVEL TO NO. 14 PILGRIM'S LANE TO BE ESTABLISHED PRIOR TO ANY WORKS COMMENCING. CONTRACTOR TO ALLOW FOR TEMPORARY TRENCH SHEETING/SHEET PILING TO FORM LGF AND STAIRCASE WITH FINAL DESIGN TO BE PROVIDED BY TEMPORARY WORKS DESIGNER ONCE LEVELS ARE ESTABLISHED
4. CONTRACTOR TO ENSURE THE STABILITY OF THE BUILDING IS MAINTAINED AT ALL TIMES AND NO AREAS/ELEMENTS ARE LEFT UNSUPPORTED
5. CONTRACTOR TO PROVIDED TEMPORARY WORKS/GROUND WORKS PROPOSALS FOR FORMING REINFORCED UNDERPINNING BENEATH EXISTING BUILDING



CONNECTION FORCES					
Type	My(kNm)	V(kN)	N(kN)	TM(kNm)	T(kN)
A		75	75		
B		150	150		
C		125	75	10	
D	20	75	75		
E		225	225		
F	5	100		100	

- STEEL CONNECTION NOTES:**
1. Forces indicated are factored (ULS)
 2. Annotations
 - My = Moment in Major Axis (kNm)
 - V = Vertical shear (kN)
 - N = Axial Tie Force (kN)
 - TM = Torsional Moment (kNm)
 - T = axial tension (kN)
 - C = AXIAL COMPRESSION (kN)
 3. Axial Tie forces may be considered as a separate connection load case. All other specified connection forces are to be considered acting simultaneously
 4. Slip resistant moment connections to be provided at all moment connections
 5. Provide minimum 4no. M16 bolts per connection
 6. Provide minimum grade 8.8 bolts
 7. Provide minimum 6mm fillet welds

Scale (s)	Date					Drawing	
1:50@ A1;	August 2023					MO	
Drawing status			Status			Revision	
Construction			A5			C3	
Project no.	Originator	Zone	Level	Type	Role	drg no.	
2210419-EWP-ZZ-	02-	DR-	S-	1020			



GENERAL KEY	
RS	INDICATES RESTRAINT STRAPS. 1200x300x2.5 RESTRAINT STRAPS TO BE INSTALLED AT Max 1200mm CTRS (STRONG BACKS) TO BE PROVIDED TO METAL WEB JOISTS AT RESTRAINT STRAP LOCATIONS. WHERE STRAPS TO BE CAST INTO 330x100x150mm MASS CONCRETE POCKETS
XC	DENOTES STEELWORK TO BE CRANKED. PROVIDE FULL STRENGTH, FULL PENETRATION BUTT WELD AT CRANK LOCATION

This drawing is to be read in conjunction with all relevant architects, engineers and specialists drawings and specifications.

Do not scale from this drawing.

LEGEND	
	EXISTING STRUCTURE TO BE RETAINED
	NEW REINFORCED CONCRETE
	NEW REINFORCED WATER RESISTANT CONCRETE
	NEW LOAD BEARING STUDWORK
	NEW MASS CONCRETE
	NEW LOAD BEARING BLOCKWORK
	NEW LOAD BEARING BRICKWORK
	PADSTONES
	LOAD BEARING STRUCTURE BELOW
	NEW STEEL BEAMS
	NEW LINTELS OVER OPENINGS
	MOMENT CONNECTION
	THERMAL BREAK

STEELWORK COLUMN SCHEDULE	
COLUMN REF	COLUMN SIZE
SC1	SHS140x140x5
SC2	UC152x152x23
SC3	SHS100x100x5
SC6	RHS200x100x10

STEELWORK BEAM SCHEDULE	
BEAM REF	BEAM SIZE
SB1	UB203x102x23
SB2	UB203x133x30
SB3	UC203x203x46
SB4	UC203x203x60
SB5	UC203x203x71
SB7	UC152x152x23
SB8	UC152x152x37
SB9	50x12mm PLATE (S275)
SB10	SHS140x140x5
SB13	UC203x203x66
SB14	RHS300x200x12.5
SB15	RHS200x150x12.5

PADSTONE SCHEDULE			
REF	LENGTH	DEPTH	HEIGHT
P1	440 mm	215 mm	225 mm
P2	450 mm	100 mm	225 mm
P3	650 mm	225 mm	225 mm
P4	450 mm	140 mm	225 mm

C3	30.09.24	NL	AS	Revised as clouded
C2	02.09.24	NL	DB	Issued for Construction
C1	02.08.24	PW	DB	Issued for Construction
P2	08.02.24	MC	IG	Updated as clouded
P1	26.01.24	MC	IG	Draft Contract Issue for Review
rev	date	by	chk	description

elliottwood engineering a better society

Elliott Wood Partnership Ltd
Central London • Wimbledon • Nottingham
Consulting Structural and Civil Engineers
(020) 7499 5888 • elliottwood.co.uk

Project
12 Pilgrim's Lane
Hampstead, London

Drawing title
Proposed Roof Plan

Scale (s)	Date	Drawn
1:50@ A1:	August 2023	MC
Drawing status	Status	Revision
Construction	A5	C3
Project no.	Originator Zone	Level Type Role
2210419-EWP-ZZ-03-DR-S-1030		

FLOOR / ROOF SCHEDULE	
	PS10 POSI-JOISTS (253mm DEEP) @ 400 c/c SHEATHED IN 18mm PLY
	PS8 POSI-JOISTS (202mm DEEP) @ 400 c/c SHEATHED IN 18mm PLY
	50x200mm C24 ROOF JOISTS / RAFTERS @ 300mm c/c SHEATHED IN 18mm PLY
ALLOW FOR ALL FLOOR JOISTS TO BE DOUBLED UP BENEATH ANY PARTITIONS RUNNING PARALLEL TO THE JOIST SPAN AND BLOCKING TO BE PROVIDED ALONG PARTITIONS ALIGNING PERPENDICULAR TO THE JOIST SPAN	
FINAL DESIGN OF POSI JOISTS BY MANUFACTURER BASED ON THE FOLLOWING SLS (UNFACTORED LOADINGS): - SUPERIMPOSED DL (EXCL SELFWEIGHT OF JOISTS) = 1.25kN/m² - SUPERIMPOSED LL = 2.00kN/m²	

1. PRIOR TO ROOF DEMOLITION, CONTRACTOR TO ALLOW FOR INSTALLATION OF TEMPORARY WORKS TO RESTRAIN CHIMNEYS UNTIL PERMANT ROOF STRUCTURE AND RESTRAINT IS PROVIDED
2. REPLACEMENT OF EXISTING FLOORS TO BE SEQUENCED INTO BAYS TO MAINTAIN RESTRAINT TO WALLS AND MAINTAIN DIAPHRAGM ACTION FOR OVERALL BUILDING STABILITY. ALTERNATIVELY PROVIDED TEMPORARY WORKS PROPOSALS FOR LARGER AREAS OF REMOVAL.
3. GROUND LEVEL TO NO.14 PILGRIMS LANE TO BE ESTABLISHED PRIOR TO ANY WORKS COMMENCING. CONTRACTOR TO ALLOW FOR TEMPORARY TRENCH SHEETING/SHEET PILING TO FORM L/GF AND STAIRCASE WITH FINAL DESIGN TO BE PROVIDED BY TEMPORARY WORKS DESIGNER ONCE LEVELS ARE ESTABLISHED
4. CONTRACTOR TO ENSURE THE STABILITY OF THE BUILDING IS MAINTAINED AT ALL TIMES AND NO AREAS/ELEMENTS ARE LEFT UNSUPPORTED
5. CONTRACTOR TO PROVIDED TEMPORARY WORKS/GROUND WORKS PROPOSALS FOR FORMING REINFORCED UNDERPINNING BENEATH EXISTING BUILDING



CONNECTION FORCES					
Type	My(kNm)	V(kN)	N(kN)	TM(kNm)	T(kN)
A		75	75		
B		150	150		
C		125	75	10	
D	20	75	75		
E		225	225		
F		5	100		100

STEEL CONNECTION NOTES:

1. Forces indicated are factored (ULS)
2. Annotations

My = Moment in Major Axis (kNm)
V = Vertical shear (kN)
N = Axial Tie Force (kN)
TM = Torsional Moment (kNm)
T = axial tension (kN)
C = AXIAL COMPRESSION (kN)

3. Axial Tie forces may be considered as a separate connection load case. All other specified connection forces are to be considered acting simultaneously
4. Slip resistant moment connections to be provided at all moment connections
5. Provide minimum 4no. M16 bolts per connection
6. Provide minimum grade 8.8 bolts
7. Provide minimum 6mm fillet welds

This drawing is to be read in conjunction with all relevant architects, engineers and specialists drawings and specifications.

Do not scale from this drawing.

LEGEND

	EXISTING STRUCTURE TO BE RETAINED
	EXISTING STRUCTURE TO BE REMOVED
	NEW REINFORCED CONCRETE
	NEW MASS CONCRETE
	NEW PRECAST CONCRETE
	NEW REINFORCED WATER RESISTANT CONCRETE
	NEW STRUCTURAL STEELWORK
	NEW LOAD BEARING BLOCKWORK
	NEW LOAD BEARING BRICKWORK
	NEW LOAD BEARING TIMBER
	NEW CROSS LAMINATED TIMBER
	NEW GLAZING
	STRUCTURE HIDDEN

PADSTONE SCHEDULE

REF	LENGTH	DEPTH	HEIGHT
P1	440 mm	215 mm	225 mm
P2	450 mm	100 mm	225 mm
P3	650 mm	225 mm	225 mm
P4	450 mm	140 mm	225 mm

STEELWORK COLUMN SCHEDULE

COLUMN REF	COLUMN SIZE
SC1	SHS140x140x5
SC2	UC152x152x23
SC3	SHS100x100x5
SC6	RHS200x100x10

STEELWORK BEAM SCHEDULE

BEAM REF	BEAM SIZE
SB1	UB203x102x23
SB2	UB203x133x30
SB3	UC203x203x46
SB4	UC203x203x60
SB5	UC203x203x71
SB7	UC152x152x23
SB8	UC152x152x37
SB9	50x12mm PLATE (S275)
SB10	SHS140x140x5
SB13	UC203x203x86
SB14	RHS300x200x12.5
SB15	RHS200x150x12.5

C2	14.10.24	MC	AS	SSL Updated
C1	02.09.24	NL	DB	Issued for Construction
P5	08.02.24	MC	IG	Updated as clouded
P4	26.01.24	MC	IG	Draft Contract Issue for Review
P3	14.09.23	PW	IG	Revised as clouded
P2	01.09.23	PW	IG	Tender Issue
P1	24.08.23	PW	IG	Tender Issue
rev	date	by	chk	description


elliottwood engineering
a better society

Elliott Wood Partnership Ltd
Central London • Wimbledon • Nottingham
Consulting Structural and Civil Engineers
(020) 7499 5888 • elliottwood.co.uk

Project
12 Pilgrim's Lane
Hampstead, London

Drawing title
Proposed Section A-A

Scale (s)				Date			Drawn
1:50@ A1;				October 2024			MC
Drawing status				Status			Revision
Construction				A5			C2
Project no.		Originator	Zone	Level	Type	Role	drg no.
2210419-EWP-ZZ-ZZ-DR-S-2000							



DRG
0900
SECTION A-A
1:50@A1

1. PRIOR TO ROOF DEMOLITION, CONTRACTOR TO ALLOW FOR INSTALLATION OF TEMPORARY WORKS TO RESTRAIN CHIMNEYS UNTIL PERMANENT ROOF STRUCTURE AND RESTRAINT IS PROVIDED
2. REPLACEMENT OF EXISTING FLOORS TO BE SEQUENCED INTO BAYS TO MAINTAIN RESTRAINT TO WALLS AND MAINTAIN DIAPHRAGM ACTION FOR OVERALL BUILDING STABILITY. ALTERNATIVELY PROVIDED TEMPORARY WORKS PROPOSALS FOR LARGER AREAS OF REMOVAL
3. GROUND LEVEL TO NO.14 PILGRIM'S LANE TO BE ESTABLISHED PRIOR TO ANY WORKS COMMENCING. CONTRACTOR TO ALLOW FOR TEMPORARY TRENCH SHEETING/SHEET PILING TO FORM LGF AND STAIRCASE WITH FINAL DESIGN TO BE PROVIDED BY TEMPORARY WORKS DESIGNER ONCE LEVELS ARE ESTABLISHED
4. CONTRACTOR TO ENSURE THE STABILITY OF THE BUILDING IS MAINTAINED AT ALL TIMES AND NO AREAS/ELEMENTS ARE LEFT UNSUPPORTED
5. CONTRACTOR TO PROVIDE TEMPORARY WORKS/GROUND WORKS PROPOSALS FOR FORMING REINFORCED UNDERPINNING BENEATH EXISTING BUILDING



! LOWER GROUND FLOOR RETAINING WALLS NEED TO BE PROPED AT HEAD AND BASE IN TEMPORARY CONDITION. IF ACCESS TO HEAD OF WALL IS RESTRICTED THEN THE TEMPORARY PROPPING NEEDS TO BE AS CLOSE TO THE HEAD AS POSSIBLE.

Do not scale from this drawing.

	EXISTING STRUCTURE TO BE RETAINED
	EXISTING STRUCTURE TO BE REMOVED
	NEW REINFORCED CONCRETE
	NEW MASS CONCRETE
	NEW PRECAST CONCRETE
	NEW REINFORCED WATER RESISTANT CONCRETE
	NEW STRUCTURAL STEELWORK
	NEW LOAD BEARING BLOCKWORK
	NEW LOAD BEARING BRICKWORK
	NEW LOAD BEARING TIMBER
	NEW CROSS LAMINATED TIMBER
	NEW GLAZING
	STRUCTURE HIDDEN

REF	LENGTH	DEPTH	HEIGHT
P1	440 mm	215 mm	225 mm
P2	450 mm	100 mm	225 mm
P3	650 mm	225 mm	225 mm
P4	450 mm	140 mm	225 mm

COLUMN REF	COLUMN SIZE
SC1	SHS140x140x5
SC2	UC152x152x23
SC3	SHS100x100x5
SC6	RHS200x100x10

BEAM REF	BEAM SIZE
SB1	UB203x102x23
SB2	UB203x133x30
SB3	UC203x203x46
SB4	UC203x203x60
SB5	UC203x203x71
SB7	UC152x152x23
SB8	UC152x152x37
SB9	50x12mm PLATE (S275)
SB10	SHS140x140x5
SB13	UC203x203x86
SB14	RHS300x200x12.5
SB15	RHS200x150x12.5

elliottwood engineering
a better society

Project no.	Originator	Zone	Level	Type	Role	drg
2210419-EWP-ZZ-ZZ-DR-S-20						




-

3. Axial Tie forces may be considered as a separate connection load case. All other specified connection forces are to be considered acting simultaneously
4. Slip resistant moment connections to be provided at all moment connections
5. Provide minimum 4no. M16 bolts per connection
6. Provide minimum grade 8.8 bolts
7. Provide minimum 6mm fillet welds

This drawing is to be read in conjunction with all relevant architects, engineers and specialists drawings and specifications.

Do not scale from this drawing.

LEGEND

	EXISTING STRUCTURE TO BE RETAINED
	EXISTING STRUCTURE TO BE REMOVED
	NEW REINFORCED CONCRETE
	NEW MASS CONCRETE
	NEW PRECAST CONCRETE
	NEW REINFORCED WATER RESISTANT CONCRETE
	NEW STRUCTURAL STEELWORK
	NEW LOAD BEARING BLOCKWORK
	NEW LOAD BEARING BRICKWORK
	NEW LOAD BEARING TIMBER
	NEW CROSS LAMINATED TIMBER
	NEW GLAZING
	STRUCTURE HIDDEN

PADSTONE SCHEDULE

REF	LENGTH	DEPTH	HEIGHT
P1	440 mm	215 mm	225 mm
P2	450 mm	100 mm	225 mm
P3	650 mm	225 mm	225 mm
P4	450 mm	140 mm	225 mm

STEELWORK COLUMN SCHEDULE

COLUMN REF	COLUMN SIZE
SC1	SHS140x140x5
SC2	UC152x152x23
SC3	SHS100x100x5
SC6	RHS200x100x10

STEELWORK BEAM SCHEDULE

BEAM REF	BEAM SIZE
SB1	UB203x102x23
SB2	UB203x133x30
SB3	UC203x203x46
SB4	UC203x203x60
SB5	UC203x203x71
SB7	UC152x152x23
SB8	UC152x152x37
SB9	50x12mm PLATE (S275)
SB10	SHS140x140x5
SB13	UC203x203x86
SB14	RHS300x200x12.5
SB15	RHS200x150x12.5

C2	14.10.24	MC	AS	SSL Updated
C1	02.09.24	NL	DB	Issued for Construction
P3	14.09.23	PW	IG	Revised as clouded
P2	01.09.23	PW	IG	Tender Issue
P1	24.08.23	PW	IG	Tender Issue
rev	date	by	chk	description

elliottwood | engineering
a better society

Elliott Wood Partnership Ltd
Central London • Wimbledon • Nottingham
Consulting Structural and Civil Engineers
(020) 7499 5888 • elliottwood.co.uk

Project
12 Pilgrim's Lane
Hampstead, London

Drawing title
Proposed Section C-C

Scale (s)	Date	Drawn
1:50@ A1:	October 2024	MC
Drawing status	Status	Revision
Construction	A5	C2
Project no.	Originator	Zone
2210419-EWP-ZZ-ZZ-DR-S-2002		

