



Location Plan  
Scale: NTS

0 0.5 1 2m

Note:

Existing Brickwork to be carefully assessed prior to undertaking works. To identify:  
- Serious decay of mortar joints and bricks  
- Spalling of brick faces due to frost action, particularly on parapets or chimney stacks, or the use of a cement mortar rather than a lime-based one  
- Cracking or bulging of brickwork

Brickwork Repair  
- Brickwork replacement to be minimised with loose broken or previously poorly repaired brickwork carefully pieced in with brick to match surrounding in terms of size, texture, colour, inclusions and variety. Bond to be carefully maintained along with pointing gauge in terms of bed and perpend dimensions

Pointing Repair  
- Loose, poor quality or inappropriate pointing to be carefully removed ensuring the integrity of existing brickwork arrises and faces. Once raked out to the extent required, likely c 20mm, to be repointed with a premixed lime mortar to match representative local sample in terms of colour, texture, aggregate, consistency and depth. Once semi cured pointing to be rough brushed and washed to expose aggregate and leaving the pointing semi recessed

Once brickwork and pointing repairs are complete facades to be carefully and gently doff cleaned to ensure that excessive dirt or other buildups are reduced but patination of age is maintained.

Rev Date Details By

Charlton Brown  
Architecture & Interiors

10-11 St Georges Mews, Primrose Hill, London, NW1 8XE

Telephone +44(0)20 7794 1234  
Email office@charltonbrown.com  
Website www.charltonbrown.com

Client

Redfrog Property

Project

Frognal Rise House

Drawing Title

Proposed North East Elevation

Date 17/04/2025 Drawn IS Checked KM

Scale  
1:50@A1 / 1:100@A3

Issue Status

Planning

Project Number 23029 Drawing Number PL-00-304 Revision