Schedule of Works Key:	13 01.300.13 - Existing windows to Sicilian House lightwell to be removed and blocked up		
to be read in conjunction with schedule 383(SL) Listed Building Consent Schedule of Works, section 01, sheet 300	14 01.300.14 - Existing non original lift overrun to be carefully taken down to allow new core to be installed, then rebuilt as existing		
01.300.01 - Existing windows and door of 21 Southampton Row's fire escape stairs to service corridor elevation to be removed and structural openings to be enlarged down to slab level	15 01.300.15 - New structural opening to be formed in existing lit motor room wall for new ductwork route		
02 01.300.02 - Existing windows to existing fire escape to be removed	16 01.300.16 - New structural opening to be formed in masonry wall, allow for new lintel to structural engineer's specification		
01.300.03 - Existing windows to Southampton Row to be retained, existing paintwork to be stripped back ready for redecoretion, plus existing secondary glazing to be removed	17 01.300.17 - Allow for existing lobby to be removed		
04 01.300.04 - Existing first floor windows to Southampton Row to be removed completely	18 01.300.18 - Existing internal plant to be removed completely		
05 01.300.05 - Existing shopfront glazing to be removed at ground floor level	19 01.300.19 - Allow for masonry wall to be removed		
06 01.300.06 - Existing non original fire escape door and window to be removed from existing structural openings	20 01.300.20 - Existing sanitaryware + assosciated fixtures, fittings and pipework to be removed completely		
07 01.300.07 - Existing dormers to be retained and repaired as required	21 01.300.21 - Existing feature round steel columns to be retained and protected throughout works		
08 01.300.08 - Lift car, associated services and shaft to be removed entirely	22 01.300.22 - Non original partitions forming services risers to be demolished entirely		
09 01.300.09 - Existing key clamp handrail guarding to be removed and stored for reuse	23 01.300.23 - Existing concrete slabs to be removed within stair core		
10 01.300.10 - Existing rooftop plant to be removed completely	24 01.300.24 - New structural opening to be formed in masonry wall, allow for new lintel to structural engineer's specification to provide new ventilation route		
11 01.300.11 - Existing roof finishes to 21 Southampton Row to be removed back to plywood deck	25 01.300.25 - Allow for existing gates to be carefully removed and retained for re-installation to suit new arrangement with addition of pass gate.		
01.300.12 - Existing windows to 21 Southampton Row lightwell to be retained, existing paintwork to be stripped	26 01.300.26 - New opening to be cut into lift motor room roof for new AOV installation		



Key Plan Scale: 1:500

20m

halebrown architects

	All dimensions to be checked on site prior to commencement of any works, and/or preparation of any	Revision
sl	shop drawings.	PL-1
	Sizes of and dimensions to any structural or services elements are indicative only. See structural and service engineers drawings for actual sizes / dimensions.	PL-2
	This drawing to be read in conjunction with all other Architect's drawings, specifications and other Consultants' information.	PL-3
All proprietary systems shown or	All and the state of the state	
	All proprietary systems shown on this drawing are to be installed strictly in accordance with the Manufacturers/Suppliers recommended details.	
	Any discrepancies between information shown on this drawing and any other contract information or	
	manufacturers/suppliers recommendations is to be brought to the attention of the Architect.	

PLANNING

Indicates original fabric to be demolished. Refer to structural engineers

information for extent of structural alterations to indicated areas

Indicates non orignal non structural

Indicates non structural elements that need to be removed / demolished

Indicates areas of structural openings to be carefully created within existing slabs in line with approved risk assessment and approved method statements Indicates areas of internal screed / finishes to be stripped back to bare

structure in line with approved risk assessment and approved method

Indicates areas of external floor finishes to be stripped back in line with approved risk assessment and approved method

Indicates areas where internal screed to be retained, areas will have reduced floor void with new raised access floor

Indicates non original fabric to be

to be installed, then rebuilt as existing.

carefully removed to allow for new core

statements

partitions to be removed

rision Date	Amendment	Date	Project	,	Job Ref.
1 22/07/202		Jan 2021	Vernon House		383
2 01/03/202	Revisions as per agreed amendments	Scale Draw	vn Check Title		
3 07/02/202	Revisions as bubbled	1:100 @A1 KP	DT 21SR - Demolition S	Section 01	
		Status	Client Ref Drwg. no.		Rev.
		PLANNING	EDR 383 (DE) 300		PL-3
		Hale Brown Architect		70 Normington Lane, London, e	SE11 5DP
		T : 020 3735 7442	E: mail@halebrown.com W	V: www.halebrown.com	