

Project Title	St Augustine's Road, 4	
Location:	Repaving works (inc. removing / repaving crossovers)	
Client:		
Correspondence File:		

ESTIMATED/MEASURED BILL OF QUANTITIES

ITEM	DESCRIPTION	QUANTITY	UNIT	SELECTED RATE	TOTAL
200.003	Take up or down and remove to tip off site precast concrete or york stone paving slabs any size type including fiber reinforced up to 65mm thick	330.00	m2		
200.019	Take up or down and set aside for reuse granite flat, edge or standard profile bus boarder kerb	120.00	m		
200.021	Take up or down and remove to tip off site granite flat, edge or standard profile bus boarder kerb	28.00	m		
500.082	Raising the level of any class of cover and frames in the footway, area of cover exceeding 0.1m2 but not exceeding 0.5m2, exceeding 50mm but not exceeding 150mm	5.00	nr		
500.083	Raising the level of any class of cover and frames in the footway, area of covers exceeding 0.5m2 but not exceeding 1.0m2, 50mm or less	5.00	nr		
600.001	Excavation of any material in footways, verges and other pedestrian areas	66.00	m3		
600.012	Disposal of any material.(except class U1B and U2 material)	66.00	m3		
600.021	Completion of commencement level on existing unbound base or sub-base material	330.00	m2		
1100.001	Granite flat kerb 300x200mm, 'fine picked' finish, laid straight or curved exceeding 12 metres radius	28.00	m		
1100.003	Granite edge kerb 150x300mm, 'fine picked' finish, laid straight or curved exceeding 12 metres radius	5.00	m		
1100.031	Remove from set aside area and relay flat granite kerb, laid straight or curved exceeding 12 metres radius	80.00	m		
1100.033	Remove from set aside area and relay edge granite kerb, laid straight or curved exceeding 12 metres radius	40.00	m		
1100.058	65mm thick fibre reinforced Artificial stone paving, any size BS A or B on existing base or base measured separately and sand bedding 30mm thick	330.00	m2		
1100.080	100mm ST1 concrete base in footways	330.00	m2		
				Sub Total	
Officer Fees					
Baxter Increase					
Contingencies					
				GRAND TOTAL	£31,529.09

Produced By:	Costa Kakouratos	Date	30/05/2013
Checked by:	Chris Smith	Date	
Approved by:		Date	
Revision:		Date	

