



John McAslan + Partners therefore accept no liability for the accuracy of this information or its use. All consultants / contractors / sub-contractors should take into account discrepancies that could exist with the base survey data and verify key dimensions on site. Any errors or discrepancies within this drawing are the sole liability of DB Surveys Ltd and should be reported directly to DB Surveys Ltd (01908 584806).

- 01 Structure
- 02 Damp proof membrane
- 03 Scheduled waterproof membrane
- 04 Scheduled render
- 05 Scheduled glass
- 06 scheduled secondary support structure
- 07 Scheduled timber structure
- 08 Scheduled insulation
- 09 Vapour Control Layer
- 10 Insult Mesh
- 11 Scheduled screed
- 12 Scheduled wall lining
- 13 30x30x12 nals steel angle
- 14 Scheduled Insulation
- 15 stainless steel plate with countersunk fixings
- 16 Scheduled 15mm plywood treated to Euro class B
- 17 Scheduled powdercoated angle
- 18 Scheduled tile
- 19 Scheduled fire curtain
- 20 Scheduled steel bracket
- 21 Scheduled plywood sheathing
- 22 Breather Membrane
- 23 Scheduled door
- 24 Underfloor heating
- 25 Scheduled downpipe
- 26 Scheduled blockwork
- 27 Fire resistant connection to glass
- 28 Scheduled stainless steel gulle
- 29 18mm Marine Plywood
- 30 Scheduled stainless steel angle
- 31 Scheduled stainless steel brackets
- 32 Existing Hopper
- 33 Scheduled soffit
- 34 Scheduled render bead
- 35 Vertical timber battens
- 36 Scheduled skirting
- 37 Scheduled rainscreen cladding
- 38 Scheduled ceiling
- 39 Scheduled luminaire
- 40 Packler
- 41 Scheduled floor finish
- 42 Scheduled metal ventilation grille
- 43 Scheduled Handrail
- 44 Stainless steel ventilation grille
- 45 Scheduled glass fin
- 46 Scheduled powdercoated aluminium panel
- 47 Scheduled acoustic panel
- 48 Scheduled steel bracket by curtain wall subcon
- 49 Scheduled windows
- 50 Scheduled acoustic underlery
- 51 Scheduled EPDM
- 52 Silicone sealant
- 53 Scheduled glass balustrade and supporting channel
- 54 Scheduled plasterboard trim
- 55 Dressed timber closer
- 56 Scheduled curtain wall
- 57 Powder coated metal trim
- 58 Lead flashing
- 59 Powdercoated aluminium channel/anglebar
- 60 Scheduled brick
- 61 Scheduled concrete padstone
- 62 Scheduled electric motor driven opening glass unit
- 63 Scheduled rain water drainage system
- 64 Scheduled roof cladding
- 65 Scheduled timber support structure
- 66 Scheduled vapour permeable underlary
- 67 Scheduled timber roofing battens
- 68 Scheduled gutter
- 69 Scheduled insulated metal panel
- 70 Curtain walling and cap
- 71 Scheduled air diffuser
- 72 Scheduled brick slip
- 73 Scheduled intercom system panel
- 74 Knaf Insulcontact and Acoustic Mastic
- 75 Knaf Plasterboard Filler
- 76 Knaf Sealant
- 77 Scheduled Knaf Stud Channel
- 78 25 x 50mm Knaf steel angle
- 79 Knaf Unversal slab RS50
- 80 Knaf Firestall
- 81 Continuous band of Knaf Plasterboard Adhesive
- 82 Knaf Unversal Bracket
- 83 Scheduled Knaf Joint Tape
- 84 Scheduled Arcoflexed Aluminium Panel
- 85 Scheduled dressed full length hardwood padeck
- 86 Scheduled timber plug
- 87 Scheduled timber seat
- 88 Scheduled steel railing
- 89 Scheduled timber panel
- 90 Scheduled glass panel shoe
- 91 Scheduled pre-cast stair
- 92 Scheduled entrance mat
- 93 Scheduled stainless steel trim to plasterboard
- 94 Painted nd box
- 95 Scheduled aluminium support frame
- 96 Scheduled ironmongery
- 97 Scheduled balustr
- 98 Scheduled tiling
- 99 Scheduled floor edge trim
- 100 Scheduled timber batten
- 101 Scheduled timber cladding
- 102 Scheduled lintel
- 103 Scheduled dading
- 104 Scheduled S4x50 Steel tie
- 105 Scheduled bedding/ adhesive
- 106 Beam and Block Structure
- 107 Scheduled Mortar
- 108 Movement Joint
- 109 Scheduled Slip Membrane
- 110 Scheduled concrete tanking fillet
- 111 Scheduled external paving
- 112 Scheduled mastic
- 113 Scheduled Negreene
- 114 Scheduled Timber Joints
- 115 Scheduled Timber
- 116 Scheduled Nosing
- 117 Scheduled Stringer
- 118 Scheduled Handrail
- 119 Scheduled Underlary

Curtain Walling Facade - Atrium 1	
Scale At A1: 1:2	Job Number: 1262
Date: 18.09.2013	Drawing: JL
Drawing Status: Planning	Checked: EG
Drawing Number: 1262-G252-D-AL-060-PL	Revision: /