

Demolition Key:

Line Denotes Removal of Existing Structure

Dash Denotes Removal of Existing Structure

Key:

New partition

Existing structure

Abbreviations:

RVP - Rain Waterpipe
 EX - Existing
 MH - Manhole
 RC - Reinforced Concrete
 SE - Structural Engineer
 PPC - Polyester Powder Coated



Existing non-original aluminium windows and door to be removed

Wall to be demolished where shown hatched to allow for new opening to corner of Northington Street and Kirk Street

Existing floor slab to be lowered by 400mm - refer to Structural Engineers report for details

Approximate level of existing manhole (beyond)

SCHOOL 16 NORTHINGTON STREET NORTHINGTON ST
 EXISTING SECTION AA



SCHOOL 16 NORTHINGTON STREET NORTHINGTON ST
 PROPOSED SECTION AA

REV B 14.06.2013 Issued for Planning
 Revisions bubbled and numbered below:
 1. Proposed hardwood door omitted, wall reinstated. Notes amended

REV A 18.09.2012 Issued for Planning

PLANNING ISSUE

Project No. 12046

Client LK Property Specialist Ltd.

Date June 2013

Scale 1:50@A1, 1:100@A3

Project The Dickens Inn, Northington Street

Drawing Title Existing & Proposed Section AA

Drawing No. P_05 B

Drawn LH Approved RD Signed

Marek Wojciechowski Architects

25 Margaret Street, W10 0EE London, UK

Tel: +44 (0)20 7494 8000

Copyright © Marek Wojciechowski Architects Ltd. 2013

All rights reserved. This drawing shall not be used for any other purpose without the written consent of the author. All dimensions are given in millimeters unless otherwise stated. The drawing shall be read in conjunction with the project brief and any other drawings. The drawing shall be read in conjunction with the project brief and any other drawings. The drawing shall be read in conjunction with the project brief and any other drawings.

0 2m 4m 6m 8m 10m