


5.0 Summary and Conclusion

- 5.1 Paragraph 14 of the NPPF makes clear that "At the heart of the National Planning Policy Framework is a presumption in favour of sustainable development, which should be seen as a golden thread running through both plan-making and decision-taking". This means that development proposals that accord with the development plan should be approved "without delay", or where the development plan is absent, silent or relevant policies are out-of-date, grant permission unless any adverse impacts of doing so would significantly and demonstrably outweigh the benefits or specific policies in the NPPF indicate development should be restricted.
- 5.2 Section 2 of this report has explained the full suite of supporting information that is being submitted with this application. The Energy Statement, although not required for a proposal of this scale, has nevertheless been submitted in order to ensure a robust and comprehensive submission. The reports submitted with this application confirm that the proposal has met all the standards required of it.
- 5.3 Section 3 of this report explains that the delivery of housing is a key challenge faced by the Council and there is clear positive policy support for developing new housing.
- 5.4 Section 4 of this report explains that within this positive context that recognises the importance of delivering housing, the Council also want to see ensure quality design. The site falls within the Fitzjohn's/Netherhall Conservation Area. The associated Conservation Area Statement describes the history and evolution of the Conservation Area and identifies its key characteristics which should inform future development proposals. These characteristics have informed the design of the scheme within the context of local and national policies which make clear that design is not prescriptive.
- 5.5 The Conservation Area Assessment has highlighted that the existing building is of no particular architectural interest and does not merit protection. It was originally a late Victorian house that has been extensively added to and altered so very little remains of the original. It is one of the few buildings that is not identified by the

Conservation Area Statement as a building that "makes a positive contribution" (p29).

- 5.6 The design of the scheme has borne in mind a number of factors identified by the Conservation Area Assessment, including its hidden location, that good quality design does not mean simply replicating existing design, and the importance of vegetation and trees. All these factors have been borne in mind in designing the application proposals. They have resulted in a scheme which officers have indicated during pre-application discussions that they support.
- 5.7 The proposal therefore fully accords with the development plan and so should be granted permission without delay.



Appendix iii
Sustainability
Statement, includ
Code for Sustaina
Homes Statement

prepared by
XCO₂

Sustainability Statement: including Code for Sustainable Homes Statement



Sustainability Statement

92 Fitzjohn's Avenue, Hampstead
For MAKE

February 2013

Page 1 of 10

XCO2 energy

92 Fitzjohn's Avenue, Hampstead, London NW3 6JL
T: +44 (0) 20 7200 1000 | E: info@xco2energy.com | W: www.xco2energy.com

Sustainability Statement



Sustainability Statement

Executive Summary

This report summarises the sustainability performance of the proposed development at 92 Fitzjohn's Avenue, in line with the requirements set out by the London Borough of Camden.

The sustainability statement is issued under two parts:

- General Sustainability Statement
- Code for Sustainable Homes


The first part provides an overview of the site and planning process applicable to any development. The second section details the assessment. The report then demonstrates how the policies have been met to achieve level 4 of the London Planning Guidance (LPG), Sustainability Risk, the whole-life cycle approach has been taken.

The numbers of people affected is 0 as there is no residential or commercial units. The report then demonstrates how the policies have been met to achieve level 4 of the London Planning Guidance (LPG). Sustainability Risk, the whole-life cycle approach has been taken.

The figures below indicates a summary average achieved over Part 1 Building Regulation and Part 2 Building Regulation. The figures are in accordance with Part 1 Building Regulation and Part 2 Building Regulation.

The levels of the report outline the sustainability measures that have been adopted to achieve Level 4 of Sustainable Homes. In Part 4, A summary of the key performance targets for the proposed sustainable development are set out in Part 1 Building Regulation and Part 2 Building Regulation.

The calculation of Code of Sustainable Homes is as follows:



92 Fitzjohn's Avenue




92 E Fitzjohn's Avenue

	Part 1	Part 2	Part 3	Part 4	Part 5
Score	100%	100%	100%	100%	100%
Target	100%	100%	100%	100%	100%
Performance	100%	100%	100%	100%	100%
Design	100%	100%	100%	100%	100%
Delivery	100%	100%	100%	100%	100%
Date	21/02/2012	22/01/2013	15/01/2013	16/02/2013	25/02/2013
Direct Reference	8.250	8.250	8.250	8.250	8.250

92 E Fitzjohn's Avenue

Sustainability Statement: including Code for Sustainable Homes Statement



Sustainability Statement: including Code for Sustainable Homes Statement

The figure is a map of the Lower Fraser River area, spanning from approximately 125°W to 123°W longitude and 49°N to 49.5°N latitude. The map shows the main course of the Fraser River flowing generally westward, with several tributaries joining it from the north and east. Two major urban centers are shown: the City of Vancouver to the west and the City of New Westminster to the east. A legend in the bottom left corner identifies two types of diversion sites:

- Proposed Diversion Sites**: Indicated by solid black dots.
- Existing Diversion Sites**: Indicated by open circles.

Several proposed diversion sites are marked along the main river and its tributaries, particularly in the northern and central reaches. Existing diversion sites are also marked, often near the boundaries of the two cities. An inset map in the bottom right corner shows the location of the study area within the context of British Columbia's coastline and neighboring provinces.

Sustainability Statement: including Code for Sustainable Homes Statement

Sustainability Statement



Code for Sustainable Homes

The Code for Sustainable Homes is the national standard for the design, delivery and operation of sustainable homes. It is a framework for development, it was introduced by the government in April 2011, in association with the Building Research Establishment (BRE) and Construction Industry Research and Innovation Association (CIRIA). The Code covers the sustainability of a development across four categories, along with decking residential.

Although the focus is on new builds, there is now a revised version of the Code for Existing Homes, which is being used in many parts of the UK. In April 2012, a further update was made.

Each standard requires a three-pointed approach to deliver maximum efficiency gains:

- Energy

- Water

- Materials

- Site

- People

- Products

- Services

- Management

<ul

Sustainability Statement: including Code for Sustainable Homes Statement



Sustainability Statement

Subject

- Non-recyclable material space will be allocated for non-recyclable household waste, this will be collected by the Local Authority.
 - Recyclable - A Local Authority collection scheme will be in operation for the collection of recyclable household waste and at least three separate bins will be provided with a total capacity of 30 litres. Each bin will have a capacity of at least 7 litres and be located in the kitchen.

WAS 2 Concentrates Site & Waste Management

The development will minimize the impact of construction waste on the environment through a Site Waste Management Plan (SWMP). This plan will include:

- Local haulers are used wherever possible
- Construction and demolition waste is reduced by pre-planning and waste audits
- Monitoring haulers and hauler haulback methods
- Additional details from the SWMP will be provided when ready.

WALS 5 Composting
A compost bin will be provided at a suitable place
in the garden. The students will learn the
importance of recycling.



03 | [Kontakt](#) | Anmelden



Sustainability Statement

Global Warming Potential (GWP): Global warming potential (GWP) is a measure of how effective a gas is at preventing the package emitted radiation (greenhouse agents used in the reduction of insulation) from a common source of heat with greenhouse gases.

3.2 R&D & innovation
In section 3.1 we outlined how to reduce the release of greenhouse gases. In section 3.2 we will look at how to increase efficiency. Some buildings have water management systems that flow through pipes. These can be replaced by a closed loop system that recycles water and electricity. The opportunities for reduction are numerous and varied.

www.ijerpi.org | ISSN: 2278-5326 | Impact Factor: 5.21



— 295 —



Sustainability Statement

Ecosystem
ECO 1 and 3 Ecological Assessment
The development is located in a developed site
likely to be fully ecological after a reasonable
amount of time will be carried out to confirm this

A longitudinal gradient will be included in the design, starting with riparian features of ecological value having retentive value possible. A drainage grid with a 1.0 m² module spacing will allow channels and also the establishment of part of the road to generate biodiversity on site.

ECDT 8 ecological requirements
A variety of qualified ecologists will be required to
the development. All key requirements remain and
20% of additional requirements to provide
an environmental audit of the area will be carried.



100



Sustainability Statement

Digitized by srujanika@gmail.com

- A Cook for Sustainable Harvests is an environmental art exhibition featuring the proposed drafting at 92 Highbury Avenue, only the largest set by the artist and poet I. M. Cook. This artwork for climate and species loss concentrates on depicting a range of sustainable measures over the life cycle of the exhibition.

Category	Sub-Category	Type of Activity	Number of Participants		Average Age	Age Range
			Male	Female		
Environmental Awareness	Enviro 1: Recycling Education	Workshop	50	75	30	18-35
	Enviro 2: Energy Efficient Home	Workshop	30	45	35	25-45
	Enviro 3: Sustainable Gardening	Workshop	20	30	32	28-42
	Enviro 4: Energy efficient vehicles	Workshop	25	35	35	25-45
	Enviro 5: Environmental advocacy	Workshop	20	30	30	25-40
	Enviro 6: Climate Change	Workshop	15	25	30	25-40
Sustainable Agriculture	Sust Ag 1: Organic Farming Techniques	Workshop	35	50	30	25-40
	Sust Ag 2: Sustainable Irrigation Methods	Workshop	25	35	30	25-40
Health & Well-being	Health 1: Mindfulness and Stress Reduction	Workshop	40	60	35	25-45
	Health 2: Healthy Eating Habits	Workshop	30	45	35	25-40
	Health 3: Exercise and Physical Activity	Workshop	25	35	30	25-40
Community Engagement	Comm 1: Local Community Improvement	Workshop	30	45	35	25-40
	Comm 2: Civic Participation	Workshop	20	30	30	25-40
Digital Literacy	Digital 1: Basic Computer Skills	Workshop	45	60	35	25-40
	Digital 2: Digital Privacy and Security	Workshop	35	50	35	25-40
	Digital 3: Online Safety	Workshop	25	35	30	25-40
	Digital 4: Basic Programming	Workshop	20	30	30	25-40
Financial Management	Finan 1: Budgeting and Financial Planning	Workshop	35	50	35	25-40
	Finan 2: Investment Basics	Workshop	25	35	30	25-40
	Finan 3: Retirement Planning	Workshop	20	30	30	25-40
Personal Development	PerDev 1: Personal Growth	Workshop	30	45	35	25-40
	PerDev 2: Self-care and Well-being	Workshop	25	35	30	25-40
Mental Health Awareness	MH 1: Mental Health Education	Workshop	30	45	35	25-40
	MH 2: Stress Management	Workshop	25	35	30	25-40
	MH 3: Mindfulness and Awareness	Workshop	20	30	30	25-40
Volunteering Opportunities	Volun 1: Local Volunteering Programs	Workshop	35	50	35	25-40
	Volun 2: National Volunteering Week Activities	Workshop	25	35	30	25-40
	Volun 3: Global Volunteering Initiatives	Workshop	20	30	30	25-40
Leadership & Civic Responsibility	Lead 1: Leadership Training	Workshop	30	45	35	25-40
	Lead 2: Civic Engagement	Workshop	25	35	30	25-40
Cultural & Social Inclusion	Cult 1: Cultural Diversity and Inclusion	Workshop	35	50	35	25-40
	Cult 2: Cultural Exchange Programmes	Workshop	25	35	30	25-40
	Cult 3: Cultural Festivals and Events	Workshop	20	30	30	25-40
Elderly Support	Elder 1: Senior Citizens Support Groups	Workshop	30	45	35	25-40
	Elder 2: Senior Citizens Day Care Centres	Workshop	25	35	30	25-40
Disability Support	Disab 1: Disability Awareness	Workshop	35	50	35	25-40
	Disab 2: Disability Rights Advocacy	Workshop	25	35	30	25-40

Appendix iv
Energy Statement

prepared by
XCO2

Energy Statement



Energy Statement

92 Fitzjohn's Avenue, Hampstead
For MAKE

February 2013

XCO Energy

Corporate address: 92 Fitzjohn's Avenue, Hampstead, London NW3 7EP
Telephone: +44 20 7946 0000 • Fax: +44 20 7947 1442
Email: info@xcoenergy.com • Internet: www.xcoenergy.com

Energy Statement



Energy Statement

www.xcoenergy.com

Contents

Executive Summary	3
Introduction	5
Demand Reduction (Be Lean)	6
Heating and Cooling Infrastructure (Be Clean)	8
Renewable Energy (Be Green)	10
Conclusion	20

Abstract
XCO Energy is a local energy company working in the built environment. We are a joint venture comprising a team of professionals and experts with specialist skills from XCO Energy, MAKE, and LIDC, all highly experienced in the built environment.

	Item 1A	Item 1B	Item 2A	Item 2B	Item 3	Item 4
Remarks	(1) a)	(1) b)	(1) c)	(1) d)	(1) e)	(1) f)
Proposed by:	SP	SP	SP	SP	SP	SP
Cross Reference:	R&E	R&E	R&E	R&E	R&E	R&E
Authored by:	R&E	R&E	R&E	R&E	R&E	R&E
Date:	21.02.13	18.02.13	22.02.13	20.02.13	19.02.13	25.02.13
Reviewed by:	SP	SP	SP	SP	SP	SP

92 Fitzjohn's Avenue



92 Fitzjohn's Avenue

Executive Summary

This report assesses the potential energy performance and carbon dioxide emissions of the proposed underground LIDC system. Overall, LIDC is a low-carbon solution to the challenge of a large building located to the east of Hampstead Avenue in Hampstead, to the the London Borough of Camden.

A feasibility study was carried out to demonstrate and a range of options were evaluated for the use of a large building to reduce the carbon dioxide emissions of the system. The options considered include geothermal energy, solar thermal panels, wind turbines, and biomass heating systems, green power, passive solar design, and insulation.

The methodology used to determine the LIDC emissions is as follows: first the London Plant Group also known as LIDC, Ltd., \$240 million and 2000 tonnes of CO₂ per annum. The analysis demonstrated that a second and a third thermal pump would be required to meet the demand. In this case, the third pump would be of the system would reduce a projected 10% increase over the shareholders.

Conclusions
The output of the LIDC system will increase a range of energy efficiency measures including levels of insulation in excess of Building Regulations minimum. The installation of high performance glazing and low energy lighting, the improvements in the heating system, the reduction in fuel oil, and the use of LIDC.

1. Increase renewable energy
The LIDC system will reduce carbon emissions through the adoption of sustainable designs and construction methods.

The output of the LIDC system will increase a range of energy efficiency measures including levels of insulation in excess of Building Regulations minimum. The improvements in the heating system, the reduction in fuel oil, and the use of LIDC.

2. Increase energy efficiency
The system design takes account of the efficient use of energy by providing increased energy generation.


The output of the LIDC system will increase a range of energy efficiency measures including levels of insulation in excess of Building Regulations minimum. The improvements in the heating system, the reduction in fuel oil, and the use of LIDC.

3. Increase the development of energy
To reduce total operating costs, an energy efficiency of 20% will be achieved by the end of 2015. This reduces emissions equivalent to 10,000 tonnes of CO₂ per annum.

In total, the development of energy will reduce CO₂ emissions by 10,000 tonnes of CO₂ per annum. Reducing LIDC to LIDC Building Regulation (2010), the use of a passive single family building.

Energy Statement

Energy Statement



Regulated Carbon Dioxide Emissions From Each Stage of the Energy Hierarchy

	Building Requirements 2010/11 (tonne)	Regulated 1 (tonne)	Unregulated 1 (tonne)
Before	9.1	1.9	
After energy efficiency	6.2	1.4	
After renewables	0.8	0.9	
After combined heat and power	1.7	2.4	



Energy Statement



Introduction

The proposed development is 42 buildings forming a cluster, a number ranging to the total cost of £1 billion. There are 16 apartment blocks, Residential Flats and 34 Apartments, Residential Schools in Horncastle, and in the London Borough of Croydon.

It should be noted that an Energy Statement is not required prior to the start of the proposed development. However, it is required to fully comply with the Sustainability Codebook (PC) where:

- The developer has or is capable of demonstrating that the proposed development will be delivered to a higher than base level of sustainability performance (see below).
- In particular, the proposed development will have been delivered to a higher than base level of sustainability performance (see below).
- The developer has or is capable of demonstrating that the proposed development will be delivered to a higher than base level of sustainability performance (see below).

This document discusses the expected energy performance of the development and explores the techniques and design features that will reduce the energy use and a range of measures of the development. These include energy efficiency measures, renewable sources, vehicles and low carbon vehicle project (this due to the lack of local public transport).

The Sustainability Codebook (PC) requires the proposed development to demonstrate that it will reduce its energy use and a range of measures of the development. These include energy efficiency measures, renewable sources, vehicles and low carbon vehicle project (this due to the lack of local public transport).

- Be lower - Improve the energy efficiency of the building.
- Be lower - Supply as much of the remaining energy requirement with low-carbon technologies such as renewables, heat and power (RHP).
- Be lower - Offset a proportion of the remaining carbon dioxide emissions by using renewable energy sources.

This report refers to the above points addressed.

Carbon Footprint



Carbon Footprint



Energy Statement



Introduction & Background Information

Planning Application

Enhanced Building Code

The proposed development is 42 buildings, a number ranging to the total cost of £1 billion. There are 16 apartment blocks, Residential Flats and 34 Apartments, Residential Schools in Horncastle, and in the London Borough of Croydon.

It should be noted that an Energy Statement is not required prior to the start of the proposed development. However, it is required to fully comply with the Sustainability Codebook (PC) where:

- The developer has or is capable of demonstrating that the proposed development will be delivered to a higher than base level of sustainability performance (see below).
- In particular, the proposed development will have been delivered to a higher than base level of sustainability performance (see below).
- The developer has or is capable of demonstrating that the proposed development will be delivered to a higher than base level of sustainability performance (see below).

This document discusses the expected energy performance of the development and explores the techniques and design features that will reduce the energy use and a range of measures of the development. These include energy efficiency measures, renewable sources, vehicles and low carbon vehicle project (this due to the lack of local public transport).

The Sustainability Codebook (PC) requires the proposed development to demonstrate that it will reduce its energy use and a range of measures of the development. These include energy efficiency measures, renewable sources, vehicles and low carbon vehicle project (this due to the lack of local public transport).


- Be lower - Improve the energy efficiency of the building.
- Be lower - Supply as much of the remaining energy requirement with low-carbon technologies such as renewables, heat and power (RHP).
- Be lower - Offset a proportion of the remaining carbon dioxide emissions by using renewable energy sources.

This report refers to the above points addressed.

Carbon Footprint



Carbon Footprint



Energy Statement



Introduction & Background Information

Planning Application

Enhanced Building Code

The proposed development is 42 buildings, a number ranging to the total cost of £1 billion. There are 16 apartment blocks, Residential Flats and 34 Apartments, Residential Schools in Horncastle, and in the London Borough of Croydon.

It should be noted that an Energy Statement is not required prior to the start of the proposed development. However, it is required to fully comply with the Sustainability Codebook (PC) where:

- The developer has or is capable of demonstrating that the proposed development will be delivered to a higher than base level of sustainability performance (see below).
- In particular, the proposed development will have been delivered to a higher than base level of sustainability performance (see below).
- The developer has or is capable of demonstrating that the proposed development will be delivered to a higher than base level of sustainability performance (see below).

This document discusses the expected energy performance of the development and explores the techniques and design features that will reduce the energy use and a range of measures of the development. These include energy efficiency measures, renewable sources, vehicles and low carbon vehicle project (this due to the lack of local public transport).

The Sustainability Codebook (PC) requires the proposed development to demonstrate that it will reduce its energy use and a range of measures of the development. These include energy efficiency measures, renewable sources, vehicles and low carbon vehicle project (this due to the lack of local public transport).

- Be lower - Improve the energy efficiency of the building.
- Be lower - Supply as much of the remaining energy requirement with low-carbon technologies such as renewables, heat and power (RHP).
- Be lower - Offset a proportion of the remaining carbon dioxide emissions by using renewable energy sources.

This report refers to the above points addressed.

Carbon Footprint



Carbon Footprint



XCO Energy



Energy Statement

Planning Application

Enhanced Building Code

The proposed development is 42 buildings, a number ranging to the total cost of £1 billion. There are 16 apartment blocks, Residential Flats and 34 Apartments, Residential Schools in Horncastle, and in the London Borough of Croydon.

It should be noted that an Energy Statement is not required prior to the start of the proposed development. However, it is required to fully comply with the Sustainability Codebook (PC) where:

- The developer has or is capable of demonstrating that the proposed development will be delivered to a higher than base level of sustainability performance (see below).
- In particular, the proposed development will have been delivered to a higher than base level of sustainability performance (see below).
- The developer has or is capable of demonstrating that the proposed development will be delivered to a higher than base level of sustainability performance (see below).

This document discusses the expected energy performance of the development and explores the techniques and design features that will reduce the energy use and a range of measures of the development. These include energy efficiency measures, renewable sources, vehicles and low carbon vehicle project (this due to the lack of local public transport).

The Sustainability Codebook (PC) requires the proposed development to demonstrate that it will reduce its energy use and a range of measures of the development. These include energy efficiency measures, renewable sources, vehicles and low carbon vehicle project (this due to the lack of local public transport).

- Be lower - Improve the energy efficiency of the building.
- Be lower - Supply as much of the remaining energy requirement with low-carbon technologies such as renewables, heat and power (RHP).
- Be lower - Offset a proportion of the remaining carbon dioxide emissions by using renewable energy sources.

This report refers to the above points addressed.

Carbon Footprint



Carbon Footprint



Energy Statement

Energy Statement

Heating and Cooling Infrastructure (Bio-Clean)


Energy System Scenarios

The energy system for the development has been selected after reviewing the London Plan Decarbonated Energy Horizon by the Energy team. In Phase 1 & 2, future energy systems should be separated in the following way. In Phase 3, the final 15 years will be guided by the London Heating Strategy.

1. Commercial & existing building and cooling infrastructure
2. Site-wide CHP systems
3. External heating

Local supply of heat and power infrastructure includes local, off-network generation systems such as district heating systems and thus, reducing CO₂ emissions.

In a commercial energy system, energy is to come from local, existing utility companies or generated from a central source and distributed via a network to surrounding residents and commercial users.



125 Queen's Avenue image of area surrounding the development

XCO ENERGY

Energy Statement

CO₂ Emissions

The table below shows the regulated and unregulated carbon dioxide emissions for the baseline scenario, as well as the reduced emissions under Local Energy Efficiency and Clean (LEE) measures have been implemented. The table below shows the energy demand for the area surrounding the site. Subject to the rate of projected growth, there would be a high level of higher density where new buildings are being developed or redeveloped near to the development.

CO₂ Emissions Breakdown

	Total	Commercial	Residential	Total
Existing buildings	5.3	3.9	1.2	5.3
After energy efficient reduction	5.0	3.6	1.2	5.0
LEEE + LEE Clean	3.1	2.1	1.0	3.1

	Total	Commercial	Residential	Total
Sandringham energy efficient reduction	2	1.5	0.5	2.0
Sandringham LEE Clean	0.0	0.0	0.0	0.0

125 Queen's Avenue image of area surrounding the development

XCO ENERGY

Energy Statement

Renewable Energy (RE) (Lee)

Once energy demand reductions have been implemented, methods of generating heat and electricity may need to be reviewed.

The renewable technologies to be considered by the developer are:

- Bio-gas
- Photovoltaic panels
- Solar thermal panels
- Geothermal source heat pumps
- Air source heat pumps
- Wind energy

In order to determine the feasibility of the above technologies, their suitability for the site and compatibility with the measures already implemented through the LEE Clean, has been appraised. The technologies deemed suitable are outlined below.

The potential energy and carbon savings achievable from implementation of each of the above renewable technologies were estimated for the proposed dwelling at 125 Queen's Avenue using the Standard SAP software.

It should be noted that the total energy from a combination of renewable sources is unlikely to be identical to the sum of savings from implementation of individual renewables due to the interaction and dependency displayed by the SAP software.

Above, provide, the final system has been used to create a REC (reduction in loss from Central Council authority) figure of 1.11 under Policy S11 of the Carbon Reduction Strategy.

The following section presents the potential savings and feasibility for the renewable technologies considered.

XCO ENERGY

Energy Statement

Photovoltaic Panels - Unshaded


Four types of solar cells available at present are monocrystalline, polycrystalline, thin film and hybrid. Although monocrystalline and hybrid cells are the most expensive, they are also the most efficient. Polycrystalline cells are cheaper but less efficient and thin film cells are only slightly less efficient but have a fraction of the cost of monocrystalline cells and are available at a lower price.

A total of 40% of 15% efficiency (240Wp) solar panels and 20% of 250Wp solar panels have been implemented after 10 years.

The technology and its implementation can be found in the Carbon Reduction Strategy at 92 Queen's Avenue on page 12.



Technology	Efficiency	Cost
Monocrystalline	15%	High
Polycrystalline	14%	Medium
Thin Film	10%	Low
Hybrid	15-20%	Medium-High



92 Queen's Avenue



92 Queen's Avenue



92 Queen's Avenue



92 Queen's Avenue

- The installation of photovoltaic panels when compared to wind turbines.
- Photovoltaic panels can be up to 10 times more expensive than wind turbines.

A total of 40% of 15% efficiency (240Wp) solar panels and 20% of 250Wp solar panels have been implemented after 10 years.

The technology and its implementation can be found in the Carbon Reduction Strategy at 92 Queen's Avenue on page 12.

Energy Statement

Energy Statement

Water Efficiency: Xcel Energy's new water rules will limit water volumes. Xcel Energy has proposed a more efficient water system compared to what is currently in the U.S. Climate Action Plan. It has committed to find alternative sources.

Water Treatment: Xcel Energy's water treatment facility at the plant, the plant will be converted towards the wastewater treatment plant's treated effluent discharge.

Carbon Dioxide Emissions: Xcel Energy's carbon dioxide emissions would be reduced by 10% by 2020. The proposed facility will reduce the total CO₂ emissions by 10% compared to the current facility. It is anticipated that the proposed facility will reduce the total CO₂ emissions by 10% compared to the current facility.

Total Emissions	Current Total Emissions
Carbon Dioxide	1,000,000 lbs/yr
Greenhouse Gases	431,700 lbs/yr
Other greenhouse gases	169,000 lbs/yr
Electricity sales (kWh)	1,151,000,000 kWh
Heat rate factor	100 lbs/kWh
Total carbon dioxide	4,371,000 lbs/yr
Estimated gas energy content (Btu)	1,150,000,000 Btu/yr
State Environmental Agency	0.72 lbs/gal
Reduced CO ₂ savings	0.6 lbs/gal
Reduced CO ₂ savings (Btu)	1,000,000 Btu/yr
Total CO ₂ savings (lbs/yr)	137,000 lbs/yr
Reduced CO ₂ savings (Btu)	100,000 Btu/yr
Total CO ₂ savings (lbs/yr)	137,000 lbs/yr



For areas where mass control

XCO ENERGY

Energy Statement

Water Efficiency: A local press operating throughout facilities of the U.S. and other countries will implement actions.

The technology will be implemented as part of the new facility strategy and will help reduce the proposed facility's impact on the local stream area, in accordance with the following goals:

The proposed facility will reduce the total CO₂ emissions by 10% compared to the current facility. It is anticipated that the proposed facility will reduce the total CO₂ emissions by 10% compared to the current facility.



XCO ENERGY

Energy Statement

Ground Heating / Cooling: A local solar system, located on the building roof, would be funded for initial public, which is a high priority customer. And system requires less maintenance than other sources, such as geothermal systems, which would require significant capital investment.

The technology will be implemented as part of the new facility strategy and will help reduce the proposed facility's impact on the local stream area, in accordance with the following goals:

A ground source system is considered not to be the primary concern for the development given the amount of space required for proper storage. The local area is limited in terms of available space and there are no plans to develop further outlets or locally sourced sites would be undertaken. There will also be concern over local air quality with the increase in NO_x emissions as a result of burning wood as fuel.



Example of ground source heat

XCO ENERGY

Energy Statement

Ground Source Heat Pump / Mat & Carpet:

Due to the building's location, utilizing the ground source heat pump system for heating systems for the proposed building would include a series of ground heatpumps, where a liquid carrier is transported past them through the system, absorbing heat from the ground as it releases the heat via an in-ground heat pump provided in the building.

A ground source heat pump system would allow for air heating through a coil in the building's duct system, which will provide heating.

A GSP system used to meet Xcel Energy's heating demand, which is 100% of 12 megawatts is the development's required CO₂ reduction. This calculation indicates that 5.6 x 10⁶ kWh of heat will be needed to meet the space heating demand and liquid heat must be used.



Example of ground source heat

Category	Value
Carbon Intensity of Electricity	0.517 kgCO ₂ /kWh
Proportion of Space Heating met by GSP	3.1%
Typical Rate of CO ₂ reduction met by GSP	23.4%
Energy used by GSP	26,057 kWh/yr
Total CO ₂ savings	0.6 t CO ₂
Regulated Grid CO ₂ emissions	0.0 t CO ₂
Total CO ₂ reductions	0.6 t CO ₂
Total CO ₂ reductions	0.6 t CO ₂
Regulated Grid CO ₂ reductions	0.0 t CO ₂
Total CO ₂ reductions	0.6 t CO ₂

Energy Statement

Energy Statement

A 5-Spoke Wind Project has proposed to install 12 turbines on the same footprint as current solar panels (50.8% Hume Street) using heat exchangers buried in the ground, heat is extracted from the ground and sent up.

A benefit of this is that the system produces passive heating and hot water through electronics, thereby reducing the need for a gas connection to the dwelling.

The efficiency of heat pumps is very much dependent on the temperature of the air entering the heat source and the space required to be heated. As a result ASHPs tend to have a higher COP than GSHPs. This is due to the lower levels of energy that GSHPs require to move the air around to the relatively stable ground temperature. In low temperatures GSHPs extract and extract air from the earth. The more efficient the system,

	CO2 Total
CO2 Total	2.5
Carbon intensity of electricity	0.53t CO2/kWh
Proportion of Solar Heating over by ASHP	80.3%
Proportion of Heat Pumps over GSHP	19.6%



925 Elizabeth Avenue

XCO ENERGY

Energy Statement

The use of ASHPs as a low carbon technology for this development would result in a required CO2 savings of 3.4%.

In addition, the following tables may be of interest:

- ASHPs are considered to be the lowest cost option for the space heating and hot water needs of the dwelling.
- heat of noise may also be of concern at night, as the development is nearby residential.

For this reason, it should be noted that the following table shows the highest potential savings if the dwelling requires the lowest wind speeds and the grid. These values are derived from the E100 scenario and used in the Carbon Footprint Model (available here). The average annual wind speed at a proposed height of 10m above the building canopy is estimated to be 5.6m/s. In reality however, different buildings, trees, and speech are required to give a more accurate figure.

Due to the spacing required between wind turbines, one turbine would be placed on the roof. The two tables below outline 2 types for two different wind turbines, a 50kW and a 100kW unit.

The results show that the required CO2 savings for both options are 3.2% and 3.0% for the 25kW and 60kW turbines respectively.

	Total Output
Average wind speed assumed	3.5 m/s
Number of turbines	1
Wind Speed (m/s)	5.6
Electricity offset by turbine	3.58t CO2/kWh
Carbon intensity of offset electricity	0.329 t CO2/kWh
Total CO2 savings	0.6 t CO2
Regulated Clean CO2 emissions	0.6 t CO2
Total Clean CO2 emissions	1.2 t CO2
% Regulated CO2 reduction	50.0%
% Unregulated CO2 reduction	33.3%
% Total CO2 reduction	33.3%

925 Elizabeth Avenue

XCO ENERGY

Energy Statement

Energy Use & Savings

Due to the visual impact of wind turbines and the actions which are likely to occur to reduce the visual impact, regulations are expected to be a more feasible option for us to mitigate concerns about the proposed dwelling than wind turbines.

The table below summarises the benefits from reduced electricity generation and reduced emissions.

The table below summarises the benefits from reduced electricity generation and reduced emissions.

The table below summarises the benefits from reduced electricity generation and reduced emissions. It includes a PV and solar thermal array which are the most feasible low cost carbon energy strategy for the proposed dwelling at 92 Elizabeth Avenue. Therefore, these two technologies will be implemented at the proposed dwelling as part of the Site Green Strategy.

The table below summarises the benefits from reduced electricity generation and reduced emissions.

XCO ENERGY

Energy Statement


It can be seen that compared to 2010 a 2.7% reduction in tonne CO2 and a 2.9% reduction in regulated emissions and a 29.3% reduction in carbon dioxide emissions of the total

CO2 Emissions
The table below shows the regulated and unregulated carbon dioxide reductions for the baseline scenario and the emissions after the low-carbon green measures has been implemented.

CO2 Emissions Breakdown

Carbon dioxide emissions	Current	Proposed
Buildings	0.1	1.9
After energy efficiency	0.8	2.9
After energy efficiency + supply	0.4	3.0
After renewables	1.1	3.4

Carbon dioxide emissions	Current	Proposed
Savings from energy efficiency - buildings	2.2	2.2
Savings from energy efficiency + supply	0.0	0.0
Savings from renewable energy	3.1	6.2
Total Cumulative Savings	5.4	8.4



925 Elizabeth Avenue



921 Elizabeth Avenue



921 Elizabeth Avenue

Energy Statement

Conclusion

The measured CO₂ emissions for the residential development at 97 Clapton Avenue have increased by 59.5% over energy efficiency measures and renovations are taken across the tenements, it is 23% ahead of target in the London Plan 2011, although it is a significant part of a project of the year.



Task 6 review - more renewable energy
Task 6 review - energy analysis of a number of
renovations to buildings for their suitability for the
site. The analysis included biomass heating systems,
gas boilers, heat pumps, biomass fuel storage,
photovoltaics, solar thermal and solar panels.

The task of the bottom of the page states the
development which is being developed has
The refurbishment is to be completed by the end
of the year.

In accordance with the strategy, the development
will incorporate a range of energy efficiency
measures including efficient lighting, levels of
insulation, spray insulation, double glazing and
the installation of high performance glazing.
The proposed urban measures savings from the
refurbishment will be compared to a standard
building kept to a Level Part Building Regulation
(LBR).


Task 6 review - supply security definition
The building clearly showed that no direct heating
networks currently exist within close proximity of
the site. It would not be feasible at this point in time
to include a network. A high efficiency gas boiler
will be required to supply space heating and hot
water to the building.

Regulated Carbon Dioxide Savings from Each Stage of the Energy Hierarchy

Regulated CO ₂ Savings	%	Total CO ₂ Savings
Tower CO ₂ Savings	%	%
Savings from energy efficient insulation	2.2	24.6%
Savings from LBR	0.0	0.0%
Savings from renewable energy	2.1	24.2%
Total CO ₂ Savings	4.3	41.8%

21 October 2014





Appendix v
Sunlight, Daylight
Overshadowing
Assessment

prepared by
XCO2

Daylight, Sunlight, Overshadowing Assessment



Daylight, Sunlight, Overshadowing Assessment

92 Fitzjohn's Avenue, Hampstead

For MARE

February 2012

Ref: Ref: 00000000000000000000000000000000

About us:
XCO₂ Energy are a low carbon consultancy working in the built environment. We are a multi-disciplinary company consisting of both architects and engineers, with specialists including CIBSE chartered consultants, Code for Sustainable Homes, Green Homes and BREMA assessors and LEED accredited professionals.

XCO₂ energy

or: www.xco2energy.com | e: marelle@xco2energy.com
t: +44(0)20 700 6666 | f: +44(0)20 7113 9920
Unit 101 | 56-58 What Road | London | N11 7SL

Contents

Executive Summary	3
Introduction	5
Site	6
Methodology	7
Daylight Assessment	9
Sunlight Assessment	20
Overshadowing of Open Spaces	23
Conclusion	23



Executive Summary

All permanent opaque building elements proposed development have been set out for daylight and sunlight analysis at the site location. The report includes the results of the analysis to the relevant planning guidance, primarily assessing the daylight and sunlight regime to an adjoining building.

The methodology set out in this report is in accordance with BREEAM's 'Site Layout Planning Daylight and Sunlight A Guide to Good Practice' by P. Ellerbeck (2011) which is detailed as part of the recommended by the BREEAM standard.

tends to one of the surrounding buildings on site.

All permanent opaque building elements proposed development have been set out for daylight and sunlight analysis at the site location. The report includes the results of the analysis to the relevant planning guidance, primarily assessing the daylight and sunlight regime to an adjoining building.

Daylight Assessment

A number of existing buildings adjacent to the proposed development have been set out for daylight and sunlight analysis. Twenty-one (21) windows were assessed in further detail.

The following assessments were carried out:

- As open as possible
- Vertical Sky Component
- Max Daylight

Analysis showed that 5 of the modelled buildings had VSCs greater than 27% and VSCs remaining windows were over 20%

existing windows.

The proposed development will result in no changes to existing windows to the rear windows. These windows will receive no daylight, which set out in the BREEAM document.

Daylight Assessment Overview

Building ID	Exterior U-value W/m ² K	Window U-value W/m ² K	Window Area m ²	Open Area m ²	Open Area m ²	VSC > 27%	VSC > 20%
Hawthorne 1	6	1.6	0.700000	0.00	0.00	0	0
Gardenfield 1	n	2-12	0.100000	0.00	0.00	0	0
North Berwick Mansard Garden Flat	4	15-15	0.1000	0.00	0.00	0	0
St Anthony's	6	1.2-2.4	0.000000	0.00	0.00	0	0
Fitzjohn's Primary	1	20-26	0.000000	0.00	0.00	0	0
Total	24	0.000000	0.000000	0.000000	0.000000	0	0

v2 Fitzjohn's Avenue



v2 Fitzjohn's Avenue



Daylight, Sunlight, Overshadowing Assessment

Daylight Assessment
The structure of the surrounding buildings represent Annual and Winter Probable Sunlight Hours analysis in order to determine the impact. The proposed development will have no significant effect on the buildings surrounding the site and will continue to contribute to meet all sunlight targets outlined in the BREEAM document.

Summary
The proposed development at 92 Egerton Avenue passes the BREEAM Daylight and Sunlight trials for the surrounding existing buildings and the sunlight hours test for surrounding open spaces.

Overshadowing of Open Spaces
An open space is a place considered to be the responsibility of a person for the sunlight they receive on it. Malls, all the parking spaces provided pass the BREEAM test with the development's shadow cast from the building in place.

Daylight Assessment Overview

	Function	Number of Windows	Window Area (%)	2D Daylight Time Factor	Probable Sunlight Hours Test	Daylight hours tested against BREEAM
Non-residential	0	3	34%	0.74	No	No
Residential	0	2	21%	0.74	No	No
TOTAL		5	25%	0.74	No	No

Overshadowing Overview

Open Space	Proportion of Proposed Building Shadow Received	Probability of Receiving Shade from Nearest Building	Daylight Hours Tested against BREEAM
Open Ground	0% (No shadow)	0% (No shade)	0% (No shade)
Total	0%	0%	0%
TOTAL	0	0%	0%

92 Egerton Avenue



92 Egerton Avenue



92 Egerton Avenue

92 Egerton Avenue

Introduction

This report is intended to assess the daylight, sunlight and overshadowing impacts of the proposed development at 92 Egerton Avenue on the existing buildings surrounding the site.

The approach is based on the BREEAM "Daylight Planning for surfaces and windows" guidance practice (BREEAM 2011), which is generally accepted as good practice by Town and Country Planning authorities.

It should be noted that although the numerical values stated in the BREEAM provide surface to shadow, distances and glazing off-sets, these are purely arbitrary and may vary depending on context. On an urban site, for example, may often represent an average value, and other compared to has no definitive value, as it is a very large or odd one - here in other is available.

Site

The proposed development at 92 Egerton Avenue is a single dwelling to be located one of Egerton Avenue, between 90 Egerton Avenue and 94 Egerton Avenue. It is a two-storey detached house with a garage and a conservatory to the right of the main entrance.

The property was at the present time an unoccupied plot and there were no other buildings, trees or structures nearby. Between 90 Egerton Avenue and 94 Egerton Avenue, the proposed development is the only building in the area.

The approach of the location and proximity to other buildings is as follows:


Methodology

Daylight
The following methodology was used to carry out the daylight assessments. The methodology is based on the guidelines set out in the BREEAM "Daylight Planning for Surfaces and Sunlight" Guide (BREEAM 2011).


1. Daylight to surrounding buildings
A plan diagram of 25m x 25m from the proposed development to the nearest building. If a new development is in close proximity to the plan, the initial daylight levels of the surrounding buildings may be reduced. When an assessment of the 25 degree plane occurs, a more detailed assessment involving the Vertical Sky Component of the internal window would need to be carried out.

2. Albedoste Vertical Sky Component
The Vertical Sky Component is the ratio of the direct Daylight received by the window to the total amount of light received through the window. Albedo refers to reflectance and is the amount of light reflected by a surface to the sky. If the VSC is less than 27%, it is considered to be greater than the VSC, which is the minimum level of VSC that would result in the day light.

3. Relative Vertical Sky Component
Each source of daylighting can still be termed a VSC, even if under 27% of direct daylight. The difference, that is the VSC for the internal room, would need to be determined.



Daylight, Sunlight, Overshadowing Assessment



Daylight Assessment

XCO ENERGY

Daylight Assessment

XCO ENERGY

Daylight Assessment

XCO ENERGY

Daylight Assessment

X

Handshake Report

This report provides an overview of the work carried out in assessing the site. It highlights the key findings and recommendations made at the planning application stage, and the proposed development. The letter of advice to the local authority has been abridged to be comparable to simple performance daylight and sunlight, and therefore is not regarded to be incorporated in the assessment.



Handshake Output VSC Results

Orientation	Latitude	Longitude	BRE Standard VSC	Design Value	Design Value (%)
1	51.500000	0.000000	100	100	100
2	50.833333	0.000000	100	100	100
3	50.000000	0.000000	100	100	100
4	49.166667	0.000000	100	100	100
5	48.333333	0.000000	100	100	100
6	47.500000	0.000000	100	100	100

Results Summary

No. Number of windows	No. Number of windows (%)
1	100 (100%)
2	100 (100%)
3	100 (100%)
4	100 (100%)
5	100 (100%)
6	100 (100%)

Daylight, Sunlight, Overshadowing Assessment

Daylight Assessment

Greenhill Building

The residential units are situated to the north of the site. The building is oriented east-west and has two levels of living floors above the roof and basement. These floors have separate daylight and lighting systems. Three windows all day one 25 degree window.



Greenhill Building VSC Results

Building	Number of windows	Number of doors	Number of skylights	Number of glass walls
1	1	0	0	0
2	1	0	0	0
3	1	0	0	0
4	1	0	0	0
5	1	0	0	0
6	1	0	0	0
7	1	0	0	0
8	1	0	0	0
9	1	0	0	0
10	1	0	0	0

Building Summary

Number of windows	Number of doors	Number of skylights	Number of glass walls
1	0	0	0
2	0	0	0
3	0	0	0
4	0	0	0
5	0	0	0
6	0	0	0
7	0	0	0
8	0	0	0
9	0	0	0
10	0	0	0

Greenhill Building



Daylight Assessment

Northbridge House Senior School

The Northbridge House Senior School is located east of the proposed development. The school is a large, single-story building with a gabled roof. It has several windows and doors on the exterior walls.



3D digital rendering of building (not to scale)

Northbridge House Senior School VSC Results

Daylight Assessment

Northbridge House Senior School

The Northbridge House Senior School is located east of the proposed development. The school is a large, single-story building with a gabled roof. It has several windows and doors on the exterior walls.

It was determined that all of the Z-doppler line is considered for all 4 windows at the front of the VSC test with active VSC codes of greater than 1% in at least 30% of the Z-doppler line.

The unused development will have no significant impact on daytime or nighttime activities.



Northbridge House Senior School VSC Results

Building	Number of windows	Number of doors	Number of skylights	Number of glass walls
1	28	0	0	0
2	27	0	0	0
3	27	0	0	0
4	27	0	0	0

Result Summary

Number of windows	Number of doors	Number of skylights	Number of glass walls
1	0	0	0
2	0	0	0
3	0	0	0
4	0	0	0


Unused Development



Daylight Assessment

Northbridge House Senior School

The Northbridge House Senior School is located east of the proposed development. The school is a large, single-story building with a gabled roof. It has several windows and doors on the exterior walls.



3D digital rendering of building (not to scale)

Northbridge House Senior School VSC Results



3D digital rendering of building (not to scale)



Northbridge House Senior School



Daylight, Sunlight, Overshadowing Assessment

Daylight Assessment

XCO
ENERGY

M. Oakley's Preparatory School:
All building's exterior surfaces of the
developed site. New windows were specified
by developer. All areas except to gain the 25
degree view and thermal access (other buildings are
required).



51. M. Oakley's Preparatory School

Building	View Direction	UCL Daylight (%)	SDC (%)	Result
17	North	100	0	Pass
18	North	100	0	Pass
19	North	100	0	Pass
20	North	100	0	Pass
21	North	100	0	Pass
22	North	100	0	Pass
23	North	100	0	Pass
24	North	100	0	Pass
25	North	100	0	Pass

Result Summary

Number of windows	Pass
Windows that pass the 25 degree view	5
Windows that pass the 25 degree view and have a UCL > 60% and SDC < 20%	5
Windows that pass the 25 degree view and have a UCL > 60% and SDC < 10%	0
Windows that do not meet the 25 degree view requirement	0

52. M. Oakley's Preparatory School Results

Daylight Assessment

XCO
ENERGY



52. M. Oakley's Preparatory School Results

Building	View Direction	UCL Daylight (%)	SDC (%)	Result
17	North	100	0	Pass
18	North	100	0	Pass
19	North	100	0	Pass
20	North	100	0	Pass
21	North	100	0	Pass
22	North	100	0	Pass
23	North	100	0	Pass
24	North	100	0	Pass
25	North	100	0	Pass

Result Summary

Number of windows	Pass
Windows that pass the 25 degree view	5
Windows that pass the 25 degree view and have a UCL > 60% and SDC < 20%	5
Windows that pass the 25 degree view and have a UCL > 60% and SDC < 10%	0
Windows that do not meet the 25 degree view requirement	0


52. M. Oakley's Preparatory School Results

Daylight Assessment

XCO
ENERGY

Fletchit's Primary School:
This primary school is located west and east of the
planned development. Four buildings have the
development footprint. The proposed development
will bring 10 higher SDC levels to these buildings.
The western building on the western building has
less windows to be a corridor. It also has an
overshadowing requirement for this reason, the corridor can
not have windows indicated in the footprint.

Although the angle remaining from these three
windows is less than the 25 degree limit due to their
proximity to the existing boundary, no additional



Fletchit's Primary School Results

Building	View Direction	UCL Daylight (%)	SDC (%)	Result
26	North	34.4	20.0	Fail
27	North	34.4	20.0	Fail
28	North	34.4	20.0	Fail

Result Summary


Number of windows	Pass
Windows that pass the 25 degree view	0
Windows that pass the 25 degree view and have a UCL > 60% and SDC < 20%	0
Windows that pass the 25 degree view and have a UCL > 60% and SDC < 10%	0
Windows that do not meet the 25 degree view requirement	0

53. Fletchit's Primary School Results

Daylight Assessment

XCO
ENERGY

Fletchit's Primary School:
Daylight analysis results show that all windows will
achieve the required UCL > 60% and SDC < 20%
overshadowing requirement. The proposed development
will bring 10 higher SDC levels to these buildings.
All these have an improvement in daylight when
due to the proposed building being located further
away from Fletchit's Primary School and has a lesser
height than the existing building on site.



53. Fletchit's Primary School Results

53. Fletchit's Primary School Results

54. Fletchit's Primary School Results

54. Fletchit's Primary School Results

55. Fletchit's Primary School Results

55. Fletchit's Primary School Results

Daylight, Sunlight, Overshadowing Assessment

Sunlight Assessment

Sunlight Assessment

Existing Buildings

Surrounding buildings which have south facing windows 27 degrees or less from the north direction on the building they receive. Therefore, the only buildings screened by this overshadowing are Henderson Court and Greenwell.

Annual and Winter Sunlight Hour Results

Henderson Court and Greenwell APM4 and WPS4 Results

Neighboring Building	# of Windows Facing South	Average Sunlight Hours (AM4 & WPS4)	Winter Sunlight Hours (WPS4)	Summer Sunlight Hours (AM4)
1. Henderson Court	1	100% (AM4)	-	-
2. Greenwell	10	100% (AM4)	-	-
3. St. Anthony's School	10	100% (AM4)	-	-
4. St. Anthony's School	10	100% (AM4)	-	-
5. St. Anthony's School	10	100% (AM4)	-	-
6. Henderson Court	1	100% (AM4)	-	-
7. Greenwell	1	100% (AM4)	-	-
8. Greenwell	1	100% (AM4)	-	-
9. Greenwell	1	100% (AM4)	-	-
10. Greenwell	1	100% (AM4)	-	-
11. Greenwell	1	100% (AM4)	-	-
12. Greenwell	1	100% (AM4)	-	-

Summary of Results:
All of the existing south facing windows pass the 20 degree test. The existing south facing facades will therefore continue to receive an adequate amount of sunlight with the new development in place.



Sunlight Assessment

Sunlight Assessment

Overshadowing of Open Spaces

An assessment of the sunlight levels of the surrounding open spaces was undertaken. Five of these open spaces were shaded as being in close proximity to the development at 10% Average Average.

CNS Evidence suggests that the 10% shade is not a concern for the sunny spaces to the south of the Greenwell Building. Sunlight hours received by a very small part of the space (just 10%) is not affected by the proposed development which is not considered to be significant.

The table below quantifies the results of the sunlight assessment for the sunny spaces to the south of the Greenwell Building. Sunlight hours received by a very small part of the space (just 10%) is not affected by the proposed development which is not considered to be significant.

The table below shows that at least half of each of the sunny areas receive more than 2 hours of sunlight. A location to the west does not require

an average of 2 hours of sunlight to open space to

function well with existing buildings in use and for the proposed development in place. It can be seen that all spaces pass the 10% test.

The table below quantifies the results of the sunlight assessment for the sunny spaces to the south of the Greenwell Building. Sunlight hours received by a very small part of the space (just 10%) is not affected by the proposed development which is not considered to be significant.

Overshadowing Results

Neighboring Space	Area of shading (sq ft)	Area of shading (sq ft) divided by area of shading in the sunny space (sq ft)	Percentage of sunny space shaded
1. St. Anthony's Prep School	100%	0.0001 (sq ft)	0.0001%
2. St. Anthony's School	100%	0.0001 (sq ft)	0.0001%
3. King Philip Elementary School	100%	0.0001 (sq ft)	0.0001%
4. Greenwell	100%	0.0001 (sq ft)	0.0001%
5. Henderson Court	50%	0.0001 (sq ft)	0.0001%

Neighboring Space

21

Sunlight Assessment

Sunlight Assessment

Conclusion

Daylight Assessment

Light Shading Assessment

Open Space Assessment

Conclusion

Sunlight Assessment

Sunlight Assessment



Conclusion

Daylight Assessment

Light Shading Assessment

Open Space Assessment

Conclusion



Sunlight Assessment

Sunlight Assessment

Conclusion

Daylight Assessment

Light Shading Assessment

Open Space Assessment

Conclusion

Sunlight Assessment

Sunlight Assessment

Conclusion

Daylight Assessment

Light Shading Assessment

Open Space Assessment

Conclusion

The results from the existing building analysis indicate that the creation of daylight will be adequate. This is due to the following findings:

- All windows receive 100% shade for the 20 degree rule.
- 3 of the 7 windows which failed 20 degree light shading are located in the surrounding buildings. These spaces showed that the shading was minimal and did not affect the surrounding buildings.
- The remaining 4 of the 7 windows which fail a 20% shade test are receiving 2 hours of sunlight or less than 10% of its previous value.

The proposed development will have no significant impact on daylight to open space.

The proposed development will have no significant impact on daylight to open space.

The proposed development will have no significant impact on daylight to open space.

The proposed development will have no significant impact on daylight to open space.

The proposed development will have no significant impact on daylight to open space.

The proposed development will have no significant impact on daylight to open space.

The proposed development will have no significant impact on daylight to open space.

The proposed development will have no significant impact on daylight to open space.

The proposed development will have no significant impact on daylight to open space.

The proposed development will have no significant impact on daylight to open space.

The proposed development will have no significant impact on daylight to open space.

Building	Number of Windows	Number of Windows Failed	20 Degree Light Shading Rule	VSC > 75% of Previous Value
Henderson Ct	5	1	100% (AM4)	n/a
Greenwell	6	2	100% (AM4)	n/a
North Star Warne Senior School	4	3	100% (AM4)	21.50/23.2
St. Anthony's	7	1	100% (AM4)	n/a
Elmwood Primary	1	0	100% (AM4)	n/a
TOTAL	26	5	100% (AM4)	21.50/23.2

Daylight Assessment Overview

Building	Number of Windows	Number of Windows Failed	20 Degree Light Shading Rule	VSC > 75% of Previous Value
Henderson Ct	5	1	100% (AM4)	n/a
Greenwell	6	2	100% (AM4)	n/a
TOTAL	12	3	100% (AM4)	n/a

Open Space Assessment Overview

Opening Space	Proportion of Open Space	Value Received 2 Hours of Sunshine on 21 March (24 hours later than 1 March)	Area Received 2 Hours of Sunshine on 21 March (24 hours later than 1 March)
TOTAL	5	1	1

Open Space Assessment Overview

Conclusion

Daylight Assessment

Light Shading Assessment

Open Space Assessment

Conclusion

Daylight Assessment

Light Shading Assessment

Open Space Assessment

Conclusion

Daylight Assessment

Light Shading Assessment

Open Space Assessment

Conclusion

Daylight Assessment

Light Shading Assessment

Open Space Assessment

Conclusion

Daylight Assessment

Light Shading Assessment

Open Space Assessment


Conclusion

Daylight Assessment

Light Shading Assessment

Open Space Assessment

Conclusion



Appendix vi
Tree survey,
Arboricultural Impa
Assessment and
Arboricultural Me
Statement

prepared by
Landmark Trees

Arboricultural impact assessment report



ARBORICULTURAL IMPACT ASSESSMENT REPORT

92 Finsbury Avenue

London

NW1 8NP

REPORT PREPARED FOR

Ms Robert Lord and Mr John Webster

92 Finsbury Avenue

London

NW1 8NP

REPORT PREPARED BY

Adam Holt

MSc ARB MSc For Arbor A MCIOB C Law

Ref: TSS029/2013/001
Date: 29 February 2013

This document and contents of this report are for the exclusive use of the client. It may not be sold, lent, hired out or divulged to any third party, not directly involved in the subject matter without Landmark Trees' written consent.

Web: www.landmarktrees.co.uk
e-mail: r@landmarktrees.co.uk
Landmark Trees, 92 Finsbury Avenue, London NW1 8NP
Telephone: 020 7278 0500 | Fax: 020 7278 0501 | Email: r@landmarktrees.co.uk
Proprietary Rights: Design Layout © Landmark Trees. All rights reserved. May not be copied.

Section	Content	Page No
1.0	SUMMARY	5
2.0	INTRODUCTION	7
2.1	Terms of Reference	7
2.2	Drawings Supplied	7
2.3	Scope of Survey	8
2.4	Survey Data	8
2.5	CABINATIONS	9
2.6	Site Description	9
2.7	Select Trees	10
2.8	Planning Status	11
2.9	DEVELOPMENT CONSTRAINTS	12
2.10	Primary Constraints	12
2.11	Secondary Constraints	14
3.0	ARBORICULTURAL IMPACTS	16
3.5	DISCUSSION	21
4.1	Rating of Primary Impacts	21
4.2	Rating of Secondary Impacts	22
4.3	Magnitude of Impacts	23
5.0	CONCLUSION	25
6.0	RECOMMENDATIONS	26
8.0	REFERENCE	27

APPENDICES

APPENDIX 1	Survey Data	26
APPENDIX 2	Recommended Tree Removal (existing trees)	30
APPENDIX 3	Recommended Tree Translocation to Existing Development	37
APPENDIX 4	Tree Constraints Plan	41
APPENDIX 5	Impact Assessment / Tree Protection Plan	43

Comments

This report is primarily an arboricultural report. Verbal comments relating to matters relating to structures or soil data may appear. Any comment that is expressed should be treated as a general observation from an appropriately qualified professional viewpoint. Such points are usually to be interpreted within the body of the report.

It is not a full safety survey of sub-surface tree assessments. These should be carried out further to the extent that they would be required. Where matters of this concern with a safety appraisal, relevant advice or a separate tree risk or safety appraisal of the report.

Indirect or tree impacts of development of the site, unassociated with trees close to people and property. What has an elevation under a larger tree. Unplanned living timber may also be generated; these will be referred to in community risk.

Any damage will be limited to effects on the size of the trees concerned but no damage to the benefits. It will be appraised, and deserved to be avoided by the client that the formal recommendation for all management of trees will be justified by the cost-benefit analysis for the amount of tree work that could remove the risk of tree related damage.

Prior to the commencement of any tree work, an ecological assessment of species that may persist to species which are situated around a tree, hedges and boundaries etc. is affected.

Arboricultural Impact Assessment Report Ref: TSS029/2013/001
Prepared for Ms Robert Lord and Mr John Webster, 92 Finsbury Avenue, London NW1 8NP
Prepared by Adam Holt, r@landmarktrees.co.uk (London) Ltd. MCIOB

Arboricultural impact assessment report

Type Committee & Protection Standard

Block:	Mr. Hachim Lant and wife	Case Ref:	18/204 JAPA AX 12
Local Authority:	LB Croydon	Date:	20/ Feb/ Apr 2013
Area:	12/ East Croydon London SE16 3EP		
Proposal: New residential development with landscaping & drainage			
Report Checklist			
Area cultural & environmental concerns	Y/N	Y/N	Y/N
Area of ecological importance	Y	Tree removal proposed	Y
Geographical Survey	Y	Geographical Survey	Y
Carriageway area	Y	Carriageway area	Y
Tree protection plan	N/A		
Tree Constraints Plan	Y	(any trees in full or partial vegetation)	
Tree protection plan required	Y		
Site Legend			
Site Info	Y	Date 07/07/13	
Areas at Risk	Y	Access	2/4 Partial/Holes
Areas affected by development	Y	Off site impacts	2/4
Tree replacement proposed	Y	3/4 areas affected by development	2/4
Tree replacement proposed	Y	5/6 areas will be indirectly affected by development	Y
Trees with the potential to be affected			
Trees likely to be felled for landscape improvement: 7/9, 30, 42, 43, 44			
Trees likely to be felled for landscape improvement scheme: 7/13, 7/20			
Others: Low RPA impacts to 1/2, 3/12			
Overall: 17/25 for access			
Site tree risk: 4/6 impacts to 1/2, category B and 1/6 category C			
Proposed mitigation: 18/21 - 13/14/15/16/17			
Comments:			
7/21 recommended setting for 2013 arboricultural practice			
Recommendations			
1. Propose a mid-July tree felling of impacts to trees 1/2, 7/13/20, 3/12.			
2. If proposed, has sufficient mitigation for tree loss?			
3. Propose to provide a detailed tree protection plan for the remaining trees.			
4. Propose to provide a detailed tree protection plan for the remaining trees.			
5. The proposed set-back is significant for heritage to native tree species.			
6. Further evaluation of the proposed re-planting.			

EFZ-Grid Pauschal-Ansatz
EFZ-Grid Pauschal-Ansatz
Risiko-Zuschlagskalkulation
Risiko-Zuschlagskalkulation
RISIKO-ZD-Faktor ist wieder zu denken: dominante und subordinante - Risiken unterscheiden

Afterwards at Duxbury & Amherst and Roxbury. (In [3] Duxbury, Roxbury, and Roxbury 100-100)
Presented by Mr. Charles Lupton and Mr. Wm. H. Duxbury. "F. F. Duxbury's Roxbury 100C-101"
Presented by James Miller in Roxbury. (See 28 Roxbury Street, Roxbury 100-101)

1. Introduction

አዲስ-በደንብ ከመ-መው የዕድል ቀናት ስርጓሜ ተመሪያ ነው፡፡ ይህም በአዲስ አበባ ተመሪያ
ችውን እንደሚከተሉት የሚከተሉት የሚመለከት ማረጋገጫ መሆኑን የሚያሳይ ነው፡፡

- 2.1 INTRODUCTION

2.1.1 URGUMA "REES" were acted by Ms Rachael Lee and Mr John Trevor. To provide summary and an encyclopedic rapid instrument of proposals for the title I am from 52 Executive Avenue, London NW1 6AP. The report is to accompany a planning application.

2.1.2 The document is for the development of the small plot of land. Aligned by the continuation of a residential dwelling with a listed landscaping strategy. The design proposes an environment which designs streets and areas around the new residence and the ground floor garage. This report will assess the impact on trees and tree constraints highlighted in our survey. Although the subjects were known at the time of the survey, Landmark Tree evidence is taken as one being within three of a herpetological survey whenever possible, with the overall plan returning this duration.

2.1.3 I am a Registered Consultant and Fellow of the Arboricultural Association and a Chartered Forester with a Masters Degree in Arboriculture and 23 years experience of the landscaping industry, educated by the Forestry Commission and postgraduate development and Advisory Service. I am a LR Registered Arborist (arborist) in single tree joint expert witness cases. I also am Chartered of the U.K. & Regional Plant Appraisal Committee, being asked to provide environmental clauses of plantations in structures.

22 *Grammatical*

- 2.2.1 The drainage required by the client and related work by Leadtech needs to be formulated at our survey stage and meeting with Surveyor 11/2005
Planned - APR 2010

Arboricultural impact assessment report

2.3 Project summary

As Arborist Tree (L1) arboricultural consultant, Atkins has surveyed the trees on site on 17th August 2012, recording relevant qualitative data in order to assess their suitability for retention and their contribution to the site in accordance with British Standards 8007:2012 Trees in relation to design, demolition and development - recommendations (BS8007:2012).

The survey of the site, the soils and any other factors is of a preliminary nature. The trees were assessed on the basis of the Yewel Tree Assessment method developed by Marples and Brink (The Code Language of Trees, 2nd, pocket Projects for Arboriculture No. 4, 1994). It has not taken any account for species and the trees have not peaked but recorded from ground level.

The survey does not cover the arrangements that may be required to accommodate for the removal or retention of on-ground trees.

2.4 Survey details & recent history

2.4.1 Detailed records of historical trees are given in the Survey Schedule in Appendix 1 to 7(a) report.

2.4.2 A site plan showing the surveyed trees, details of the survey findings / topographic survey is provided in Appendix 4.

2.4.3 This plan also serves as the Tree Constraints Plan for the Residential Reconstruction Protection Areas (RPA) tree controls and space constraints (from BS8007:2012 Chapter 6.1). These constraints are then mapped on site onto the client's plans to create an Arboricultural Impact Assessment Plan in Appendix 5. General information and description follow below.

3.0 OBSERVATIONS

3.1 Site description



Fig 1a: Aerial view of the site

- 3.1.1 The site is informally bounded principally by roads, though adjacent, private or land that have been brought under the same ownership by the client. The last plot comprises the existing house and garden at 32 Highgate Avenue, which forms a detached two-storey brick built property, which was internally remodelled post-war, recently altered and retaining the late Victorian habit to remove all traces of the original. It is arranged over a multi-level ground and first floor with a dormer window above. It has a good sized front door and wider garden.
- 3.1.2 The ground plot is our south east streetside area to the North Edge House corner school which has no rights to requirements. This is currently divided from the developing plot by a high wall. The constraint site is situated within the Hampstead Woods district of the London Borough of Camden (Highgate Woods).
- 3.1.3 Access is currently provided by access to a private roadway running from Highgate's Avenue to the site, under joint ownership with O'Brien's Office.
- 3.1.4 In terms of the British Chamber of Surveyors, the site overlies the Chalcots Formation, fine grained yellow/orange clay (plan extract below). At the southern end of the London Clay there is a intrusion between the clay and the London Claybank Park above (between o and e). Within the Nagle area the material is sand, no generally highly stoniferous clay o to stony permeable sandy clay interbedded with bone over clay. Such lighter plastic soils are prone to movement, subsidence and erosion.
- 3.1.5 Obviously, the older kinds of soil types are not as clearly defined on the ground to or plan and have to be assessed differently. Further sources remain the relevant experts in the specific soil properties can be sought as necessary.

3.1.6 They soils are prone to compaction during development with damage to tree structures potentially having a massive impact on tree health. The design of infrastructure non-problematic tree spaces and who need to talk with construction substance risk. Further advice from the relevant experts on the specific soil properties can be sought as necessary.




Figure 1: Screenshot from the DCLG Landscaping & Sustainable Design tool

3.2 Detailed trees

- 3.2.1 There are 45 trees surveyed on or around the site, of which 9 are 'B' category ('Inherently Quality'), 2 are 'C' category ('Inherently Poor Quality'), 24 'C' category ('Low Quality'), 6 are 'C' (Poorly Applicable for Protection) and 17 category ('Unsuitable for Retention').
- 3.2.2 In terms of age distribution there is a wide spread from young to mature, with the majority of the trees being semi or early mature.

- 3.2.3 Surveyed trees 1 to 6, 21-23 (and beside path 5) are in decay and present within the grounds of Headstone Court. To these trees, a notable nearby one, who undertake 'they consist a series of these broadleaves, predominantly maple, with appearance such as very present trees 12-23 stand on or near the eastern boundary of the site remaining among its row, is tree 12, a monopodial quality, 1m in dia, radius spreading and rounded crown of c7m average. The remaining trees on the bank of the site are underdeveloped and unknown.

3.2.4 Tree 24 is a prominent lym ball, situated immediately to the rear (west) of the dwelling. 27-45 stand to the west of the garage beyond a 9m wall. This is a mixed quality group and will be of concern during initial contact. a 41-43 44-45 & 46. Tree 4, 36 stand directly to the north, within an adjoining property. Tree 27 is more distant within the group, being a 1m tall, very small & non-committed specimen.

3.2.5 The surveyed trees and considerable anomaly to the developed urban area. Tree 27-33 provide a suitable screening to Headstone Court to the north and trees 12-23, 34 & 37 (as equally) follow the western boundary.

3.2.6 See Appendix 7 for detail of surveyed trees.

3.3 Planning Status

- 3.3.1 We are not aware of the existence of any Tree Preservation Orders (TPOs) but understand new plots within the Egerton & Hallward Conservation Area (hereafter 'Egerton') which will affect the subject trees. It is a strict offence to prune damage > half their radial projection from the local authority.
- 3.3.2 Further investigations can be made on request at time allows, for dialogue with the authority (LS Council).

Arboricultural impact
assessment report

5.0 Table 1: Arboricultural Impact Assessment

(Impacts assessed prior to mitigation and rated with reference to From Matheny & Cork (1998))

B.S. Cat.											Hide irrelevant		Show All Trees	
											Ref: T38/92FJA/AIA/01c			
Tree No.	Species	Impact	Tree / RPA Affected	Age	Growth Vitality	Species Tolerance	Impact on Tree Rating	Impact on Site Rating	Mitigation					
B 3	Maple, Norway	Pruning/brown lfts to facilitate access	m N/A %	Matue	Normal	Moderate	Low	N/A	Remedial tree surgery (see Rec. Works)					
B 10	Yew, Common	Pruning/brown lfts to facilitate access	m N/A %	Early Matue	Normal	Good	Low	N/A	Remedial tree surgery (see Rec. Works)					
B 12	Sycamore	Drive Construction within RPA Boundary fence in RPA Parking within honeydew	16.5 m ² N/A % 10.48 %	Matue	Normal	Moderate	Low	N/A	No-dig construction Crown-lft for access Boundary wall secured with min-piles					
C 13	Holly	Felled to Facilitate Landscaping Scheme	m N/A %	Early Matue	Normal	N/A	N/A	Low	New planting accordance with a landscape strategy					
C 14	Cherry, Wild (Gean)	Felled to Facilitate Landscaping Scheme	m N/A %	Young	Normal	N/A	N/A	Low	New planting accordance with a landscape strategy					
C 15	Rosin, variety	Felled to Facilitate Landscaping Scheme	m N/A %	Young	Normal	N/A	N/A	Low	New planting accordance with a landscape strategy					

5.0 Table 1: Arboricultural Impact Assessment

(Impacts assessed prior to mitigation and rated with reference to From Matheny & Cork (1998))

B.S. Cat.											Hide irrelevant		Show All	
											Ref: T38/92FJA			
Tree No.	Species	Impact	Tree / RPA Affected	Age	Growth Vitality	Species Tolerance	Impact on Tree Rating	Impact on Site Rating	Mitigation					
C 16	Amelanchier ssp	Felled to Facilitate Landscaping Scheme	m N/A %	Young	Normal	N/A	N/A	Low	New planting w/ a landscape					
C 17	Ceanothus	Felled to Facilitate Landscaping Scheme	m N/A %	Mature	Moderate	N/A	N/A	Low	New planting w/ a landscape					
C 18	Liquet	Felled to Facilitate Landscaping Scheme	m N/A %	Semi-mature	Normal	N/A	N/A	Low	New planting w/ a landscape					
C 19/20	Priet	Felled to Facilitate Landscaping Scheme	m N/A %	Early Matue	Normal	N/A	N/A	Low	New planting w/ a landscape					
C 21	Coloneaster	Felled to Facilitate Landscaping Scheme	m N/A %	Early Matue	Normal	N/A	N/A	Low	New planting w/ a landscape					
C 22	Magnolia (M grandiflora)	Felled to Facilitate Landscaping Scheme	m N/A %	Semi-mature	Normal	N/A	N/A	Low	New planting w/ a landscape					

Arboricultural impact assessment report

5.0 Table 1: Arboricultural Impact Assessment

(Impacts assessed prior to mitigation and rated with reference to From Matheny & Cork (1998))

B.S. Cat											Tree No.	Species	Impact	Tree / RPA Affected	Age	Growth Vitality	Species Tolerance	Impact on Tree Rating	Impact on Site Rating	Mitigation
C	23	Clive	Felled to Facilitate Landscaping Scheme	m ² Semi-mature N/A %	Normal	N/A	N/A	N/A	Low	New planting accordance with a landscape strategy										
C	25	Cherry, Autumn Flowering	Felled to Facilitate Development	m ² Young N/A %	Normal	N/A	N/A	N/A	Low	New planting accordance with a landscape strategy										
B	29	Sycamore	50m ² GF (less existing 11m ²) 20.4% Building Construction within Canopy	30 m ² 20.4 %	Mature	Normal	Moderate	Medium	N/A	Low-invasive foundation design Low-invasive root design										
C	30	Holly variegated	Ground floor building: 7m ²	7 m ² 10.48 %	Mature	Normal	Good	Low	N/A	Low-invasive foundation design										
Cu	31	Willow, Sallow	Pruning/crown lifts to facilitate access.	m ² N/A %	Semi-mature	Normal	Moderate/good	Low	N/A	Remedial tree surgery (see Rec Works)										
B	34	Sycamore	Demolition of existing house	m ² N/A %	Mature	Normal	Moderate	Positive	N/A	Poor/no impact on RPA where built development removed with care										

5.0 Table 1: Arboricultural Impact Assessment

(Impacts assessed prior to mitigation and rated with reference to From Matheny & Cork (1998))

B.S. Cat											Tree No.	Species	Impact	Tree / RPA Affected	Age	Growth Vitality	Species Tolerance	Impact on Tree Rating	Impact on Site Rating	Mitigation
C	35	Cypress, Lawson variety	Felled to Facilitate Development	m ² N/A %	Early Mature	Normal	N/A	N/A	Low	New planting accc with a landscape										
C	36	Cypress, Lawson variety	Felled to Facilitate Development	m ² N/A %	Early Mature	Normal	N/A	N/A	Low	New planting accc with a landscape										
B	37	Sycamore	LGF steps 16m ² additional RPA impact (19%) OF construction 14m ² , but ex. garage demo=1.8m ²	16 m ² 15.18 %	Early Mature	Normal	Moderate	Low	N/A	Pre-emptive root f of terms of LGF th Gym to be cantrip All roots swept to										
Cu	40	Elder	Felled to Facilitate Development	m ² N/A %	Mature	Poor	N/A	N/A	Low	New planting accc with a landscape										
C	41	Cherry	Felled for good arboricultural practice	m ² N/A %	Semi-mature	Dead	N/A	N/A	N/A	New planting accc with a landscape										
C	42	Cedar (C deodara)	Felled to Facilitate Development	m ² N/A %	Young	Normal	N/A	N/A	Low	New planting accc with a landscape										

Arboricultural impact assessment report

5.0 Table 1: Arboricultural Impact Assessment

(Impacts assessed prior to mitigation and rated with reference to from Matheny & Cork (1998))

[Filter by Impact](#) [Show All Trees](#)

Ref: TSS/925/AAIA/01c

B.S. Cat.	Tree No.	Species	Impact	Time / RPA Affected	Age	Growth Vitality	Species Tolerance	Impact on Tree Rating	Impact on Site Rating	Mitigation
CA	43	Elder	Felled to Facilitate Development	m Mature	N/A	Moderate	N/A	N/A	Low	New planting accordance with a landscape strategy
CA	44	Cherry, Wild (Giant)	Felled to Facilitate Development	m' Semi-mature	N/A %	Moderate	N/A	N/A	Low	New planting accordance with a landscape strategy

21

6.0 DISCUSSION

E.1 Catalog of Primary Impacts

E.1.1 The principal primary impacts on the our site proposals are the removal of 2 trees. The 2 trees removed to widen existing paths, their removal will have little arboricultural impact. 10 further impacts (T1 - T20) will be listed and assessed with good quality tree inventory or site ecology low quality ($< 1\%$ Category). We understand that landscape mitigation will be provided in the Design and Assess Statement.

E.1.2 The impacts we retained, retained paths, have complex mitigation. Mitigation requirements of the trees after RPA 1 of T20-120 and T173 by 20% (20% 10% area, respectively). Further retaining structures from the development are required with T12 RPA 6 by 93%. The impacts to T20 and T30 could suffer in existing populated location, where root activity is likely to have been limited. Stability issues in T20 occur with rising tree stumps. Thus, the current RPA impacts are likely to be low given sufficient site investigation and mitigation. Similarly, potential above ground impacts of buildings upon removal of T20 & T30 have been resolved through design and pathway. The need to facilitate access along the existing route shared with St Annes school should also require some further pruning crown lifting of T3, T10 and T12. If tree quality below T21 which overhangs the site by 1-2m would deteriorate to be cut back in the scenario to facilitate construction.

E.1.3 The principle of RPA 1 are retained & established within RPA 2012/2017 and characteristics of source obscuring. National Joint Utilities Guidance 10 (v1.4 1995) (DfES 2012) HLG introduced the 1/2 diameter Preservative Zone for repeated working and Protected Zone at a universal 1m from the base of the tree. RPA's are frequently calculated with the HLG Preservative Zone when they clearly correlate with the HLG Preservative Zone.

An RPA 1 requirement of 120% of RPA 1 will be considered as the impact, given the conservative references to 20% RPA reduction and proposed safety factors with BS6849-2012 and other authors references to healthy trees tolerating up to 30-50% root tolerance (Colas, Helland, and Wilson in GLH 2003).

E.1.4 The trees in question are healthy specimen of species with a good resistance to development impacts, and quite capable of tolerating slight low root impacts.

E.1.5 In practice 50% roots can potentially be removed with little problems and 30% or 40% roots removed, evaluated. The degree of root loss will seriously disrupt growth and often lead to tree decline. In terms of root, 1/2 diameter root areas with high importance of root system rather than what the context is published science, planning should not be solely concerned by a approach that assumes the root system treated. For most it is not a 50% planning the mitigation the probability of the LCF calculations is 1/20.

E.2 Rating of Secondary Impacts

E.2.1 Secondary impacts of post-development junctions between the new standards and carriageway are generally improved through densification. The current carriageway 2 metres (approximately T20 & T3). The junctions now marginally closer in off the tree however, due to the new 2m ground clearance (T4), which is to the benefit of the public the principle canopy participation already occurs.

E.3 Mitigation of Impacts

E.3.1 All trees and vehicles mitigate in diameter 1m should retain surface roughness outside the 1m shaded run-in a temporary surface designed to protect the underlying soil (BS 7500). The carriageway should proceed forward in a full open fashion. E.3.2 Surface within the RPA of trees, existing T20 and T31, can be filled with c by a mechanical operator again staying away from the tree. Careful densification structures (bulldozes and bulldozer) and re-planting with soft earthworks, structural design will also reduce and impact.

E.3.2 In terms of mitigation, the LCP (located one week) will shear plane adjacent to T20-120 impacted by the road to avoid further cutting through the RPA. Closer to T173, tree plug earthworks would be 1/2-diameter and root traced by hand to depth wider 200mm/100mm excavation.

E.3.3 The GL earthworks would employ the reverse design with earthworks located to the left of the road above 120% RPA and the right below T20 & T3. Gentle earthworks will use continuous root cut to reduce debris at the site determined by soil characteristics, again under structural reinforcement. The original trenching would also be mitigated, using a low-pressure foundation design.

Arboricultural impact assessment report

23

1.3.4 Oneway/awayward rethinking about Plan 6 & 7.12 will need to refine or refine upon the existing site case without overlooking the surrounding habitat and species. Tree paving needs to be less permeable than paving and therefore a permeable surface / tree section is to be employed. A permeable paving system would be built up in the RFA using 'drilled' construction techniques such as a 'reinforced' permeable system with soil then applied to the substrate. The finished section is likely to be 150mm above ground. Depending on final specification, which will need to be factored into the overall footprint size levels. The current construction system uses a temporary hard surface (e.g. road) which can be used for the areas during construction and the surface material required on completion of construction.

1.3.5 The matured canopy improvements will be planted with trees between 10-15cm diameter of lower height, over 10m apart, including a 3-4m ground clearance and planting design distances. This is likely to be achieved by the use of the British tree planter (TTS and ST 4, either costs £17 of £23m (c. 2.5%) as further recommended for TTS).

1.3.6 Landscape opportunities can be exploited with regular tree pruning and branch traps on the following basis (Figure 5 below). The shading impacts have been further mitigated in building design, with the provision of multiple shaded walkways and shades of roof layout. The landscape impact of trees will still be dealt with by the landscape principles. Landscape principles will be present in the Design and Assess Document, which will ensure that the Category C trees removed for landscape enhancement (TTS & 2.2) will be replaced with higher quality trees.




Figure 5. A shaded area is shown where shade is to be introduced in 2.2m wide ground.

Adult of age limit (Category 1) under Plan 12 which is limited to 1m²/DPF
Report for Site Ref: 12/01/2012 Date: 21/07/2012 Author: L. Foster - 1002/BP
Prepared for: Balfour Beatty Construction Ltd (Balfour Beatty Construction Ltd) BP
Prepared by: Adult Unit of Landscape Team 22 (Balfour Beatty) Ltd (Balfour Beatty) BP

7.0 CONCLUSION

- 7.1 The potential impacts of development are all relatively low in terms of both quality of trees (assessed at 0.00% SPA achievement) or threat to tree health.
- 7.2 The full potential of the impacts can be mitigated through design and proactivity measures. These measures have been elaborated in our Method Statement (TTS_027_A, AMS_024) in further support of the planning application.
- 7.3 The species affected are generally tolerant of disturbance / common reactors and the retained trees are generally in good health and capable of withstanding these reduced impacts.
- 7.4 The trees that are recommended for felling are of little individual significance, such that their loss is not likely to affect the visual character of the area. The replacement planting is distance 7, the Design & Assess Statement for the garden and the rest of the area developed.
- 7.5 Therefore, the processes will not have any significant impact on wider the retained trees & wider biodiversity.

24

24

8.0 RECOMMENDATIONS

8.1 Specific Recommendations

- 8.1.1 Tree works recommendations are found in Appendices 2 & 3 to this report. Any tree removals or fellings recommended within this report should only be carried out with local authority consent / STAA1 or equivalent.
- 8.1.2 Escalation and mitigation projects will in the RPA's of trees identified in Table 1 grow, and need to be carried out by method statements specifying mitigation measures. Upgraded in part 4.2 areas must be assessed and prioritised as developed. Annex 1b/2/3 plantations have been produced in our Method Statement (TTS_027_A, AMS_024) as further support of the planning application.
- 8.1.3 Replace the listed trees with suitable equivalent species and under careful best practice in conforming to the planting requirements with the following:
 - BS 3308:1980 Arbovitae Spp.
 - BS EN 1634:1998 Incorporating Semiaquatic Trees, Part 1
 - BS 2236:1995 Cultivation and Planting of Trees in the Alkaline and Saline Areas, Cologen
 - As 1338:1999 General Principles for the Planting of Trees in the Urban Environment

- BS 3308:1980 Arbovitae Spp.
- BS EN 1634:1998 Incorporating Semiaquatic Trees, Part 1
- BS 2236:1995 Cultivation and Planting of Trees in the Alkaline and Saline Areas, Cologen
- As 1338:1999 General Principles for the Planting of Trees in the Urban Environment

25

9.0 REFERENCES

- Bureau J & Harrison G 1993 Streets By Trees, A Practical Manual 2nd Ed, AAUS Further Study
- Built Services Institute 2012 Trees & Buildings in Design, Guidance for Construction & Recommended DS 5027 2012/HG0 London
- Cavers for Ecology & Hygiene 2006 Tree Roots in the Built Environment HNSC London
- Fidell P 1989 Planning for New Trees Landscape Design, July Project issue
- International Society of Arboriculture (ISA) 1994 The Landscape Sector Round ICA Chicago IL USA
- Landscape D 1993 Research for Adults Trees 4.2 Principles of Tree Hazard Assessment and Management HNSC London
- Lawton, J & Clark J K 1926 Trade and Development, A Technical Guide to Application of Trees during Land Development B&A, Champaign Illinois USA
- Mazzoni C & Simola H 1997 Research for Adults Trees 2.2 The Body Language of Trees, HNSC London
- Monk P 2000 Trees: Their History, Cambridge University Press, Cambridge
- Pritchard J & Baskett M 2001 Trees in the Urban Landscape: Site Assessment Design and Installation J Wiley & Sons Inc., USA
- Urban Tree Management Trust 2012 Planning Manual London, HNSC BP Report for: Balfour Beatty Construction Ltd (Balfour Beatty) Ltd (Balfour Beatty) BP Prepared by: Adult Unit of Landscape Team 22 (Balfour Beatty) Ltd (Balfour Beatty) BP
- Urban Tree Management Trust 2012 Planning Manual London, HNSC BP Report for: Balfour Beatty Construction Ltd (Balfour Beatty) Ltd (Balfour Beatty) BP Prepared by: Adult Unit of Landscape Team 22 (Balfour Beatty) Ltd (Balfour Beatty) BP

Appendix 1. Tree schedule

APPENDIX 1											
TREE INVENTORY - A tree by Guidance											
DBH - Stem dia: is the diameter of the trunk at 1.5m above ground level at the point of the greatest resistance to the wood incision boundary											
Class/Cultur: refers to the heritage classifications in Section 4.5 BS6837:2012 and concerning the site index: 1. High Quality (+) (Green) 2. Moderate Quality (0) (Blue) 3. Low Quality (-) (Grey) 4. Unsuitable for Retention (-) (Red)											

landmark Trees Ltd
Tel: 020 7851 4544

BS5837 Tree Constraints Survey Schedule

Page

Site: 92 Fitzjohn's Avenue, London NW3 6NP
Date: 7th August 2012

Surveyor(s): James Bell
Ref: TSSW/2/JA/AA/01a

Tree No.	English Name	Height	Crown Spread	Ground Clearance	Age Group	Diam	Protection Radius	Growth Velocity	Structural Condition	Landscape Contribution	B.S. Cat	Sub Cat	Useful Life	Observations
1	Holly	13	2223	4	Mature	420e	12	3.0	Moderate	Fair?	Medium	B	1	20-40 Offsite
2	Sycamore	16	7377	7	Mature	550e	12	6.4	Moderate	Fair?	Medium	B	1	20-40
3	Maple, Norway	17	6884	2	Mature	650e	12	7.8	Normal	Fair?	Medium	B	1	20-40
4	Holly	6	3	2	Early Mature	250e	12	3.0	Normal	Fair?	Low	C	1	20-40 Offsite
5	Birch, Silver	16	4433	5	Early Mature	300e	12	3.6	Moderate	Fair?	Medium	C	1	20-40 Offsite
6	Birch, Silver	16	5	5	Early Mature	350e	12	4.2	Moderate	Fair?	Medium	C	1	20-40 Offsite
7	Birch, Silver	16	5332	5	Early Mature	320e	12	3.8	Moderate	Fair?	Medium	C	1	20-40 Multiple pruning rounds on stem Offsite

Notes:

- 1 Height describes the approximate height of the tree measured in meters from ground level
- 2 The Crown Spread refers to the crown radius in meters from the stem centre and is expressed as an average of HSTW if symmetrical
- 3 Ground Clearance is the height in meters of crown clearance above adjacent ground level
- 4 Stem Diameter is the diameter of the stem measured in millimeters at 1.5m from ground level for single stemmed trees. See section 4.6 for detail of treatment for multi stems
- 5 Protection Radius is a radial distance measured from the trunk centre
- 6 Growth Velocity - Normal growth, Moderate (below normal), Poor (sparse/breaks), Dead (dead or cut tree)
- 7 Structural Condition - Good (no or only minor defects), Fair (moderate defects), Poor - Major defect present
- 8 Landscape Contribution - High (prominent landscape feature), Medium (visible in landscape), Low (secluded among other trees)
- 9 B.S. Cat refers to British Standard 5837:2012 Table 1 and refers to tree group quality and value
- 10 High, 'B' - Moderate, 'C' - Low, 'L' - Unsuitable for Retention
- 11 Sub Cat refers to the retention criteria values where 'L' is mainly arboricultural benefit, 'M' is main landscape qualities and 'S' is mainly cultural values including conservation.
- 12 Useful Life is the tree's estimated remaining contribution in years

Appendix 1. Tree schedule

Landmark Trees Ltd
Tel: 020 7851 4544

BS5837 Tree Constraints Survey Schedule

Page

Site: 92 FitzJohn's Avenue, London NW3 6NP
Date: 7th August 2012

Surveyor(s): James Bell
Ref: TSS/92FJA/AIA/01a

Tree No.	English Name	Height	Crown Spread	Ground Clearance	Age Class	Stem Diameter	Protection Radius	Growth Vitality	Structural Condition	Landscape Contribution	B.S. Sub Cat	Useful Life	Observations
8	Oakmoss	17	7	6	Mature	5204	12	62	Normal	Fair?	Medium	B	1 20-40 Offsite, low quality older & have at base
9	Walnut, Common	8	424	2.5	Early Mature	2994	12	34	Normal	Fair?	Low	C	1 20-40 Offsite
10	Yew, Common	9	5	1.8	Early Mature	480	12	58	Normal	Fair?	Low	B	1 >40 Offsite
11	Cherry, Wild (Ginn)	11	4344	4	Semi-mature	1794	12	28	Moderate	Fair	Low	CA	1 10-20 Poor form Office
12	Sycamore	17	6666	2	Nature	560	12	71	Normal	Good	Medium	B	1 >40 Forks at 1.5m, 45m clearance over garden
13	Holly	4.5	15	1.8	Early Mature	184	12	20	Normal	Good	Low	C	1 20-40 Twin stem SD=100 & 130
14	Cherry, Wild (Ginn)	4.5	1.525/2.51	1.5	Young	80	12	11	Normal	Good	Low	C	1 20-40

Notes:

1. Height describes the approximate height of the tree measured in meters from ground level
2. The Crown Spread refers to the crown radius in meters from the stem centre and is expressed as an average of HSWV aspect if symmetrical
3. Ground Clearance is the height in meters of crown clearance above adjacent ground level
4. Stem Diameter is the diameter of the stem measured in millimeters at 1.5m from ground level for single stemmed trees. See section 4.6 for detail of treatment for multi stems

5. Protection Radius is a radial distance measured from the trunk centre
6. Growth Vitality - Normal growth, Moderate (below normal), Poor (sparsely/weak)
7. Structural Condition - Good (no or only minor defects), Fair (moderate defects), Poor - Major defects present
8. Landscape Contribution - High (convenient landscape feature), Medium (visible in landscape), Low (secluded/obscured other trees)
9. B.S. Cat refers to (British Standard 5837 2012 Table 1) and refers to tree/group quality and value 'A': High, 'B': Moderate, 'C': Low, 'U': Unsuitable for Retention
10. Sub Cat refers to the retention criteria values where 1 is mainly arboricultural qualities, 2 mainly landscape qualities and 3 is mainly cultural values including conservation
11. Useful Life is the tree's estimated remaining contribution in years

Landmark Trees Ltd
Tel: 020 7851 4544

BS5837 Tree Constraints Survey Schedule

Page

Site: 92 FitzJohn's Avenue, London NW3 6NP
Date: 7th August 2012

Surveyor(s): James Bell
Ref: TSS/92FJA/AIA/01a

Tree No.	English Name	Height	Crown Spread	Ground Clearance	Age Class	Stem Diameter	Protection Radius	Growth Vitality	Structural Condition	Landscape Contribution	B.S. Sub Cat	Useful Life	Observations	
15	Rose, variety	4	1	2	Young	60	12	0.7	Normal	Good	Low	C	1 20-40	
16	Amanancher sap	4	15	1	Young	60	12	0.7	Normal	Good	Low	C	1 20-40	
17	Capercaillie	3	3	1.5	Mature	114	12	1.4	Moderate	Fair	Low	C	1 10-20 Mult stem 3 SD=90, 70 & 40, stably	
18	Liquidambar	2.5	15	3	Semi-mature	60	12	1.6	Normal	Good	Low	C	1 10-20 Garden ornamental	
19	5	Prunus	4	15	6	Early Mature	179	12	2.1	Fair/Fair	Fair	Low	C	1 10-20 Multi stem 3 SD av = 60, shaped
21	Colonoster	3	1	1	Early Mature	70	12	0.8	Normal	Good	Low	C	1 10-20	
22	Magnolia (M. grandiflora)	3	1	1	Semi-mature	80	12	1.0	Normal	Fair	Low	C	1 20-40	

Notes:

1. Height describes the approximate height of the tree measured in meters from ground level
2. The Crown Spread refers to the crown radius in meters from the stem centre and is expressed as an average of HSWV aspect if symmetrical
3. Ground Clearance is the height in meters of crown clearance above adjacent ground level
4. Stem Diameter is the diameter of the stem measured in millimeters at 1.5m from ground level for single stemmed trees. See section 4.6 for detail of treatment for multi stems
5. Protection Radius is a radial distance measured from the trunk centre
6. Growth Vitality - Normal growth, Moderate (below normal), Poor (sparsely/weak)
7. Structural Condition - Good (no or only minor defects), Fair (moderate defects), Poor - Major defects present
8. Landscape Contribution - High (convenient landscape feature), Medium (visible in landscape), Low (secluded/obscured other trees)
9. B.S. Cat refers to (British Standard 5837 2012 Table 1) and refers to tree/group quality and value 'A': High, 'B': Moderate, 'C': Low, 'U': Unsuitable for Retention
10. Sub Cat refers to the retention criteria values where 1 is mainly arboricultural qualities, 2 mainly landscape qualities and 3 is mainly cultural values including conservation
11. Useful Life is the tree's estimated remaining contribution in years

Appendix 1. Tree schedule

Landmark Trees Ltd
Tel: 020 7851 4544

Site: 72 FitzJohn's Avenue, London NW3 6NP
Date: 7th August 2012

B55837 Tree Constraints Survey Schedule

Page

Tree No.	English Name	Height	Crown Spread	Ground Clearance	Age Class	Stem Diameter	Protection Multiplier	Protection Radius	Growth Vitality	Structural Condition	Landscape Contribution	B.S. Sub Cat	Useful Life	Observations
23	Olive	3	1.5	1	Semi-mature	160	12	1.9	Normal	Good	Low	C	1	20-40 Shaped
24	Oncidio (Madagascar Tree)	10	2	2	Semi-mature	150e	12	1.6	Normal	Fair?	Low	C	1	>40 Offsite
25	Maple, Norway	10	4	3	Early Mature	350e	12	4.2	Normal	Good	Medium	B	1	20-40 Offsite, crimson cv
26	Cherry, Autumn Flowering	4	2.5	1	Young	60	12	0.7	Normal	Good	Low	C	1	20-40 Clipping
Q27	Hawth & Elder	7	2.5	2	Early Mature	170	12	2.1	Normal	Fair?	Low	C	2	10-20 Multi stem 20+ Av SD = 40
29	Sycamore	18	7477	7	Mature	650e	12	7.6	Normal	Fair?	Medium	B	1	20-40 4 trunks from 3m Fork obscured 2m clearance off roadside offsite
30	Holly, variegated	12	3	2	Mature	380	12	4.8	Normal	Fair?	Medium	C	1	10-20 Multi stem - 3 Ivy smothered SD=300e 170e & 170e debreck in upper crown

Notes:

- 1 Height describes the approximate height of the tree measured in meters from ground level
- 2 The Crown Spread refers to the crown radius in meters from the stem centre and is expressed as an average of NSEW aspect if symmetrical
- 3 Ground Clearance is the height in meters of crown clearance above adjacent ground level
- 4 Stem Diameter is the diameter of the stem measured in millimeters at 1.5m from ground level for single stemmed trees. See section 4.6 for detail of treatment for multi-stems.

- 5 Protection Radius is a radial distance measured from the trunk centre
- 6 Growth Vitality - Normal growth, Moderate (below normal), Poor (severely poor), Dead (dead or dying tree).
- 7 Structural Condition - Good (no or only minor defects), Fair (moderate defects), Poor - Major defects present
- 8 Landscape Contribution - High (prominent landscape feature), Medium (visible in landscape), Low (barely discernible other trees)
- 9 B.S. Cat refers to British Standard 5637 2012 Table 1) and refers to tree/group quality and value 'A' - High, 'B' - Moderate, 'C' - Low, 'U' - Unsuitable for retention
- 10 Sub Cat refers to the retention criteria values where 1 is mainly arboricultural qualities, 2 mainly landscape qualities and 3 is mainly cultural values including conservation
- 11 Sub Cat refers to the selection criteria values where 1 is mainly arboricultural qualities, 2 mainly landscape qualities and 3 is mainly cultural values including conservation
- 12 Useful Life is the tree's estimated remaining contribution in years

Landmark Trees Ltd
Tel: 020 7851 4544

Site: 72 FitzJohn's Avenue, London NW3 6NP
Date: 7th August 2012

B55837 Tree Constraints Survey Schedule

Page

Tree No.	English Name	Height	Crown Spread	Ground Clearance	Age Class	Stem Diameter	Protection Multiplier	Protection Radius	Growth Vitality	Structural Condition	Landscape Contribution	B.S. Sub Cat	Useful Life	Observations
31	Willow, Sallow	6	1322	2	Semi-mature	113	12	1.4	Normal	Fair?	Low	C	10-20	Twin stem Offsite, SD=80 x 2
34	Sycamore	15	6	2	Mature	670	12	8.0	Normal	Fair?	Medium	B	1	Ivy smothered Fork at 1.7m Offsite, crown growing onto bank of build over root base. Involve so SD estimate notional
35	Cypress, Lawson variety	8	2.5	1.8	Early Mature	300	12	3.8	Normal	Good	Low	C	1	Garden ornaments
36	Cypress, Lawson variety	7	2.5	1.8	Early Mature	240	12	2.9	Normal	Good	Low	C	1	Garden ornaments
37	Sycamore	15	5546	2.5	Early Mature	483	12	5.8	Normal	Fair?	Medium	B	1	Twin stem SD=100 & 270
38	Heather, Common	4	1.5	2	Young	49	12	0.5	Normal	Fair	Low	C	1	20-40

Notes:

- 1 Height describes the approximate height of the tree measured in meters from ground level
- 2 The Crown Spread refers to the crown radius in meters from the stem centre and is expressed as an average of NSEW aspect if symmetrical
- 3 Ground Clearance is the height in meters of crown clearance above adjacent ground level
- 4 Stem Diameter is the diameter of the stem measured in millimeters at 1.5m from ground level for single stemmed trees. See section 4.6 for detail of treatment for multi-stems.
- 5 Protection Radius is a radial distance measured from the trunk centre
- 6 Growth Vitality - Normal growth, Moderate (below normal), Poor (severely poor), Dead (dead or dying tree).
- 7 Structural Condition - Good (no or only minor defects), Fair (moderate defects), Poor - Major defects present
- 8 Landscape Contribution - High (prominent landscape feature), Medium (visible in landscape), Low (barely discernible other trees)
- 9 B.S. Cat refers to British Standard 5637 2012 Table 1) and refers to tree/group quality and value 'A' - High, 'B' - Moderate, 'C' - Low, 'U' - Unsuitable for retention
- 10 Sub Cat refers to the selection criteria values where 1 is mainly arboricultural qualities, 2 mainly landscape qualities and 3 is mainly cultural values including conservation
- 11 Sub Cat refers to the selection criteria values where 1 is mainly arboricultural qualities, 2 mainly landscape qualities and 3 is mainly cultural values including conservation
- 12 Useful Life is the tree's estimated remaining contribution in years

Appendix 1. Tree schedule

Landmark Trees Ltd
Tel: 020 7851 4544

Site: 92 Fitzjohn's Avenue, London NW3 6NP
Date: 7th August 2012

B55837 Tree Constraints Survey Schedule

Page

Tree No	English Name	Height	Crown Spread	Ground Clearance	Age Class	Stem Diameter	Protection Multiplier	Protection Radius	Growth Vitality	Structural Condition	Landscape Contribution	R.S. Cat	B.S. Cat	Useful Life	Observations
30	Hornbeam Common	2.5	1.5	2	Young	33	12	0.4	Normal	Fair	Low	C	1	20-40	
26	Holly	1.2	1	2	Mature	35e	12	4.2	Normal	Fair?	Medium	Cb	1	20-40	
36	Haw Common	7	2.5	1.8	Semi-mature	210	12	2.6	Normal	Good	Low	C	1	>40	Two stems SD=160 & 150e
38	Yew Common	5	2.22	1.7	Semi-mature	150e	12	1.6	Normal	Good	Low	C	1	>40	
40	Elder	7	2.42	2	Mature	240	12	2.9	Poor	Fair	Low	Ca	10-20	A sparser than normal canopy Two stems SD=180 & 160	
48	Cherry	4	0.32	2	Semi-mature	140	0.6	Dead	Poor	Low	U			Dead	
42	Cedar/C deodar	4.5	1.5	0	Young	100	12	1.2	Normal	Good	Low	C	1	>40	

- Notes:**
1. Height describes the appropriate height of the tree measured in meters from ground level
 2. The Crown Spread refers to the crown radius in meters from the stem centre and is expressed as an average of NSEW aspect if symmetrical
 3. Ground Clearance is the height in meters of crown clearance above adjacent ground level
 4. Stem Diameter is the diameter of the stem measured in millimeters at 1.5m from ground level for single stemmed trees. See section 4.6 for detail of treatment for multi-stems
 5. Protection Radius is a radial distance measured from the trunk centre
 6. Growth Vitality - Normal growth, Moderate (below normal), Poor (severe break), Dead (dead or dying tree)
 7. Structural Condition - Good (no or only minor defects), Fair (remediable defects), Poor - Major defects present
 8. Landscape Contribution - High (prominent landscape feature), Medium (visible in landscape), Low (indistinct among other trees)
 9. B.S. Cat refers to (British Standard 5837:2012 Table 1) and refers to tree/group quality and value 'A' - High, 'B' - Moderate, 'C' - Low, 'U' - Unstable for Retention
 10. B.S. Cat refers to the retention criteria values where 1 is mainly arboricultural qualities, 2 mainly landscape qualities and 3 is mainly cultural values including conservation
 11. Useable Life is the tree's estimated remaining contribution in years

Landmark Trees Ltd
Tel: 020 7851 4544

Site: 92 Fitzjohn's Avenue, London NW3 6NP
Date: 7th August 2012

B55837 Tree Constraints Survey Schedule

Page

Tree No	English Name	Height	Crown Spread	Ground Clearance	Age Class	Stem Diameter	Protection Multiplier	Protection Radius	Growth Vitality	Structural Condition	Landscape Contribution	R.S. Cat	B.S. Cat	Useful Life	Observations
43	Elder	4	2	1.5	Mature	200	12	2.4	Moderate	Fair	Low	Ca	2	10-20	Ivy smothered
44	Cherry Wild(Green)	4.5	2.32	2	Semi-mature	220	12	2.6	Moderate	Fair	Low	Ca	2	10-20	Ivy smothered Electrical cencer
45	Cherry Wild(Green)	8	1.85/2	2.5	Early Mature	330	12	2.7	Moderate	Fair	Low	U	10	<10	Leans to GE Dense no exposed roots
46	Cherry Wild(Green)	6	0.32	3.5	Early Mature	320e	12	3.0	Moderate	Fair	Low	Ca	10-20	Leans to GE Ivy smothered	

- Notes:**
1. Height describes the appropriate height of the tree measured in meters from ground level
 2. The Crown Spread refers to the crown radius in meters from the stem centre and is expressed as an average of NSEW aspects if symmetrical
 3. Ground Clearance is the height in meters of crown clearance above adjacent ground level
 4. Stem Diameter is the diameter of the stem measured in millimeters at 1.5m from ground level for single stemmed trees. See section 4.6 for detail of treatment for multi-stems
 5. Protection Radius is a radial distance measured from the trunk centre
 6. Growth Vitality - Normal growth, Moderate (below normal), Poor (severe break), Dead (dead or dying tree)
 7. Structural Condition - Good (no or only minor defects), Fair (remediable defects), Poor - Major defect present
 8. Landscape Contribution - High (prominent landscape feature), Medium (visible in landscape), Low (indistinct among other trees)
 9. B.S. Cat refers to (British Standard 5837:2012 Table 1) and refers to tree/group quality and value 'A' - High, 'B' - Moderate, 'C' - Low, 'U' - Unstable for Retention
 10. B.S. Cat refers to the retention criteria values where 1 is mainly arboricultural qualities, 2 mainly landscape qualities and 3 is mainly cultural values including conservation
 11. Useful Life is the tree's estimated remaining contribution in years

Appendix 1. Tree schedule

Landmark Trees Ltd Recommended Tree Works To Facilitate Development

Tel: 0207 851 4544 Page:

Site: 92 FitzJohn's Avenue, London NW3 6NP

Date: 7th August 2012

Surveyor(s): James Bell

Ref: TSS/92FJA/AIA/01c

Tree No.	English Name	Height	Dia mm	Crown Spread	Recommended Works	Comments/ Reasons
41	Cherry	4	140	0322	Fell	Dead Admirable for good arboricultural practice
45	Cherry Wld (Gean)	9	380	15/5 2/2 (or apply to fell)	Fell	Leans to SE Decay in exposed roots Admirable for good arboricultural practice
46	Cherry Wld (Gean)	8	320w	0321	Monitor	Leans to S/E Ivy smothered Admirable for good arboricultural practice

Notes:
 CB - Cut Back to boundary lines 8 cm structure
 CLS - Crown Lift to given height in meters
 CTR% - Crown Thinning by identified %
 CCL - Crown Clean (remove deadwood/crossing and hazardous branches and stubs)
 CR% - Crown Reduce by given maximum % (of outermost branch & twig length)
 DWD - Remove deadwood
 Fall - Fall to ground level
 FInv - Further investigation (generally with decay detection equipment)
 Poll - - Pollard or re-pollard
 Mon - Monitor ongoing condition (annually by staff / owners & every 2-3 yrs by consultant)
 S/Ivy / Cl/Bs - - Sever Ivy / clear base and re-inspect base / stem for concealed defects

Appendix 2. Recommended tree works to facilitate development

Landmark Trees Ltd Recommended Tree Works To Facilitate Development

Tel: 0207 851 4544 Page:

Site: 92 FitzJohn's Avenue, London NW3 6NP

Date: 7th August 2012

Surveyor(s): James Bell

Ref: TSS/92FJA/JAMS/01a

Tree No.	English Name	Height	Dia mm	Crown Spread	Recommended Works	Comments/ Reasons
3	Maple, Honey	17	650w	0641	CL 8m	Crown lift to facilitate access Recommended to permit development
10	Yew, Common	9	250	3	CL 8m	Crown lift to facilitate access Ornate Recommended to permit development
12	Sycamore	17	580	0866	CL 4m	Crown lift to facilitate access Ground protection with allowance for planting Poles at 1.5m above ground level over path Recommended to permit development
13	Holly	4.5	154	1.5	Fell	Tree stem SD=100 & 130 Part of landscape improvement scheme
14	Cherry Wld (Gean)	4.5	90	1.5/2	Fell SD=52.5	Part of landscape improvement scheme
15	Rosin variety	4	60	1	Fell	Part of landscape improvement scheme
16	Amaranthus spp	4	60	1.5	Fell	Part of landscape improvement scheme
17	Cocculus	3	114	2	Fell	Mulch stem 3 SD=80.70 & 40 whub Part of landscape improvement scheme
18	Laurus	2.5	80	1.5	Fell	Garden ornamental Part of landscape improvement scheme

Notes:
 CB - Cut Back to boundary lines 8 cm structure
 CLS - Crown Lift to given height in meters
 CTR% - Crown Thinning by identified %
 CCL - Crown Clean (remove deadwood/crossing and hazardous branches and stubs)
 CR% - Crown Reduce by given maximum % (of outermost branch & twig length)
 DWD - Remove deadwood
 Fall - Fall to ground level
 FInv - Further investigation (generally with decay detection equipment)
 Poll - - Pollard or re-pollard
 Mon - Monitor ongoing condition (annually by staff / owners & every 2-3 yrs by consultant)
 S/Ivy / Cl/Bs - - Sever Ivy / clear base and re-inspect base / stem for concealed defects

Appendix 2. Recommended tree works to facilitate development

Landmark Trees Ltd Recommended Tree Works To Facilitate Development

Tel: 0207 851 4544 Page

Site: 92 Fitzjohn's Avenue, London NW3 6NP Surveyor(s): James Bell

Date: 7th August 2012 Ref: TSB/02FJA/AMS/01a

Tree No.	English Name	Height	Stem Diameter	Crown Spread	Recommended Works	Comments/Reasons
16/09	Pine	4	17%	1.5	Fell	Multi stem - 5 SU av = 60 shaped Part of landscape improvement scheme
21	Cotoneaster	3	70	1	Fell	Part of landscape improvement scheme
22	Magnolia (M. grandiflora)	3	80	1	Fell	Part of landscape improvement scheme
23	Olive	3	180	1.5	Fell	Shaped Part of landscape improvement scheme
26	Cherry, Autumn Flowering	4	60	2.5	Fell	Gaps 2 Recommended to permit development
31	Willow, Sallow	6	115	1323	CB1-2	Cut back 1-2 metres to facilitate a access Recommended to permit development
35	Cypress, Lawson variety	8	300	2.5	Fell	Garden ornamental Recommended to permit development
36	Cypress, Lawson variety	7	240	2.5	Fell	Garden ornamental Recommended to permit development
37	Sycamore	15	463	5546	CL5m	Ground protection with allowance for piling CL for working clearance/reduction in shading Recommended to permit development
40	Elder	7	241	2427	Fell	A sprayer base normal canopy Recommended to permit development
42	Cedar (C. deodara)	4.5	100	1.5	Fell	Recommended to permit development

Abbrev:

- CB - Cut Back to boundary/leaves from structure
- CLx - Crown Lift to given height in meters
- CTR% - Crown Thinning by identified %
- CCL - Crown Clean (remove deadwood/crossing and hazardous branches and stubs)
- CRD% - Crown Reduce by given maximum % (of outermost branch & twigs length)
- DWD - Remove deadwood
- Fell - Fell to ground level
- FIR - Further investigation (generally with decay detection equipment)
- Pol - Pollard or re-pollard
- Mon - Monitor ongoing condition (annually by staff / owners & every 2-3 yrs by consultant)
- Svr Ivy / Cr Br - Silver ivy / clear base and re-inspect base / stem for concealed defects

Landmark Trees Ltd Recommended Tree Works To Facilitate Development

Tel: 0207 851 4544 Page

Site: 92 Fitzjohn's Avenue, London NW3 6NP

Surveyor(s): James Bell
Date: 7th August 2012 Ref: TSS/02FJA/AMS/01a

Tree No.	English Name	Height	Stem Diameter	Crown Spread	Recommended Works	Comments/Reasons
43	Elder	4	200	2	F&G	Ivy smothered Recommended to permit development
44	Cherry Wild (Green)	4.5	220	2322	F&G	Ivy smothered Bad root cause Recommended to permit development


Abbrev:

- CB - Cut Back to boundary/leaves from structure
- CLx - Crown Lift to given height in meters
- CTR% - Crown Thinning by identified %
- CCL - Crown Clean (remove deadwood/crossing and hazardous branches and stubs)
- CRD% - Crown Reduce by given maximum % (of outermost branch & twigs length)
- DWD - Remove deadwood
- Fell - Fell to ground level
- FIR - Further investigation (generally with decay detection equipment)
- Pol - Pollard or re-pollard
- Mon - Monitor ongoing condition (annually by staff / owners & every 2-3 yrs by consultant)
- Svr Ivy / Cr Br - Silver ivy / clear base and re-inspect base / stem for concealed defects

Appendix 4. Tree constraints plan



Appendix 5. Arboricultural impact assessment plan



Arboricultural Method Statement



REFERENCES AND METHODS STATEMENT

SCF & CEF
London
1973 (1st)

Ms Rachel Ladd and Mr John Weston
92 Finsbury's Avenue
London
EC2M 8HP

www.sagepub.com

Adam Morris

Ref-1834744053C12

The contact and login of the Super user for the exclusive use of The Client. It may not be used and, hence shall be submitted to any third party and does not exceed the duration of the License granted authorizing I amCloud Technologies without permission.

Wigle, who founded Steel City in 1984, e-mail: relo@comcast.net or fax 802/251-1434.   

CONTENTS		
1	Introduction	
1.1	Purpose of the Method Statement	2
1.2	Terms of Reference	3
1.3	Descriptive Prose	4
1.4	Sequence of events	5
1.5	Site Selection	5
1.6	Site Monitoring	6
1.7	Statement Action	7
2	Pre-Development site preparation	
2.1	Agricultural Works	8
2.2	Installation of Tree Protective Barrier	8
2.3	Pre-development Site Inspection	9
3	Development Phase	
3.1	General Principles	10
3.2	The Root Protection Area (RPA)	10
3.3	Site Access, Aspects Protection and Scarifice	10
3.4	Supply and Installation Services	11
3.5	Changes in Grade	11
3.6	Desirable Measures	11
3.7	Construction Method	11
4	Harvest of Tree Protection Barrier	
4.1	Summary of Proposed Methods	12
4.2	Table of Inputs and Outputs	12
5	Compliance	
5.1	Compliance Meeting	12

- 1.0 Introduction**

1.1 Purpose & Use of the Listed Statement

1.1.1 This Local Listed Statement has been prepared for Mr Rachid Lard and Mr John Wade relating to the calculations that will be implemented to mitigate the potential risk during the proposed development at 20 Regents Avenue, London NW1 1BP. The application for the proposed site to be located in the London Borough of Camden Council, this document is to be used to meet the requirements of the Council for this protection. The tree replacement in landscape mitigation is dealt with below by the Design and Access Statement.

1.1.2 This document aims to set out the methodology for a proposed solution that they have in effect to the issues and a solution to the site. It is to start with the site area and analyse the key factors of the development proposals that have been submitted in the planning application. It is recommended that this document form part of the overall scheme and specification related to the listed structures as well as be used in the post contract.

1.1.3 Output of the document will be available to download on site. The developer will inform the local planning authority how to access the information contained in this statement.

1.2 Terms of Reference

1.2.1 We (CLT) are instructed by the client, Mr Rachel Lard and Mr John Wade to prepare a Local Listed Statement for proposed development based on the above planning application with reference to L 560/21 D/21 Town & Roads to Design, Development and Construction

1.2.2 To that purpose, the client has appointed us to do the work set out below (1.1-13) and the overall process plan (APP 2025 - 2021) in agreement. This Statement will replace a Generic Site Report setting the policy to be used for the proposed dwelling (No. 2252C). We are to retain our own impact assessment report TIGS020/2019/001 and prior coverage of the constraints carry forward.

1.3 Development Proposals & Potential Impact

1.3.1 The proposed site area is to be developed in the existing dwelling, informed by the conclusion of a replacement dwelling with a robust landscaping strategy. The design proposes a preexisting garage structure which needs to be removed for the rehousing of the ground floor unit.

1.3.2 The proposed primary intention will be to protect and the removal of 7 mature trees of 10m qualification to retention (12A, 1B, 1C, 42, 43, 44) involving due care and agreed, in removal of which there will be substantial remedial. A further 10 (approximately 15 - 20m) will be left as part of an overall ecological scheme which are to be replaced with good quality trees, drawn from the existing tree gallery (P.1 of 'Cassons').

Tree survey & arboricultural assessment

- 1.2.1 The effects on retained, mature quality trees comprise building/parking encroachments of the tree canopy RFA of 12% T2C and 13% or 27% (0.5% and 15% area respectively). Further resulting encroachments from the development on the retained active 11% RFA by 10% in terms of height, the LPA boundaries will be altered and adjusted to T2C (the only trees impacted at this level) to avoid further building through the RFA / closer to the tree. Tree planting encroachments will be pre-evaluated and monitored by hand to 25m²/100m² when under arboricultural supervision. The GfC encroachments of mature low-matured species are anticipated to account for the additional area within 12% RFA and the tree within 12% RFA. Assuming GfC encroachments will be determined plus any disturbance of the tree locations determined by tree assessors. The potential canopy impacts to 29 & 37 trees above ground construction will be reduced by design and planting 100% away from the boundaries though tree crown RFA of 2.0% & 2.1% are still re-assessed. The impact of the proposed canopy will be mitigated by using low-impact landscape design. The impact of the development on 112 will be managed by using passive paving / no dig construction technique. Control demolition of existing structures (underground and surface) and replacement were not landscape or hard landscape design will not exceed 10m². Further critical instruments to mitigate conflicts can be made in the pre-planned zones during the landscape phase.

1.3 Site Supervision

- 1.4.1 The sequence of works will be as follows:
- site works - setting out, grubbing and planting for working derivatives
 - removal of tree Protection Zone (TPZ) & ground protection
 - demolition & using heavy & vermiculite
 - reduction of tree canopy growth
 - installation of underground services
 - plant construction
 - removal of TPZ
 - soft landscaping
- These works and their arboricultural implications are outlined in sequence below

Information: Major Submission Ref: 11/22/2023/Permit_London/00000000000000000000000000000000
Project Ref: 00_Easy_1 and 00_Soft_Needs_01_Forestry_Arborist_January_2023
Request for: Arborist / Landscaping / Tree / Soft Landscaping / Soil / Site Preparation

1.5 Site Supervision

- 1) Site supervisors – an individual e.g. the Site Agent, must be nominated to be responsible to all arboricultural matters or vice versa. An agent must be nominated to take place of head of operation and to nominate individuals or contractors separately. The agent must:
 - be present on site for the majority of the time
 - be aware of the arboricultural requirements in the RFA, LPA and TPZ and ensure that these are carried out as per the approved methodology and during any other unchanged instructions
 - have the authority to stop any work that is causing, or has the potential to cause harm to any tree
 - be responsible for ensuring that all site operatives are aware of their responsibilities towards trees on site and the consequences of failure to observe these responsibilities
 - make arrangements with the local authority prior to retained arboriculture in the event of any tree related incidents occurring, whether actual or potential
 - Contact details for Landmark Trees are provided at the end of this report
 - Contact details for the Local Authority Tree Officer are as follows:

Mark Weston
Freeport Landscapes - Project
Lewisham Borough Council
60 Rose Town Hill Extension
Argyle Street
London SE15 3AD

Email: mark.weston@lewisham.gov.uk
Telephone: 020 7924 5979

1.6 Site Monitoring

- 1.6.1 Landmark Trees will be retained as Arboricultural Consultants responsible for monitoring the outcome of the development. Key personnel are in the role Agent Head (AG) see necessary James the Tech Guy, subject to any new staff roles. Site monitoring will be undertaken by a qualified and experienced arboriculturist at pre-determined times against the RFA.
- 1.6.2 The arboricultural will arrive at the site check in at the office and be given secured access to the site by the site agent, checking the necessity of tree protection measures. Access will generally be unobstructed. However, an arboriculturist will also be obliged to observe and follow any agreed to supervisor's directions and advice (e.g. 10m²)
- 1.6.3 General site monitoring will have the task of regular inspections (of e.g. protection measures), ongoing liaison with all concerned parties in the site development and with the LA. Any defects

Information: Major Submission Ref: 11/22/2023/Permit_London/00000000000000000000000000000000
Project Ref: 00_Easy_1 and 00_Soft_Needs_01_Forestry_Arborist_January_2023
Request for: Arborist / Landscaping / Tree / Soft Landscaping / Soil / Site Preparation

requiring rectifying must be notified to the Site Agent and the Client and copied to the LA by email. Emergencies will be notified to the LA by phone. Appropriate records will be kept and be made available to the LA if required to show evidence of site monitoring (Appendix 3).

- 1.6.4 Post specific site supervision will require the arboriculturist to be present during key operations to ensure detailed levels are carried out as per the approved methodology and during any other unchanged instructions. (b) the arboriculturist must be copied to LPA agreements for planning consent. This supervisor will regard the arboriculturist to be present during the LA to ensure the arboricultural standards are met. However, where the trees are ongoing arboricultural standards, and after an appropriate notice, the supervisor may be released to telephone and email contact between the LA, Local authority and arboriculturist. Site supervisor should include the handbook titled 'Code of Practice for boundary wall insulation and construction of cycle paths' within the RFA.

- 1.6.5 The recommended frequency will be fortnightly for the first three months and monthly thereafter. At 2000hrs a site logbook will be kept by the Site Agent to record all stages of the development from the granting of the development to daily check of the fencing through to the completion of the project. "A site Agent must be available to the LA if required to demonstrate or give evidence. Site monitoring should include:
 - Any Government Site Inspection (S23)
 - Construction Site Audit (C15)
 - Inspection of site features (S23)
 - Condition of fence surfaces / structures within RFA (D7)
 - Construction of new or lost surfaces (F2 around within RFA S1 O7)
 - Site occupation monitoring (S1)

- 1.6.6 The LPA & Arboricultural Consultant will have free access to any drawings issued directly to the developer's Project Arboricultural Unit, who will have sole use of the site and these measurements to the developer on how best to safely the situation and ensure replacement/s. A final sign-off will also be carried out at the end of the development work & formal letter issued to the client and LA confirming we are fit for inspection (S1).

- 1.6.7 NR. Landmark Trees will only be responsible for providing monitoring in for as often they instructed to do and regularly check for such instances by the client. In the absence of instruction Landmark Trees will not be liable for any damage or loss caused particularly by contractors and the LPA will be informed of the cessation of monitoring. The client will also monitor the site to detect Landmark Trees and liaise with another contractor, but must inform the LPA.

1.7 Statement of Adoption

- 1.7.1 It is recommended that, at due course, acceptance of the recommendations in this report is demonstrated by the developer, the contractor, and/or the LPA by signing to this building contract in due consideration of the contents, and by agreement in writing to adopt these recommendations. If such is not done, it will be assumed that the contractor accepts the recommendations and LPA, provided it conflicts with them in part, it is true that the developer in the course of development has either been advised orally or in writing, or qualified arboriculturist, it concluded otherwise. Lack of such care is often accepted, good design and safety of such trees can result design fails and can result in significant remedial action, costly or even demolition of such trees. Developers should reflect poorly on the construction and design performance reviewed. Trees that have been rejected or carry a warning during construction add considerably to the overall risk and value of the developer's assets.

Information: Major Submission Ref: 11/22/2023/Permit_London/00000000000000000000000000000000
Project Ref: 00_Easy_1 and 00_Soft_Needs_01_Forestry_Arborist_January_2023
Request for: Arborist / Landscaping / Tree / Soft Landscaping / Soil / Site Preparation

Tree survey & arboricultural assessment

2.0 Pre-Development Site Preparation

2.1 Arboricultural Work

- 2.1.1 All works will be carried out by a competent arborist in accord with BS 3086: 2010 *arboriculture: tree felling, pruning, root and ground clearance, with reference to providing safe professional practice*.
- 2.1.2 Specific works (as necessary to facilitate development) in the removal of trees/trees* (Fig 2.1.2), 26-30, 40-42, 43-45, Crown lifting at 13, 15 and 17m will be required to restore access, with 37 remaining to provide sufficient working distance. A low quality timber 131 which overhangs the site by 1.2m would also need to be cut back to the boundary to facilitate construction. Tree specific works in relation to development and any other necessary works are listed in Appendix 3.

2.2 Installation of Tree Protection Bumper

- 2.2.1 A Tree Protection bumper (TPB) comprising steel mesh panels of 2.4m in height (Fig 2.2.1) should be erected to protect new buildings to be constructed as shown. These panels will be mounted at a scaffolding frame as shown in Figure 1 below (Fig 1 page 2 of BS5627: Trees in Relation to Design, the Removal and Construction in paragraph 2.2.1).

- 2.2.2 The TPB is to be erected before any work commences on site, to remain in situ throughout the duration of all work or each phase, and only to be removed once all work is completed. If any work is deemed necessary prior to the erection of a bumper, a temporary protection should be retained to reduce their presence to ensure the work being carried out.

- 2.2.3 The only other exception to the completion of 'not breaking out' of any structures (other than the TPB) is to be carried out as part of soil landscaping within the RPA, an arboricultural assessment must be carried out and any work or products required must be 'not breaking out' of the RPA should carry out a risk assessment during access within the RPA.

- 2.2.4 The Tree Protection Plan in Appendix 5 illustrates where the protective fencing will be located to form the boundary of the Tree Protection Zone (*TP). The TP is an exclusion zone established to allow for safety to prevent access by pedestrians and vehicles and the storage of any works materials. Landscaping will be located outside of the TPZ.




Fig 1 Tree Protection Bumper (Panel 2 from BS5627 - Detailed specification for protection plan)

2.3 Pre-Development Site Inspection

- 2.3.1 Upon completion of the tree works the TP represented will meet the revised local authority member on site to check the standards of the work. If there are any encroachments to either the tree works or building/structure measures they will be agreed at this meeting and confirmed in writing.

3.0 Development Phase

3.1 Pre-felling general precautions will apply

- * No trees shall be made or any part of the site or within 20m of any tree to be retained.
- * No lifting or moving of trees with overhead, or that are made on any part of the site.
- * No methods that are likely to have an adverse effect on the tree such as oil burners or ceramic air vents or discharge areas to the rest of the trunk of a tree that is to be retained.
- * No storage or discharge of wet mortar or concrete shall be made on any part of the site.
- * No storage of materials shall be made within the protection zone.
- * No breaking or moving of any drainage feature whether it is apparent or as anticipated.
- * Attention is given within the tree protection fence areas, shall be avoided.

3.2 Root Protection Areas (RPA)

- 3.2.1 The Root Protection Area (RPA) is a controlled zone of protection around the tree existing system and there have been marked on the plan in Appendix 4. As much as possible the RPA's will be within the TPZ and therefore as fully retained as possible. However, this degree of protection is not always possible as the tree is occupying a particular space (e.g. path, water or RPA) or there is no alternative of moving the tree and no underlying installation of services and construction of same building (e.g. foundations, piles, etc.) are active.

- 3.2.2 All overhead parties will need to be made aware of the difference. In these instances, cables and overhead working as detailed in Sections 3.4 & 3.5 (tripping of cables) and 3.6 (removal of surfaces) to 3.7 (cable damage) will be avoided.

- 3.2.3 Ground outside the TPZ must be protected from traffic and not left exposed during construction. As far as practical, earth and surfaces should be returned to initial ground protection levels for purposes of adopted landscape until the landscaping phase and/or substituted implements are available/replaced (e.g. Cultivator, Ground Guards etc.). Consideration of re-planting intercropping. Existing terrain will not be adequately ground treated or heavily planted up. To this end a concrete hardcore and reinforced ground protection will be substituted where necessary (see Appendix 3). Contractors to the RPA's should have 160mm concrete bags temporarily available to protect overhead construction roots.

3.3 Site Access, Accommodation & Storage

- 3.3.1 Site access and accommodation will be as per the layout within the Tree Protection Plan (Appendix 5), making use of the existing access road with supplementary ground protection where necessary. Site accommodation and storage will be located in the garden area, away from the TPZ. 3.3.2 Plant equipment access will be for site, 1.5m suitable to vehicular access.

3.4 Working & Installation of Services

- 3.4.1 Hard surfaces, trench line presence are to be determined in general, where any underground canals/tunnels exist a 1.2m. Into the preferred 2.0m, and 1.0m VSU (i.e. 4m away from the RPA) and 1.0m trenching and no more trenching under arboricultural management.

3.5 Changes to Cables

- 3.5.1 The upper layer of top soil covering the majority of a trees root and if this is disturbed by excavation of ground level, sensible mitigation will be applied to the disturbed areas (TPZ, RPA). It will be the duty of the head contractor and the managing architect to ensure the affected areas are restored.

- 3.5.2 If the relevant parties request, this will be reviewed along these principles:

- 3.5.3 If ground layers need to be stripped away within the RPA, a legal agreement must be signed and given by either a local authority tree officer or a TCC Consultant.

- 3.6 Duration of Works

- 3.6.1 Actual foundation cutting will be undertaken to prevent intrusive contact between foundation and the tree(s). Any such cutting will be undertaken in accordance with British Standard 3035: Requirements for tree works (See Section 2.1 / Appendix 1).

- 3.6.2 Derivation of structures when root disturbance is or may be present within the TPZ, 30, 34 and 37.

- 3.6.3 All plant and machinery engaged in demolition works (excavators only) will either operate outside 10% of root, 20% within the building/but structure and tree standing near root. Plants will stand adjacent to structures required for demolition. It will be necessary to understand exactly where within the footprint of the existing building column reference to 'set back' our back!'

3.7 Protection of Existing Features (E.g. Existing Paths, Ledges, Etc.)

- 3.7.1 Protection of paths, ledges, etc. will be undertaken to prevent intrusion into the structure or the tree(s). Such measures apply in particular to 3.9, 30, 34 and 37.

3.8 Protection of Existing Features (E.g. Existing Paths, Ledges, Etc.)

- 3.8.1 Protection of paths, ledges, etc. will be undertaken to prevent intrusion into the structure or the tree(s). Such measures apply in particular to 3.9, 30, 34 and 37.

3.9 Protection of Existing Features (E.g. Existing Paths, Ledges, Etc.)

- 3.9.1 Protection of paths, ledges, etc. will be undertaken to prevent intrusion into the structure or the tree(s). Such measures apply in particular to 3.9, 30, 34 and 37.

Tree survey & arboricultural assessment

12

- 3.6.4 Specifically the demolition of the main structure will be carried out by using a 200 tonne hydraulic excavator and, where necessary, a hydraulic impact breaker.
- 3.6.5 The root baulks will be lifted from the surface using the grapple and lowered to the ground where they will be further processed prior to being stacked ready for removal and removed from site as a suitable form of waste.
- 3.6.6 Having completed the removal of all structures, the main structure & brickwork elements of the tower will be demolished using a JCB excavator. The soil will be piled over in small increments and lowered to the side in the corners of the building, where they will be flattened and chipped to prevent it falling away from site to a suitable location nearby.
- 3.6.7 Heavy plant will be driven down and lowered from the ground floor slab to the ground floor slab by using a 300 tonne excavator equipped with, if necessary, the hydraulics required to move the concrete blocks safely. The hydraulics required will be the standard required to break the concrete & not be difficult to break. It will be done with the excavator bucket. The quarry action being preferred the concrete will be broken into manageable size pieces. Where the foundations are more than three times the size will be broken out in small sections and the void back filled and compacted prior to the next section being broken off.
- 3.6.8 Throughout all mechanical operations a barrier will be present at all times. Dust generated by the work will be suppressed using water sprays.
- 3.6.9 The weather in 'city' time will be assessed down to regular soil testing by arboricultural providers, either from a real building or from the ground. It may be necessary to seek the advice of Lichfield Town Council's environmental team. Following any significant rainfall advice will be sought.
- 3.6.10 All trees will be treated individually with root cutting glands.
- 3.6.11 Heavy plant used to remove imported materials and grade the surface will be de-bladed in one complete pass. This will be achieved by using necessary machinery on top of the existing grade level and working systematically away from relevant trees. The aim is to ensure that spoil is removed away from RPA's but it is very important that their original soil levels are only lowered under consultant supervision as roots will be close to the surface and can easily be damaged.
- 3.6.12 The hard standing within the tree's RPA's will be laid down up with thermal power tools and then carefully removed with earth by a cold machine contractor. Soil cover on the structure will not be removed over RPA's prepared in site and protected with reinstatement ground or mulch (as per para 3.2.1) for post development treatment (as per para 3.8.1).
- 3.6.13 Where replacement or a complementary ground protection is required following the removal of hard standing, it will be reinstated prior to the appearance of cutwaters.

13

3.7 Construction Measures

- 3.7.1 Detailed method statements and risk assessments will be obtained prior to specialist subcontractors involved in the new build and these will be submitted by the sub agent to ensure the AAFS requirements have been considered therein.
- 3.7.2 The building subcontractors will require the use of specialised foundation techniques. The LGF contractors will sheet piles through T2 & RPA of T2 before the crane range. Piling should not exceed the ground bearing pressure in the tree canopy (soil load survey), where a lifting slot will be required. The loads of the CLF contractor will mean the RPA will be un-excavated and root cut by hand to flatten earth under specialist supervision.
- 3.7.3 Roots greater than 20mm diameter may be cut directly with a sharp prying bar or excavators back to a medium. Roots larger than 20mm diameter may only be cut in consultation with an arboriculturalist.
- 3.7.4 To excavate to required depth all spoil to be loaded into trucks outside the RPA's until ground pressure is reduced and reinforced. Construction materials will generally be delivered as forms and equipment on load and unloading outside RPA's.
- 3.7.5 Concrete will be delivered to site pre-cast in 9m² items and distributed by a static concrete pump located outside RPA's where possible.
- 3.7.6 The G/F foundations will be entirely back-filled within the RPA. Feasibility of trial pile position and batter slope has been built into the foundation design.
- 3.7.7 The ground protection in T2 & RPA will allow evaluation of the pile and shallow twin treads in early archaeological supervision. The purpose of T2 & ground protection is to: 1) develop a pre-excavation area and to protect a surbur that is not affected by these excavation works. The piling must for T2 & RPA excavation will be undertaken on the ground protection as specified.
- 3.7.8 During the construction phase and throughout 10% percent, on site major testing areas will be formed and to control dust pollution. In the event of dust build up on trees, causing a botanical advice will be sent and free-standing reinforced membranes such as hessian liners to be used.
- 3.7.9 Where considering trees to be established within the RPA the following ground protection should be utilised alongside site works:




Figure 3 - Installation of Geotextile

- 3.7.10 The lighting in a sample localisation for lighting or site illumination by tree 312.
- c. The construction should ideally be undertaken between May and October as ground is sufficiently dry to prevent contractor drowning. The sub-contract should be to lay small holes as a trial to bring up to the required depth.
- d. install F1/F2 Separation Separation fabric over existing ground surface.
- e. The geotextile should be laid out over soft soil to act as a liner.
- f. The Cof. when cellular confinement system ref. 1 x 100 mm. Called: The 'Tension System' is recommended for use only for 20mm for calculating the area on the perimeter and adjacent panels are joined together. Please stating 'Tension System' cells open. The panels should be laid out and overlaid so that the contractor programme across the length of the area. The panels are laid with no final edge joints which serving as a platform for the next sheet.
- g. There is no limit at any time for the ground to be cleared by heavy offsite plant or material transported from the site by low level van confinement system by MECLEAR2000 and installed by H4ND. These will respond onto the RPA bay and the installation of the confinement system itself.
- h. Panels are supplied with an inner 20mm portion and three outer 10mm panels. If off site can be rolled to compact the panels and create a tight interlock as such.
- i. The finished surface can then be laid or top. Again no loose material to be laid around the root ball owing to possible damage is preferable for a 20mm thick in ground.
- j. Once the tree has been planted and the ground has been stabilised, the tree will be checked for stability and a botanical advice will be issued.
- k. We suggest a more extensive search as detailed below in further pages as 100m radius.

- 3.7.11 See construction diagram, Figure 4 below for further information. For technical data for the Geotextile and the Cellular cellular confinement system sheets refer to the manufacturer's guide, scope and implementation. Further technical advice can be gained from the manufacturer.

Contractor:
Holland and Ducker is a trading name of Gecotecniq Ltd
Holland Road
Birmingham Industrial Estate
Wolverhampton
WV1 1EO
T: 01902 562200
F: 01902 562201
E: info@geotecniq.com
www.geotecniq.com

Tree survey & arboricultural assessment

3.4 Removal of Ground Protection & Post Construction Landscaping & 'Hard' Areas

- 3.4.1 The tree protection areas shall be removed upon completion of the construction phase and after all drainage and services have been installed and any site remediation has been removed from the RSA.
- 3.4.2 Following the development phase, repeated check about the RSA inventory identified for such treatment will assess removal and remediation treatment, depth and nature of the damage to the viewer and self-inspecting.
- 3.4.3 Any further landscaping works should avoid the creation of ground levels or deep digging measures that don't such as tractor mounted excavators must be used within the RSA's or existing trees.
- 3.4.4 Heavy plant tools should not be used on the vicinity of any retained trees.
- 3.4.5 Planting areas should be used to protect the vicinity of any retained trees.
- 3.4.6 If planting areas to be used they should be appropriate to their purpose and for it such as to do damage are referred to soil or regulation.
- 3.4.7 Ideally, RSA's set 2008 should be within 5m from areas in this relates the creation of compaction and subsidence of root systems.
- 3.4.8 Any new parking schemes adopted should consider aspects of the site such as current design, layout and future use. Consideration should also be given to the site type, climate and overall character of the landscape.

4.0 Summary of Proposed Methods

4.1 Table of Impacts and Mitigation

- 4.1.1 The table below summarises the main areas where trees could become at risk during the proposed development and the methods that need to be adopted in order to prevent such damage.

Impact	Mitigation	Reference	Area Affected
General tree access material or debris etc.	Chainsawed or to acceptable standards	Para J2.1 & J2.3 Tree Protection Points Appendix A	All retained trees
Crosses roads / construction vehicles existing canopy	Tree surgery	Section 2.1	J2, J6, J12, J14, J2
Description of existing SCD within HCP	Full down / back reduction where safe	Section 3.6	J25, J30, J34 and J37
Damages to trees caused by building / retaining wall foundation movements etc.	Cut piles and beams and / or piles and / or specification for backfill	Section 3.7 & 8	J2, J30 and J37

5.0 Completion

5.1 Construction

- 5.1.1 Following completion of the works listed above, a Landscaper / Tree contractor will meet with a local authority representative(s) and agree upon what further work is deemed necessary.

- 5.1.2 A separate LT post-development tree inspection (with specific reference to trees identified in the Appendix 1 programme) is recommended to facilitate a constructive meeting and to monitor the health of some of the more vulnerable trees over time.

- 5.1.3 Any works agreed as the above meeting will be confirmed in writing and will be performed to BS 3688:2010 Tree Works.

- 5.1.4 Localised tree reinforcement that may result from proposed plant canopies will be clarified to avoid penalty for performing illegal work on a protected tree.

- 5.1.5 If conflicts between any part of a tree and the building(s) arise in the course of development, these can often be removed quickly and at little cost if a suitable alternative is provided promptly. Loss of such care is often apparent quickly and earlier and death of such trees can cost significantly and can affect other stability and major points on the remaining tree and cause personal injury. Trees that have been the recipient of careful handling during construction and corroborated by the Apples and Pears of the proposed development.

Adam Hollis MSc ARB MRCoP Arbor A
22nd February 2013
For and on behalf of Landmark Trees

With whom correspondence can be made at:
e-mail: adi@predmet.com.co.uk
Tel: 0207 851 4544
London Office: 22 Brookland Road, London, SW19 8PL
Regional Office: 33 Shrubland Road, London, SW19 8PL
Johannesburg Office: 1000 Parkwood Street, Braamfontein, Johannesburg, South Africa
Gauteng Office: 288 Wim Hofstraat, Johannesburg, South Africa

Signed

Appendix 1. Arboricultural Works

Landmark Trees Ltd Recommended Tree Works To Facilitate Development

Tel: 0207 851 4544
Site: 92 FitzJohn's Avenue, London NW3 6NP
Date: 7th August 2012

Surveyor(s): James Bell
Ref: TSS/02FJA/AMS/01a

Page

[Hide Irrrelevant](#) [Show All Trees](#)

Tree No.	English Name	Height	Biomass Diameter	Crown Spread	Recommended Works	Comments/Reasons
3	Maple, Norway	17	850s	660s	CL4m	Crown lift to facilitate access Recommended to permit development
10	Vine Common	9	460	3	CL4m	Crown lift to facilitate access Ornate Recommended to permit development
12	Sycamore	17	580	6888	CL4m	Crown lift to facilitate access Ground protection with allowance for piling Fork at 1 fm - 45cm clearance over path Recommended to permit development
13	Holly	4.5	184	1.5	Fell	Twin stem SD=100 & 50 Part of landscape improvement scheme
14	Cherry, Wild (Gash)	4.5	90	1 5/2	Fell	SD=100 & 50 Part of landscape improvement scheme
15	Rosace variety	4	80	1	Fell	Part of landscape improvement scheme
16	Ambleside spp.	4	60	1.5	Fell	Part of landscape improvement scheme
17	Ceanothus	3	114	2	Fell	Multi stem 3 SD=0.70 & 40 shrub Part of landscape improvement scheme
18	Ligustrum	2.5	80	1.5	Fell	Cardio ornamental Part of landscape improvement scheme

Codes:
CB - Cut Back to boundary/below tree structure

CLB - Crown Lift to given height in meters

CT% - Crown Thinning by identified %.

CCL - Crown Clean remove deadwood/crossing and hazardous branches and stubs.

CRW% - Crown Reduce by given maximum % (of outermost branch & twig length)

DWD - Remove deadwood.

Fell - Fell to ground level.

FInv - Further investigation (generally with decay detection equipment)

Pd - Pollard or respollard.

Mon - Monitor ongoing condition (annually by staff / owners & every 2-3 yrs by consultant).

Svr Inv / Cr Br - Sever Inv / clear base and re-inspect base / stem for concealed defects.

Landmark Trees Ltd Recommended Tree Works To Facilitate Development

Tel: 0207 851 4544
Site: 92 FitzJohn's Avenue, London NW3 6NP
Date: 7th August 2012

Surveyor(s): James Bell
Ref: TSS/02FJA/AMS/01a

Page

Tree No.	English Name	Height	Biomass Diameter	Crown Spread	Recommended Works	Comments/Reasons
19/20	Pivel	4	178	1.5	Fell	Multi stem - 5- SD ev = 50, shaped Part of landscape improvement scheme
21	Cocoonester	3	70	1	Fell	Part of landscape improvement scheme
22	Magnolia (M grandiflora)	3	80	1	Fell	Part of landscape improvement scheme
23	Clive	3	160	1.5	Fell	Shaped Part of landscape improvement scheme
26	Cherry, Autum Flowering	4	80	2.5	Fell	Ornang Recommended to permit development
31	Willow, Dallow	6	113	1523	CB1-2	Cut back 1-2 metres to facilitate access Recommended to permit development
35	Cypress, Lawson variety	6	300	2.5	Fell	Garden ornamental Recommended to permit development
36	Cypress, Lawson variety	7	240	2.5	Fell	Garden ornamental Recommended to permit development
37	Syphonia	15	483	5548	CL5m	Ground protection with allowance for piano CL for working clearance when/when in shading Recommended to permit development
40	Elder	7	241	2422	Fell	A sparser than normal canopy Recommended to permit development
42	Cedarr(C Broadb)	4.5	100	1.5	Fell	Recommended to permit development

Codes:
CB - Cut Back to boundary/below tree structure.

CLF - Crown Lift to given height in meters

CT% - Crown Thinning by identified %.

CCL - Crown Clean remove deadwood/crossing and hazardous branches and stubs

CRW% - Crown Reduce by given maximum % (of outermost branch & twig length)

DWD - Remove deadwood.

Fell - Fell to ground level.

FInv - Further investigation (generally with decay detection equipment)

Pd - Pollard or respollard.

Mon - Monitor ongoing condition (annually by staff / owners & every 2-3 yrs by consultant).

Svr Inv / Cr Br - Sever Inv / clear base and re-inspect base / stem for concealed defects.

Appendix 1. Arboricultural Works

Landmark Trees Ltd Recommended Tree Works To Facilitate Development					
Tel: 0207 851 4544					
Site: 92 FitzJohn's Avenue, London NW3 6NP					
Surveyor(s): James Bell					
Tree No.	English Name	Height	Dia Stem Diameter	Crown Spread	Recommended Works
43	Elder	4	200	2	Fell Ivy smothered Recommended to permit development
44	Cherry Wht (Green)	4.5	220	2322	Fell Ivy smothered Beechroot collar Recommended to permit development

Page

Appendix 2: General Guidelines

- 3.1 All work must be BS 3998:2010 - Recommendations for tree work*.
- 3.2 Staff carrying out the work must be qualified, experienced and ideally be Arboricultural Association approved contractors, and will be covered by adequate public liability insurance.
- 3.3 Any defects seen by a contractor or the client that were not apparent to the consultant must be brought to the consultant's attention immediately.
- 3.4 No liability can be accepted by the consultant in respect of the trees unless the recommendations of the method statements are carried out under the supervision of a Landmark Trees consultant.
- 3.5 It is advisable to have trees inspected by a Landmark Trees consultant regularly. On this site it is recommended that these inspections are made every year.

Notes:

- CB - Cut Back to boundary/clear from structure.
- CLL - Crown Lift to given height in meters.
- CTP% - Crown Thinning by specified %.
- CCl - Crown Clean (remove deadwood/rotting and heartrot branches and stubs).
- CCR% - Crown Care by given maximum % (or outermost branch & twig length).
- DDO - Remove defective.
- Fell - Fall in ground line.
- FIw - Further investigation (generally with decay detection equipment).
- Pal - Pollard or re-pollard.
- Mon - Monitor ongoing condition (annually by staff / owners & every 2-3 yrs by consultant).
- Saw Ivy / Ch Br - Sever ivy / clear base and re-inspect base / stems for concealed defects.

Appendix 4. Indicative pruning guidelines




Site Monitoring Report Sheet

Client:	Planning Ref:	
Local Authority:	Date:	
SIP Number:		
Protocol:		
Valley Checklist	T/F	T/F
Tree protection barrier (TPB) in place	T/F	TPB as per specified
Crown protection (CP) in place	T/F	CP as per specified
TPB / CP breaches		Tree damaged
TPB / CP removed		
TPB / CP breached		
TPB / CP removed		
Comments:		
Recommendations:		
Outcomes:		
1.		
2.		
3.		

Web: www.landmarktrees.co.uk
Email: info@landmarktrees.co.uk
Tel: 0207 851 4544


Landmark Trees is a trading name of Landmark Trees Ltd Registered in Wales Reg No. 330095





NOTE: Branches pruned back to suitable outward pointing bud or small branch.


REDUCING THE CROWN



CROWN LIFTING

Landmark Trees is a trading name of Landmark Trees Ltd Registered in Wales Reg No. 330095
Accredited by ARLA, RICS, FSC, BSI, BIFM, LABC Quality Standard Approved
Project™ is a trademark of Project™ Ltd. All rights reserved.
Previously known as Project™ Ltd, Project™ Ltd is now Landmark Trees Ltd.


Appendix 5. Tree protection plan



Appendix vii
Construction
Management Plan

prepared by
ARUP

Construction Management Plan



Contents		
1	Introduction	1
2	Controlling Environmental Impacts	2
2.1	Segregated Scheme Environmental Aspects	2
2.2	Segregated Scheme Environmental Impacts	4
2.3	Segregated Scheme Environmental Controls	5
3	Programme	7
4	Controlling Highway Impacts	8
4.1	Access to the Development Site and Construction Vehicle Working	8
4.2	Unique Vehicles for Each Construction Phase	10
4.3	Access within the Development Site	10
4.4	Other Transport Considerations	10
5	Conclusion	11
J	Construction Phasing Details	
1	Construction Sequence (Five sheets)	
2	Outline Programme	

1. Construction Planning Details
2. Construction Sequence (live sheet)
3. Schematic Programme

Construction Management Plan

1 Introduction

The purpose of this document is to provide a Construction Management Plan (CMP) for the proposed development at 92 Evelyn's Avenue, London NW1. It is intended the CMP will outline how, based on the current design, the construction phase of the development can be managed in order to mitigate the potential impacts of the works on both neighbours and surrounding road networks. The CMP must be completed with unless otherwise agreed with the Council. The project manager will be responsible for managing the works directly with the Council and relevant parties to ensure, where possible, milestones relating to construction and noise, during the course of the works, the project manager shall review and if necessary make amendment to this CMP to address any issues that may arise. Any future revised plan must be approved in writing by the Council and completed with thereafter.

London Borough of Camden require Construction Management Plans where developments are on constrained sites, in close proximity to schools or car parks, where the construction process will take place over a number of months and where there is very narrow or restricted site access. All of the above conditions apply to the development at 92 Evelyn's Avenue which in broad terms includes the demolition of an existing building and construction of a new residential property with new landscaping.

This Construction Management plan has been produced in accordance with Camden Planning Department LPP 1000, in particular section D, relating to Camden Core Strategy Policy C55 'Managing the impact of proposed development' and in particular development policies DP20 and DP23 ('Assessment of goods and materials' and 'Managing the impact of development on occupiers and neighbours' respectively).

The CMP is split into two elements. The first is focused on controlling environmental aspects, e.g. air quality, dust and other emissions. The second element is traffic control with a view to minimising traffic disruption and avoiding dangerous situations for pedestrians and other road users.


2 Controlling Environmental Impacts

2.1 Significant Scheme Environmental Aspects

Location

The development at 92 Evelyn's Avenue is situated a site bounded to the north by Grosvenor Apartment Block, to the east by the Royal School (Hamstead), to the south by St. Anthony's Primary School, to the southwest by St Anthony's Primary School and to the west by Henderson Court (Age UK Camden Resource Centre) (Figure 1).

It is noted the Royal School (Hamstead) has been renamed North Bridge House School. For the purpose of consistency with drawings and other reports the original name will be used in this document.



Acreage

The site is currently occupied by an existing private road from 91 Evelyn's Avenue, close to its junction with Arundell Road, and this will continue during the construction period.

There will also be an opportunity to access the site from the Royal School site via Victoria Close. The extent of this access and details of the types of vehicles to be used will be confirmed in the final CMP.

Demolition

The existing structures on the site comprise an L-shaped two storey residential property and out houses. The development requires the removal of all structures along with hard and soft landscaping.

Perimeter 35m

To Henderson Court: The existing fence maintained on a low masonry wall will be retained and impacted temporarily during construction of adjacent foundations.

To Grosvenor: The existing masonry wall will be retained and supported horizontally during construction of adjacent structures.

To The Royal School: A new boundary will be created by construction of a reinforced concrete and masonry wall.

In St. Anthony's Primary School grounds, a large temporary retaining wall will be required to support the existing concrete and masonry wall incorporating blocks salvaged from the original wall following its collapse in Summer 2012 where necessary this will be supported with salvaged blocks of a similar type, see Design and Assess Statement for full details.

To St. Anthony's School: The existing boundary will be replaced with a new concrete wall.

Excavations

The lower level ground floor excavation will be formed by demolishing a perimeter wall and creating on main levels up to level of its base slab. Excavation of the side of the excavation or in which the retaining wall is constructed will be halted back although may also be supported by shoring when close to retained trees.

Soil reinforcement

It is anticipated that, subject to final design, the above ground structures will comprise a steel frame with thin concrete slab.

2.2 Significant Scheme Environmental Impacts

The aim of the contractor responsible for the works must be to minimise the environmental impact of the development on surrounding properties, neighbours and the local road network. To this end, and in addition to the measures outlined below, it is recommended they are put to the 'Considerate Construction Scheme' and work within London Borough of Camden's 'Guide to Contractors Working in Camden'.

2.3 Significant Scheme Environmental Controls

The Construction Management Plan is intended to provide a framework upon which detail can be added, mainly due to these being aspects of the works that can

only be confirmed by detailed design and appointment of main contractor and specialist subcontractors (who may employ specialist techniques/equipment).

Given there are details concerning the development that are to be confirmed, the control measures listed below should be seen as minimum requirements.

2.3.1 Hours of Operation

To be agreed with LBC, but generally seen as being at least with industry standards, namely:

• Between 08:00 Monday to Friday, and
• Between 07:00 Saturday.

Exceptional operations (such as crane crossings, demolition and delivery of key plant/staff or excavators) can take place outside of these hours and will be notified to the contractor's project manager. It is not expected that a will be any works on Sunday, however, if any exceptional works are required, the contractor must advise the client in advance.

• Protection of South facing windows above the proposed roof level or roof edge outside of 07:00 to 19:00 hours as long as they are only involved in ground work (LBC Guide to Contractors Working in Camden part 4.1).

2.3.2 Disturbance

Particular attention will be paid to minimising noise and dust. Noise will be limited, where possible, by dismantling rather than breaking (which also prevents the creation of sharp edges) and by using appropriate equipment. Dust will be controlled either by protective break walls or will also minimise noise along with extracting plant operators not to drop loads from height. Dumper cleaning down will be restricted during demolition of the existing structure to minimise dust.

2.3.3 Asbestos

There is potential that asbestos will be present in flat cement property on site and the fact it is an extremely deleterious in the short term period. Attention may be given to features such as chimney stacks, brickwork, floor tiles, fireplaces, and any other potential sources of asbestos (this is not an exhaustive list). The property and out buildings will always require a full asbestos survey prior to demolition, carried out in accordance with the Control of Asbestos Regulation 2012. Any asbestos removal that is necessary must also be carried out in accordance with current legislation.

2.3.4 Noise

The client will be advised of the Henderson Court (Age UK Camden Resource Centre) noise that may well be a concern once during the construction period. While the Council accepts that "all construction and demolition work will result at least some noise and disturbance" (CPG6: Amenity, paragraph 8.2), the contractor is expected to use best practical means and work within the requirements of Part 6

Construction Management Plan

Standard HS 5228, Parts 1, 2 and 4 to minimise noise. This will include although not limited to using well maintained plant, using noise buffers especially in plant such as generators.

The contractor is expected to work with the adjoining schools to establish controls that significantly reduce any nuisance arising from noise during exam periods. This particularly applies to the Royal School Hampton.

2.3.5 Contaminated Land Management

The area occupied by the development plot was a green area or farmland prior to construction of the late current Victorian villa. Therefore significant contamination is not expected on the site although this will need to be confirmed by investigation and/or analysis of excavated material as the works proceed.

2.3.6 Dust

In the early stages of the development phase dust will need to be controlled during ground works and in particular during landscaping. This has been controlled by good housekeeping within the site and monitoring the area of exposed soil, especially during dry, windy weather.

2.3.7 Smoke

There will not be any burning on the site as smoke is not considered to be an issue.

2.3.8 Odour Control

This is not considered to be an issue. Certain types of waterproofing membranes that may be used over low level ground slab may give rise to a requirement for odour control but this will need to be assessed as the design is developed.

2.3.9 Necessity of Adjacent Properties

Foundation and Lower Ground designs are to include provision for temporary supports to the boundary walls during construction of the permanent structures. The current property within the development site has a garage built against the wall to Greenwich to the north and an elevation against the boundary to Elstjohn's Primary School to the south. The contractor is expected to carry out an assessment of these adjacent structures prior to demolition.

The temporary nature of the site means the contractor must ensure that any excavated material is not allowed to compromise adjacent structures or boundary walls.

2.3.10 Vibration

It is not considered there will be any construction techniques employed that will result in excessive or prolonged vibration. The contractor will need to ensure vibration is kept to a minimum by avoiding dropping loads and ideally maintaining flat access ways for tracked vehicles (the movement of which can set up vibrations).

2.3.11 Protection of Listed Buildings

Elstjohn's Primary School is a Grade 2 listed building and approximately 3m from the boundary in the new development. The contractor would be advised to undertake a photographic survey of this and all other adjacent structures prior to start of work.

2.3.12 Protection of Biodiversity and Trees

Refer to the arboricultural impact assessment report prepared by Mactan Landscapes, Tree.

2.3.13 Air Quality and Climate Change Considerations

The contractor will employ best practice to control dust emissions (see 2.3.6 above). The contractor will also apply best practice to control CO₂ and NOx emissions from vehicles and plant. This will include measures such as ensuring drivers/operators have appropriate training, using fuel management plant (including off equipment when not in use, using remote electricity (with appropriate solar) measures for site power supply rather than diesel generators). These techniques will also assist in reducing CO₂ emissions from construction vehicles.

3 Programming

Appendix 1 and 2 contain indicative information relating to the key construction phases required by the developer and an outline construction programme, showing the start date in April 2013 and completed September 2014 as contained in Appendix 1.

I should be noted the final phasing and programme will be dependent on design procurement and any constraints relating to start end dates. Furthermore, some aspects of the works may need to be planned to coincide with school holidays. For reference the adjacent schools have issued the following regarding Easter and Summer holidays:

Holiday	School	Start	End
Easter 2013	Royal School	22 Mar	10 Apr
	Elstjohn's Primary	29 Mar	15 Apr
	St Anthony's School	27 Mar	23 Apr
Summer 2013	Royal School	11 Jul	4 Sept
	Elstjohn's Primary	19 Jul	4 Sept
	St Anthony's School	10 Jul	5 Sep
Easter 2014	Royal School	2 Apr	24 Apr
	Elstjohn's Primary	4 Apr	22 Apr
	St Anthony's School	28 Mar	24 Apr
Summer 2014	Royal School	10 Jul	
	Elstjohn's Primary	23 Jul	
	St Anthony's School	31 Jul	

4 Controlling Highway Traffic

The development site is currently accessed from Elstjohn's Avenue via a private road on the Henderson Court side of St Anthony's School and this will continue to be the point of access for the new property. For a period during the construction there may be the opportunity for construction vehicles to access the site via Vale Close and the Royal School in the east.

4.1 Access to the Development Site and Construction Vehicle Routing

Figure 4 shows the current proposed development route to Transport for London's C17 local distributor along with key London and local distributor roads. From this it can be seen that, at approximately 0.600m, 0.61-0.63 miles, Road 9 (the classic TD9) if accessed using Ardford Road (designated a Major Local Distributor road by LHC), as an alternative to Ardford Road and at a distance of 1.2km, construction traffic could access the site from the A10 at Swiss Cottage using the wider Petropole's Avenue (designated a Major Local Distributor road by LHC).

The ability for larger delivery vehicles, such as concrete mixer trucks, to turnaround within the site will not be available during the later stages of construction. From this point larger vehicles will need to reverse into site under the control of a driver. It is anticipated that vehicles will enter the site in such a manner until there is approach to the north (both North Street free traffic and as proceeding into Ardford Road 90.6 and then reverse into the site entrance).

The shorter route using Major Local Distributor roads between the A10 and Road 9 in Hill Vale Close site access is a distance of 1.2km travelling via Ardford Road, Elstjohn's Avenue and Lyndhurst Road. This compares with a slightly longer distance of 1.96km from Swiss Cottage to Vale Close (using the Major Local Distributor roads below Avenue and Belize Park).

The A10 approaches the other TD9 and within the borough which can be accessed at Archway (5.1km) or more likely to the north of the development at Horsell (4.3km). The latter route would see construction traffic going Northland Way and Hounds Street which would use vehicles that need to reverse into the site.

It is believed there are no low bridge or weight restrictions on any of the routes described above.

Construction Management Plan



4.2 Example Vehicles for Each Construction Phase

See Appendix I

3.3 Access within the Development Site

The development site is approximately 10m x 2.5m in size. Construction will start at the North end of the site with the removal of high quality topsoil. The topsoil will then be transported to the southern edge of the site and the piles are laid out in two distinct levels (as opposed to the general slope currently across the site). This difference in level will influence construction phasing which in turn will impact on access and opportunities for set up and material storage. As a consequence the contractor will plan works to minimise the need for on-site storage i.e. use just in time deliveries.

Vehicles exiting the site onto Fitzjohn's Avenue are expected to be controlled by bollards as will all movements along the private road to the side of St. Anthony Street. When there is no longer space within the development site to turn vehicles, they will be required to turn around on the public highway. In such circumstances the high-street site driver should be in contact to mitigate the problem of restricted rear vision. Larger vehicles extending to or over into the side road will approach from the north (Heath Street).

All deliveries are expected to be off-loaded within the development site with the exception of large items of plant which may be delivered by lorry trailer. These can include specialist piling rigs, mobile tower cranes and excavators. In such cases it is anticipated the plant will be delivered during off peak periods to either Fitzjohn's Avenue or Arkwright road and trucked to the site under the control of a haulier.

4.4 Other Transport Considerations

With the site located well away from Fitzjohn's Avenue it is not anticipated there will be haulage, scaffolding or site accommodation storage adjacent to public highways. Therefore the development is not expected to require any highway works or the impingement of parking bays.

The interface with the public highway will be restricted to vehicles entering and exiting the site which will be under the control of a haulier.

Cross boundary traffic within the site and the length of access to Fitzjohn's Avenue mean there is not expected to be a problem with mud or dirt being deposited on the public highway. While the cleanliness of site access will be the responsibility of the contractor this is not expected to require much, if any, wheel washing.

The contractor is expected to coordinate deliveries with the start and end of the school day so as to minimise disruption to the immediate road network during these very busy periods.

5 Conclusion

Within this Construction Management Plan we have outlined a sequence of constructing for the development of 97 Fitzjohn's Avenue. We have endeavoured to identify the potential impacts of the construction works, along with the means to mitigate their effect on the immediate surroundings. In addition, routes have been identified between the development site and transport for materials and services.

In order for this document to form a working reference through to project completion it will need to be updated, where appropriate, prior to start of the works.

Construction Management Plan

Appendix 1. Phasing information

Appendix 1: Phasing Information

Phase	Works	Dates	Vehicles + Routes	Comments
1	Demolition and site clearance	-	7.5 tonne flat bed trucks width 2.4m (seafold lorries) Roll on roll off skips (similar size to 7.5t trucks) or 15-tonne tipper lorries (2.6m wide). Access via Fitzjohn's Ave with ability to turn vehicles within the site.	Potential opportunity to use some or all of the demolition lorries as temporary hard standings for deliveries and piling equipment
2	Piling for perimeter walls and wall construction	-	Excavators and specialist equipment delivered on low loader located on Fitzjohn's Ave or Ardwright Road. Concrete wagons (2.6m wide) and 15-tonne tipper lorries will access via Fitzjohn's Ave and possibly Vane Close (labc)	
3	Lower ground floor construction	-	Combination of Phase 1 and 2 type vehicles with possible use of small tower crane. Access via Fitzjohn's Ave with ability to turn vehicles within the site. Possible access via Vane Close for works to eastern elevation	Any mobile tower crane used in this stage of construction will need to depart prior to start of Phase 4
4	Retaining wall between upper and lower gardens	-	Excavator with lifting capacity, concrete wagons. Access via Fitzjohn's Ave. Area required for wall construction will reduce opportunities to turn vehicles within site	
5	Upper ground floor	-	As Phase 4. Ability to turn vehicles within site limited to trench on site. Any larger delivery vehicles will need to access the site by reversing in from Fitzjohn's Ave	
6	Superstructure	-	Telescopic telelift truck, articulated dumper, mini digger for landscaping. Concrete can be placed using the forklift although there may be a requirement for use of a static concrete pump located in the entrance to the site. During such an operation access to site will be completely blocked by pump and concrete delivery trucks.	Confirmation required whether the structure is concrete or stick built. Use of pre-fabricated modular panels unlikely due to access issues and lack of space for a crane
7	Landscaping	-	Bulk movements of excavated materials out and new materials in (topsoil / tree soil) will best be completed before loss of access brought about by Phases 4 and 5. Vehicle access to the gardens will come towards the end of Phase 6 with completion of the pad terrace.	
8	Fit out	-	Transit van deliveries with some specialist equipment, such as structural glazing, delivered by 7 Strata. Access from Fitzjohn's Ave	


Construction Management Plan

Appendix 2. Construction sequence



Construction Management Plan


Appendix 2. Construction sequence



Construction Management Plan

Appendix 3. Outline programme

Appendix 3: Outline Programme



make

FITZJOHN'S AVENUE

N.W.3



