



external (escape) stairs to receive extensive re-bonding of existing brick and pre-cast concrete treads that are currently de-bonded, loose and present a trip hazard on these main escape routes from Kennedy Hall.

all bricks and treads to be salvaged complete and re-used in a like-for-like repair using mortar matched to the existing mix for appearance and differential movement reasons.