## **WEIGHT LOADINGS**

## **Project Name:**



**ASQUITH NURSERIES** 

B120436

Specification Build-up	Thickness/ mm	Weight kgs/m <sup>2</sup>
Vapour Barrier - DS1 Duo	3.5	4.3
FA-TE Insulation	140	5.7
Underlayer - KSA DUO	3	3.5
Plant-E	5	6
SDF Mat	20	0.6
XF301 Combination Sedum Vegetation Blanket	33	43.8
System build-up	204.5	
Overall saturated weight in kgs/m <sup>2</sup>		63.9