

SCHEDULE OF WORK

BASEMENT AND FIRST FLOOR **3 PARK VILLAGE WEST, LONDON NW1 4AE**

Basement

- Party garden walls and rear wall of the main house to be underpinned
- Excavation to be carried out to form new basement
- Bedrooms and bathrooms to be formed
- New staircase, to connect to the existing one, to be formed

First Floor

- Existing doors, architraves and windows to be retained.
- Architrave and door to shower room to be moved 200 mm.
- Door between bedroom and master en-suite to be blocked off.
- Door between master bedroom and master en-suite to be formed matching the existing design of the existing doors.
- Door between landing and walking wardrobe to be blocked off.
- Opening between master bedroom and walking wardrobe to be formed.
- All other doors and architraves and cornices to be retained.
-

End.