



Demolition and Excavation: Area in highlighted in tan to be excavated to same level as existing lower ground flat patio. NE steps to be removed or blocked in as part of new retaining wall. Existing brick retaining wall to be removed. Approximately 22 square meters of dirt to be removed . (6475mm X 3500mm X 1000mm). Retaining walls with drainage to be installed.

