



REINFORCEMENT ESTIMATE										
MEMBER	WEIGHT		H8	H10	H12	H16	H20	H25	H32	
CAPPING BEAMS	60kg	PER METRE RUN	10%				15%	90%		
FLOOR BEAMS	60kg	PER METRE RUN	5%					30%	50%	
INTERNAL WALLS	30kg	PER SQUARE METRE			20%		80%			
RETAINING WALLS	95kg	PER SQUARE METRE				45%		55%		
FLOOR SLABS	85kg	PER SQUARE METRE				5%	95%			
COLUMNS	25kg	PER METRE HEIGHT	10%			90%				

PRELIMINARY

C	23.03.12	GARDEN WALL AMENDED.		
B	15.03.12	DRAWING GENERALLY UPDATED.		
A	30.01.12	TITLE BLOCK, UNDERPINNING AND REINFORCEMENT ESTIMATE ADDED.		
Rev	Date	Alteration		
MICHAEL CHESTER & PARTNERS Consulting Civil and Structural Engineers 8 Hale Lane London NW7 3NX tel 020 8959 9119 fax 020 8959 9662		Date DEC 11	Drg No	Rev
		Drawn DM	11015/201	C
		Scale 1:50		
SECTION A		Project 16A LYNDHURST GARDENS LONDON NW3		