

KEY

- 1 layer 15mm Gyproc Duraline
- 15mm plywood inner layer to wall linings

ων

- Gypframe GL8 Track fixed at 600mm centres. Fixing to be removable for future demounting
- Existing masonry of wall lining
- Hard wearing non-slip vinyl flooring.
- Coved vinyl skirting to match floor finish.

8 7 6 5 4

- Linoleum covering and 6mm lipping to front Existing historic door B10A, in elevation. 750 x 16mm Trespa Worktop with 2mm
- 16x40mm Trespa Upstand and side edges.
- 16x40mm Trespa Downstand
- 40x40x2mm Epoxy Coated Bench Tie Rail
- Unit Stop Rail 40x40x2mm Epoxy Coated Bench Support Leg
- Service Space

9 10 10 11 12 12 13 13 14 15 15 16 17 17 19

- Site leveling feet
- Wall batten Water supply
- Air Supply
- Service Trunking

GOWER STREET CHADWICK BUILDING

t: 020 7275 7676 f: 020 7275 9348 w: levittbernstein.co.uk e: post@levittbernstein.co.uk Levitt Bernstein 1 Kingsland Passage London E8 288 Levitt Bernstein

THIS IS NOT A CONSTRUCTION DRAWING, IT IS UNSUITABLE FOR THE PURPOSE OF CONSTRUCTION AND MUST ON NO ACCOUNT BE USED AS SUCH.

revisionsT1 21.03.12

ssued for tender.

date FEB 12

c≣ent UCL

drawn checked drawing number ED TL 2964 A_501 scale drawing
AS NOTED@A3 WALL DETAILS - SHEET 2 OF 2

⊒ ē