

George Plakides  
Projects Manager  
Royal Free Hospital  
Service Floor  
Pond Street  
London  
NW3 2QG

01 December 2011

## QUOTATION

**Ref** Queen Marys **Tree works**

Item	Species	Works Description	Sub-total	Total
<u>See Map</u>				
7.0	Bay	Crown reduce 30% and shape. Prune to clear building by 2m.	490.00	
8.0	Bay	Poor condition. Dead stem. Fell to ground level to coppice.	540.00	
16.0	Privet	GMS11 (See below for description)	30.00	
19.0	Lime	GMS1 (See below for description). Prune to clear building by 3m	310.00	
20.0	Elder	Fell to ground level and treat stump to prevent regrowth.	160.00	
21.0	Sycamore	GMS1 (See below for description). Prune to clear building by 3m	280.00	
22.0	Sycamore	Reduce height of Ivy to 4m. Crown thin 10% and remove major deadwood >50mm. Judiciously prune back overhang to neighbours by 25%.	790.00	
23.0	Horse Chestnut	Reduce height of Ivy to 4m. Crown thin 10% and remove major deadwood >50mm. Judiciously prune back overhang to neighbours by 25%. Remove trunk epicormics.	780.00	
			<hr/> 3,380.00	3,380.00
Total amount excluding Vat				<hr/> 3,380.00
Vat at 20%				<hr/> 676.00
Grand total including Vat				<hr/> <hr/> 4,056.00

### GMS1

#### General Maintenance Schedule: Mature Trees

To include the following:

- i) Remove deadwood, stubs and broken or crossing branches
- ii) Remove epicormic growth throughout crown and basal suckers
- iii) Raise canopies to statutory height over carriageways and pedestrian areas as applicable
- iv) Reduce from properties, street furniture and telephone cables etc. to give 2-3m clearance as applicable