

DAYLIGHT AND SUNLIGHT REPORT

43 GRAYS INN ROAD

Prepared by: GIA

Reference: 6349

Date: 7th December 2011



CONTENTS PAGE

CLIENT: AWW Architects

ISSUE DATE: 7th December 2011

DOCUMENT REFERENCES: 6349-rol-bh-11-1207-mr(DaySun Report)
Principles of Daylight and Sunlight
6349/01, 02, 03, 04, 05, 06 (Rel 01)
Tables of Results: VSC/ADF/DD/APSH (Rel 20)

AUTHOR FOR AND BEHALF OF GIA: Barry Hood

AUTHORISATION FOR GIA :

This report is intended solely for AWW Architects and may contain confidential information. The Liability of this Report extends to AWW Architects and their duly appointed advisors. No part or whole of its contents may be disclosed to or relied upon by any Third Parties without the consent of this Practice. This report is accurate as at the date of publication but does not take into account anything that has happened since the date of this report.

CONTENTS		PAGE
1.0	INSTRUCTIONS	1
2.0	INTRODUCTION	1-2
3.0	SOURCES OF INFORMATION	2
4.0	ASSUMPTIONS	3
5.0	THE SITE	3
6.0	THE PROPOSAL	4
7.0	SURROUNDING PROPERTIES	4-7
8.0	CONCLUSIONS	7

~~~~~

|                   |   |                                                |
|-------------------|---|------------------------------------------------|
| <i>APPENDIX 1</i> | - | <i>PRINCIPLES OF DAYLIGHT AND SUNLIGHT</i>     |
| <i>APPENDIX 2</i> | - | <i>EXISTING AND PROPOSED DRAWINGS</i>          |
| <i>APPENDIX 3</i> | - | <i>DAYLIGHT AND SUNLIGHT TABLES OF RESULTS</i> |

## 1.0 INSTRUCTIONS

You have instructed this Practice to provide you with a technical survey based analysis in respect of the daylight and sunlight implications of the proposed scheme at the 43 Gray's Inn Road site to the surrounding properties and the daylight and sunlight amenity within the proposed accommodation.

## 2.0 INTRODUCTION

### ***DAYLIGHT AND SUNLIGHT***

In considering the development potential and the quality of amenity for the surrounding properties once the scheme has been implemented, the analysis is based upon the Building Research Establishment (BRE) guidelines '***Site Layout Planning for Daylight and Sunlight***' which provides the criteria and methodology for calculation in connection with daylight and sunlight. This handbook is the primary authority for this matter and therefore it is not only this Practice, but also the Local Authority, who will be considering your application by reference to these guidelines.

The BRE guidelines provide three main methods of calculation for daylight. The first is known as the Vertical Sky Component (VSC) method which considers the potential for daylight by calculating the angle of vertical sky at the centre of each of the windows serving the residential buildings which look towards the site. This is a more simplistic approach and it could be considered as a "rule of thumb" to highlight whether there are any potential concerns to the amenity serving a particular property.

The second method is the No Sky Line or Daylight Distribution method.

This simply assesses the change in position of the No Sky Line between the existing and proposed situations. It does take into account the number and size of windows to a room, but still does not give any qualitative or quantitative assessment of the light in the room, only where sky can or cannot be seen.

The third method of calculation is the Average Daylight Factor (ADF). This is a more detailed and thus more accurate method which considers not only the amount of sky visibility on the vertical face of the window, but also the window size, room size and room use.

Where dimensions of the room to be assessed are available this is the best method of assessment, but even where they are not, it provides a very informative result. It gives guidance as to the qualitative and quantitative change in daylight and is related to the British Standard BS 8206 Part II.

In relation to sunlight, the criteria given calculates the annual probable sunlight hours (APSH) which considers the amount of sun available in both the summer and winter for each given window which faces within 90° of due south. Summer is considered to be the six months between March 21<sup>st</sup> and September 21<sup>st</sup> and winter the remaining months.

### **3.0 SOURCES OF INFORMATION**

#### **GIA**

Partial Site Survey  
Site Photographs  
Aerial Photographs  
OS Map

#### **VALUATION OFFICE AGENCY**

Property Usage

#### **AWW ARCHITECTURE**

Proposed Scheme Dated 14<sup>th</sup> November 2011  
Drawing Nos: 2957-2200-2208, 1001, 2210-2218

#### **LONDON BOROUGH OF CAMDEN TOWN AND PLANNING**

Proposed Drawings for 5 Kings Mews

#### **PURCELL MILLER TRITTON**

Proposed Drawings for 5 King's Mews

#### **HEBERT PERCY AND PARKER ARCHITECTS**

Proposed Drawings for 7 & 8 King's Mews

## 4.0 ASSUMPTIONS

1. A partial site survey has been made available, however, due to the complexity of the site and difficulty in gaining access, this does not cover all neighbouring elevations completely and therefore it has been necessary to indicatively model, from photographs, the windows which were beyond the scope of the survey. This is satisfactory where there is a need to understand the light sensitivity of rooms served by these windows. However, more accurate information should be sought if this indicative analysis indicates that the rooms are in fact vulnerable to small changes in the light.
2. We have not sought or obtained access to any of the adjoining properties and therefore have made reasonable assumptions as to the internal layouts of the rooms behind the fenestration. This is normal practice where access to adjoining properties is undesirable in terms of development confidentiality. Unless the building form dictates otherwise, we assume a standard 4.2m deep room (14ft) for residential properties and the 6m (20ft) deep from for commercial properties.
3. Floor levels have been assumed for adjoining properties as access has not been obtained. This dictates the level of the working plane which is the point at which rights of light assessments are carried out. It is also relevant for the No Sky Line and ADF daylight assessments.
4. We have made best estimates as to the uses which are carried out legally within the adjoining properties in terms of commercial and residential. We have estimated these from external observation and the uses are identified in the report below.

## 5.0 THE SITE

The site comprises 43 Grays Inn Road which is currently a 4 storey commercial property.

Our understanding of the existing building on the site is depicted in drawings 6349/01, 02 and 03 which can be found within Appendix 2.

## 6.0 THE PROPOSAL

The proposed scheme involves an increase in the massing by 1 extra storey which is set back on the Grays Inn Road elevation.

Our understanding of the AWW Architecture proposal is depicted in drawings 6349/04, 05 and 06 which can be found within Appendix 2.

## 7.0 SURROUNDING PROPERTIES

The majority of neighbouring buildings are commercial in usage or light industrial warehouses and have been omitted from technical analysis due to their expectation for natural light and reliance upon artificial light. There are a number of residential properties in the vicinity and the surrounding properties material for consideration are:

**51 GRAY'S INN ROAD**

**49 GRAY'S INN ROAD**

**47 GRAY'S INN ROAD**

**41 GRAY'S INN ROAD**

**39 GRAY'S INN ROAD**

**37 GRAY'S INN ROAD**

**35 GRAY'S INN ROAD**

**4 – 10 THEOBALDS ROAD**

**12 THEOBALDS ROAD**

**1 KING'S MEWS**

**2 – 4 KING'S MEWS**

**5 KING'S MEWS**

**7 – 8 KING'S MEWS**

**9 – 11 KING'S MEWS**

**12 – 13 KING'S MEWS**

**144 – 148 GRAY'S INN ROAD**

To deal with these properties in turn, I will begin in the north and move clockwise.

### **51 GRAY'S INN ROAD**

It is our understanding that this property at first floor and above, residential usage and enjoys a rear terrace to the west of the building which contains a glass conservatory.

In daylight terms and for planning purposes, this property will experience no alteration in its daylight or sunlight and all windows comply with the BRE Guidelines. It will therefore be BRE compliant for daylight and sunlight matters.

### **49 GRAY'S INN ROAD**

All rooms relating to residential accommodation will experience no alteration in their daylight and sunlight and all windows comply with the BRE Guidelines in relation to sunlight. Therefore this property will be BRE compliant in daylight and sunlight terms.

#### **47 GRAY'S INN ROAD**

It is our understanding that this property at first floor and above relates to residential usage, the rear elevation contains windows.

There is either no change to the daylight enjoyed by this property or a tiny and imperceptible alteration which is entirely BRE compliant. There is no change in sunlight.

This property is entirely BRE compliant.

#### **41 GRAY'S INN ROAD**

It is our understanding that this property at first floor and above is in residential usage, the rear elevation contains windows.

It has been possible to obtain floor layout plans for 41 Gray's Inn Road which confirms that only one of the windows which face the development site is considered material for consideration in daylight and sunlight terms. I.e. the majority of windows serve circulation space, bathrooms or WC's. The one room material for consideration serves a kitchen, and the daylight to this room is not altered beyond the level considered acceptable by the BRE Guidelines. This building will therefore be BRE compliant in daylight terms.

The same holds true for Sunlight with the one window material for consideration serving a kitchen and this room will retain an APSH of 47% for the whole year, against a target value of 25% as set down in the BRE Guidelines.

This property will therefore be BRE compliant in terms of daylight and sunlight.

#### **39 GRAY'S INN ROAD**

It is our understanding that this property at first floor and above is in residential usage, the rear elevation contains windows.

It has been possible to obtain floor layout plans for the residential floors of 39 Gray's Inn Road which confirm that only two of the windows which face the development site are considered material for consideration in daylight and sunlight terms.

All windows and rooms material for consideration will comfortably satisfy BRE Guidance and are either entirely unaffected for barely affected by the scheme proposal in both daylight and sunlight terms.

This property will be BRE compliant in terms of daylight and sunlight.

### **37 GRAY'S INN ROAD**

It is our understanding that this property at first floor and above is in residential usage, the rear elevation contains windows.

The property is barely affected in daylight and sunlight terms and entirely BRE compliant.

### **35 GRAY'S INN ROAD**

It is our understanding that this property at first floor and above is in residential usage, the rear elevation contains windows.

The property is barely affected in daylight and sunlight terms and entirely BRE compliant.

### **4 – 10 THEOBALDS ROAD**

It is our understanding that this property at first floor and above relates to residential usage, the rear elevation contains windows.

This property lies to the south of the site and consists of a lightwell punctuated by three columns of windows. Whilst the measured site survey did not extend this far due to restrictions in terms of visibility, it has been possible to understand the location of windows in this area and room usage, based upon a site inspection from a vantage point on a neighbouring adjacent terrace and therefore create a detailed indicative model.

This property is entirely unaffected in daylight and sunlight terms and is therefore BRE compliant.

### **12 THEOBALDS ROAD**

The Local Planning Authority (LPA) is unlikely to be concerned with daylight and sunlight matters and commercial buildings, thus we have not assessed this building.

### **1 KING'S MEWS**

The Local Planning Authority (LPA) is unlikely to be concerned with daylight and sunlight matters and commercial buildings, thus we have not assessed this building.

### **2 – 4 KING'S MEWS**

The property is barely affected in daylight terms and entirely BRE compliant.

This elevation does not face within 90° of due south and is therefore not material for consideration in sunlight terms.

### **5 KING'S MEWS**

The property is barely affected in daylight terms and entirely BRE compliant.

None of the windows within this property face within 90° of due south and therefore are necessary to consider in sunlight terms.

### **7 – 8 KING'S MEWS**

The property is barely affected in daylight and sunlight terms and entirely BRE compliant.

### **9 – 11 KING'S MEWS**

The rear of this property appears to be in commercial usage and is therefore not material for consideration in BRE terms for daylight and sunlight compliance.

### **12 – 13 KING'S MEWS**

At first floor, there are rooms within this property which could potentially be within residential usage, though it is more likely that they are actually ancillary to the commercial use below. However, for sake of completeness, we have considered these in daylight and sunlight terms. Both rooms within this property will comply with the BRE Guidelines in terms of daylight.

### **144 – 48 GRAY'S INN ROAD – TEST WINDOWS**

We have inserted test windows in this block for the sake of completeness.

At ground floor, this mansion block is in commercial/retail usage, with the area below the test windows in use by the Sevenoaks Sound and Vision retail company. The floors above are divided into residential apartments and we have placed test windows within these properties to ensure that daylight and sunlight compliance is possible.

In relation to daylight, all rooms are able to meet and satisfy the daylight criteria as stipulated by the BRE Guidelines and all are able to satisfy the sunlight criteria too. This building will therefore continue to be BRE compliant, notwithstanding the proposed scheme being constructed.

## **8.0 CONCLUSIONS**

The proposed scheme implies universal BRE compliance in daylight and sunlight terms for all neighbouring residential properties. The majority of buildings are entirely unaffected and where there is some small change in daylight this will not be perceptible to the occupier.

# APPENDIX 1

PRINCIPLES OF DAYLIGHT AND SUNLIGHT

---

## PRINCIPLES OF DAYLIGHT AND SUNLIGHT

---

### BACKGROUND

The quality of amenity for buildings and open spaces is increasingly becoming the subject of concern and attention for many interested parties.

Historically the Department of Environment provided guidance of these issues and, in this country, this role has now been taken on by the Building Research Establishment (BRE), the British Standards Institution (BSI) and the Chartered Institute of Building Services Engineers (CIBSE). Fortunately they have collaborated in many areas to provide as much unified advice as possible in these areas.

Further emphasis has been placed on these issues through the European Directive that require Environmental Impact Assessments (EIA's) for large projects. Part of these assessments include the consideration of the micro-climate around and within a proposal. The EIA requires a developer to advise upon, amongst other matters, the quality of and impact to daylight, sunlight, overshadowing, solar glare and light pollution.

It is also clear, particularly through either adopted or emerging Unitary Development Plans (UDP's), that local Authorities take this matter far more seriously than they previously did. There are many instances of planning applications being refused due to impact on daylight and sunlight to neighbouring properties and proportionately more of these refusals are appealed by applicants.

Where developers are seeking to maximise their development value, it is often in the area of daylight and sunlight issues that they may seek to 'push the boundaries'. Local Authorities vary in their attitude of how flexible they can be with worsening the impact on the amenity enjoyed by neighbouring owners. In city centres, where there is high density, it can be the subject of hot debate as to whether further loss of amenity is material or not. There are many factors that need to be taken into account and therefore each case has to be considered on its own merits. Clearly, though, there are governing principles which direct and inform on the approach that is taken.

These principles are effectively embodied within the UDP's and the guidance they expressly rely upon. For example, in central London, practically all of the Local Authorities expressly state they will not permit or encourage developments which create a material impact to neighbouring buildings or amenity areas. Often the basis on what is constituted as 'material' will be derived specifically from the BRE Guidelines. The guidelines were produced in 1991, as a direct commission from the Department of the Environment, and entitled 'Site Layout Planning for Daylight and Sunlight – A Guide to Good Practice'.

These guidelines are normally the only official document used by local Authorities and consequently they are referred to extensively by designers, consultants and planners. Whilst they are expressly not mandatory and state that they should not be used as an instrument of planning policy, they are heavily relied upon as they advise on the approach, methodology evaluation of impact in daylight and sunlight matters.

## **THE BRE GUIDELINES**

The BRE give criteria and methods for calculating daylight, and sunlight and to some degree overshadowing and through that approach define what they consider as a material impact. As these different methods of calculation vary in their depth of analysis, it is often arguable as to whether the BRE definition of 'material' is applicable in all locations and furthermore if it holds under the different methods of calculation.

As the majority of the controversial daylight and sunlight issues occur within city centres these explanatory notes focus on the relevant criteria and parts of the Handbook which are applicable in such locations.

In the Introduction of 'Site Layout Planning for Daylight and Sunlight' it states that:-

*"The guide is intended for building designers and their clients, consultants and planning officials. The advice given here is not mandatory and this document should not be seen as an instrument of planning policy. Its aim is to help rather than constrain the designer. Although it gives numerical guidelines, these should be interpreted flexibly because natural lighting is only one of many factors in site layout design (see Section 5). In special circumstances the developer or Planning Authority may wish to use different target values. For example, in an historic city centre a higher degree of obstruction may be unavoidable if new developments are to match the height and proportions of existing buildings".*

Again, the second paragraph of Chapter 2.2 of the document states:-

*'Note that numerical values given here are purely advisory. Different criteria may be used, based on the requirements for daylighting in an area viewed against other site layout constraints'.*

The reason for including these statements in the Report is to appreciate that when quoting the criteria suggested by the BRE, they should not necessarily be considered as appropriate. However, rather than suggest alternative values, consultants in this field often remind local Authorities that this approach is supportable and thus flexibility applied.

## **MEASUREMENT AND CRITERIA FOR DAYLIGHT & SUNLIGHT**

The BRE handbook provides two main methods of measurement for calculating daylight which we use for the assessment in our Reports. In addition, in conjunction with the BSI and CIBSE it provides a further method in Appendix C of the Handbook. In relation to sunlight only one method is offered for calculating sunlight availability for buildings. There is an overshadowing test offered in connection with open spaces.

### **DAYLIGHT**

In the first instance, if a proposed development falls beneath a 25° angle taken from a point two metres above ground level, then the BRE say that no further analysis is required as there will be adequate skylight (i.e. sky visibility) availability.

The three methods for calculating daylight are as follows:

- (a) Vertical Sky Component (VSC)
- (b) No Sky Contours (NSC)
- (c) Average Daylight Factor (ADF)

Each are briefly described below.

#### **(a) Vertical Sky Component**

##### Methodology

This is defined in the Handbook as:-

*"Ratio of that part of illuminance, at a point on a given vertical plane, that is received directly from a CIE Standard Overcast Sky, to illuminate on a horizontal plane due to an unobstructed hemisphere of this sky."*

*"Note that numerical values given here are purely advisory. Different criteria may be used, based on the requirements for daylighting in an area viewed against other site layout constraints".*

The ratio referred to in the above definition is the percentage of the total unobstructed view that is available, once obstructions, in the form of buildings (trees are excluded) are placed in front of the point of view. The view is always taken from the centre of the outward face of a window.

This statement means, in practice, that if one had a totally unobstructed view of the sky, looking in a single direction, then just under 40% of the complete hemisphere would be visible.

The measurement of this vertical sky component is undertaken using two indicators, namely a skylight indicator and a transparent direction finder. Alternatively a further method of measuring the vertical sky component, which is easier to understand both in concept and analysis, is often more precise and can deal with more complex instructions, is that of the Waldram diagram.

The point of reference is the same as for the skylight indicator. Effectively a snap shot is taken from that point of the sky in front of the window, together with all the relevant obstructions to it, i.e. the buildings.

An unobstructed sky from that point of reference would give a vertical sky component of 39.6%, corresponding to 50% of the hemisphere, and therefore the purpose of the diagram is to discover how much sky remains once obstructions exist in front of that point.

The diagram comes on an A4 sheet (landscape) and this sheet represents the unobstructed sky, which in one direction equates to a vertical sky component of 39.6%. The obstructions in front of a point of reference are then plotted onto the diagram and the resultant area remaining is proportional to the vertical sky component from that point.

### Criteria

The BRE Handbook provides criteria for:

- (a) New Development
- (b) Existing Buildings

A summary of the criteria for each of these elements is given and these are repeated below:-

## New Development

### *Summary*

*In general, a building will retain the potential for good interior diffuse daylighting provided that on all its main faces:-*

- (a) no obstruction, measured in a vertical section perpendicular to the main face, from a point 2m above ground level, subtends an angle of more than 25 degrees to the horizontal;*
- (b) If (a) is not satisfied, then all points on the main face on a line 2m above ground level are within 4m (measured sideways) of a point which has a vertical sky component of 27% or more.*

## Existing Buildings

### *Summary*

*If any part of a new building or extension measured in a vertical section perpendicular to a main window wall of an existing building, from the centre of the lowest window, subtends an angle of more than 25 degree to the horizontal, then the diffuse daylighting of the existing building may be adversely affected. This will be the case if either:*

- (a) the vertical sky component measured at the centre of an existing main window is less than 27%, and less than 0.8 times its former value;*
- or*
- (b) the area of the working plane in a room which can receive direct skylight is reduced to less than 0.8 times its former value.*

The VSC calculation has, like the other two methods, both advantages and disadvantages. In fact they are tied together. It is a quick simple test which looks to give an early indication of the potential for light. However, it does not, in any fashion, indicate the quality of actual light within a space. It does not take into account the window size, the room size or room use. It helps by indicating that if there is an appreciable amount of sky visible from a given point there will be a reasonable potential for daylighting.

**(b) No Sky Contours**

This is the part (b) of the alternative method of analysis which is given under the Vertical Sky Component heading in this Appendix. It is similar to the VSC approach in that a reduction of 0.8 times in the area of sky visibility at the working plane may be deemed to adversely affect daylight. It is however, very dependent upon knowing the actual room layouts or having a reasonable understanding of the likely layouts. The contours are also known as daylight distribution contours. They assist in helping to understand the way the daylight is distributed within a room and the comparisons of existing and limitations of proposed circumstances within neighbouring properties. Like the VSC method, it relates to the amount of visible sky but does not consider the room use in its criteria, it is simply a test to assess the change in position of the No Sky Line, between the existing and proposed situation. It does take into account the number and size of windows to a room, but does not give any quantitative or qualitative assessment of the light in the rooms, only where sky can or cannot be seen.

**(c) Average Daylight Factor**

This is defined in Appendix H of the BRE Document as:

*“Ratio of total daylight flux incident on the working plane, expressed as a percentage of the outdoor illuminance on a horizontal plane due to an unobstructed CIE Standard Overcast Sky.”*

This factor considers interior daylighting to a room and therefore is a more accurate indication of available light in a given room, if details of the room size and use are available.

Criteria

The British Standard, BS8206 Part II gives the following recommendations for the average daylight factor (ADF) in dwellings.

The BRE Handbook provides the formula for calculating the average daylight factor. If the necessary information can be obtained to use the formula then this criteria would be more useful.

| <b>Room</b>  | <b>Percentage</b> |
|--------------|-------------------|
| Kitchen      | 2%                |
| Living Rooms | 1.5%              |
| Bedrooms     | 1%                |

It is sometimes questioned whether the use of the ADF is valid when assessing the impact on neighbouring buildings. Firstly, it is often the case that room layouts and uses may not have been established with certainty. Additionally this method is not cited in the main body of text in the BRE Guidelines but only in Appendix C of that document. It is however, the principal method used by both the British Standard and CIBSE in their detailed daylight publications with which the BRE guide recommends that it should be read.

The counter-argument to this view is that whilst room uses and layouts may be not definitely established, reasonable assumptions can easily be made to give sufficient understanding of the likely quality of light. Building types and layouts for certain buildings, particularly residential, are often similar. In these circumstances reasonable conclusions can be drawn as to whether a particular room will have sufficient light against the British Standards. In addition, the final result is less sensitive to changes in the room layout than the No Sky Contour method as it is an average and this element represents only one of the input factors. It is in cases where rooms sizes have been assumed a more reliable indicator than the No Sky Line method.

Clearly if a room which is being designed for a new development is deemed to have sufficient light against the British Standards, then it should equally follow for a room assessed in a neighbouring existing building.

The average daylight factor considers the light within the room behind the fenestration which serves it. The latter is therefore likely to be more accurate because it takes into account the following:-

- a) All the windows serving the room in question.
- b) The room use.
- c) The size and layout of the room.
- d) The finishes of the room surfaces.

## **SUMMARY**

The VSC (which forms part of the ADF formula) is helpful as an initial first guide, especially where access to the rooms in question is not available. Where the room layouts and uses are established or can be reasonably estimated we consider it appropriate to analyse the average daylight factor as well as the vertical sky component.

## SUNLIGHT

### (a) Annual Probable Sunlight Hours (APSH) method

Sunlight is measured in the Handbook in a similar manner to the first method given for measuring the VSC.

A separate indicator is used which contains 100 spots, each representing 1% of annual probable sunlight hours.

The BRE calculated that where no obstructions exist, the total annual probable sunlight hours would amount to 1486. Therefore, each dot on the indicator equates to 14.86 hours of the total annual probable sunlight. Again, to use this indicator the obstructions need to be scaled down and overlaid onto the sunlight indicator.

Those spots which remain uncovered by the scaled obstructions are counted and this gives the percentage of total annual probable sunlight hours for that particular reference point. Again, like the VSC, the reference point is taken to be the centre of the window.

#### Criteria

Again, the BRE Handbook gives criteria for:

- (a) New Development
- (b) Existing Buildings

A summary is given in the handbook on page 12 and this is as follows:-

#### New Development

##### *Summary*

*In general, a dwelling or non-domestic building which has a particular requirement for sunlight, will appear reasonably sunlit provided that:*

- (a) *at least one main window wall faces within 90 degrees of due south;*

*and*

- (b) *on this window wall, all points on a line 2m above ground level are within 4m (measured sideways) of a point which receives at least a quarter of annual probable sunlight hours, including at least 5% of annual probable sunlight hours during the winter months, between 21 September and 21 March.*

### Existing Buildings

#### *Summary*

*If a living room of an existing dwelling has a main window facing within 90 degrees of due south, and any part of a new development subtends an angle of more than 25 degrees to the horizontal measured from the centre of the window in a vertical section perpendicular to the window, then the sunlighting of the existing dwelling may be adversely affected. This will be the case if a point at the centre of the window, in the plane of the inner window wall, receives in the year less than one quarter of annual probable sunlight hours including at least 5% of annual probable sunlight hours between 21 September and 21 March and less than 0.8 times its former sunlight hours during either period.*

It will be noted that the BRE clearly separate summer from winter and indicate that a 20% reduction for either may be material. The Handbook also states that *“To find out whether an existing building still receives enough sunlight, the British Standard can be used. It is suggested that all main living rooms of dwellings and conservatories, should be checked if they have a window facing within 90° of due south. Kitchens and bedrooms are less important, although care should be taken not to block too much sun ..... The British Standard recommends that a ‘window reference point’, at the centre of each window on the plane of the inside surface of the wall, should be used for the calculations”* and thus this practice gives greater consideration to the effect on the main window of a living room.

#### **(b) Area of Permanent Shadow**

The BRE Handbook, ‘Site Layout Planning for Daylight and Sunlight’ also provides criteria for open spaces.

In particular it gives guidance for calculating any areas of open space that may be in permanent shadow on 21 March. There is no criteria for the overshadowing of buildings.

In summary the BRE document states the following:-

*“It is suggested that, for it to appear adequately sunlit throughout the year, no more than two-fifths and preferably no more than a quarter of any garden or amenity area should be prevented by buildings from*

*receiving any sun at all on 21 March. If, as a result of new development, an existing garden or amenity area does not meet these guidelines, and the area which can receive some sun on 21 March is less than 0.8 times its former value, then the loss of sunlight is likely to be noticeable”.*

In relation to general overshadowing we often provide, where appropriate, an hourly record for existing and proposed situations, the effect of overshadowing on December 21<sup>st</sup>, March 21<sup>st</sup> and June 21<sup>st</sup>.

For open spaces the permanent shadow criteria is naturally adopted but this offers limited understanding of how a space will feel or appear generally.

## **CITY CENTRES**

The introduction of the BRE document gives the example of 'historic city centres' being a case where there is the need for flexibility and altering the target values for criteria when appropriate, to reflect other site and layout constraints.

To explain why it is appropriate to alter these values, one needs to go further into the BRE Handbook to examine how the criteria for the vertical sky component criteria was determined and the reason therefore for varying the criteria in City Centres.

Appendix G of the document is dedicated to the use of alternative values and, it also demonstrates the manner in which the criteria for skylight was determined for the Summary given above, i.e. the need for 27% vertical sky component for adequate daylighting.

This figure of 27% was achieved in the following manner:

A theoretical road was created with two storey terraced houses upon either side, approximately twelve metres apart. The houses have windows at ground and first floor level, and a pitched roof with a central ridge.

Thereafter, a reference point was taken at the centre of a ground floor window of one of the properties and a line was drawn from this point to the central ridge of the property on the other side of the road. The angle of this line equated to 25 degrees (the 25 degrees referred to in the summaries given with reference to the criteria for skylight).

This 25 degrees line obstructs 13% of the totally unobstructed sky available, leaving a resultant figure of 27% which is deemed to give adequate daylighting. This figure of 27% is the recommended criteria referred to earlier in this report. It will be readily appreciated that in a City Centre, this kind of urban form is unlikely and is

impractical. It would therefore be inappropriate to consider values for two storey terraced housing in a City Centre.

It is therefore sometimes necessary to apply different target criteria or at least acknowledge that the recommendations in the BRE cannot be achieved.

In addition, it is often the case that residential buildings within city centres are served by balconies. Balconies restrict lighting levels even more and thus if they were to be rigidly taken into account, a neighbouring proposal would be artificially and inappropriately constrained. This view is supported by the BRE and is equally another reason for flexible and sensible interpretation of the guidelines.

# APPENDIX 2

EXISTING AND PROPOSED DRAWINGS





Sources of Information

GIA  
 Partial Site Survey  
 Site Photographs

PURCELL MILLER TRITTON  
 Proposal Drawings for 5 King's Mews

HEBER PERCY & PARKER ARCHITECTS  
 Proposal Drawings for 7&8 King's Mews

BRANSON COATES ARCHITECTURE  
 2-4 Kings Mews Plans

AWW ARCHITECTURE  
 43 Gray's Inn Road scheme dated 14-11-11  
 Dwgs Nos. 2957-2200-2208, 1001, 2210-2218

Notes

Existing Development  
 ALL HEIGHTS GIVEN IN mm AOD

| Rev | Date | Description   | Initials |
|-----|------|---------------|----------|
| A   |      | Initial Issue |          |
|     |      |               |          |
|     |      |               |          |
|     |      |               |          |
|     |      |               |          |
|     |      |               |          |

Project  
 43 GRAY'S INN ROAD  
 LONDON WC1

Title  
 SITE PLAN  
 EXISTING BUILDINGS

Scale  
 1:500 @A3

Date  
 DEC 11

Drawn  
 SL

Checked  
 -


Drawing No.  
 6349/1

Rel No.  
 1

Revision  
 A

**gia**

The Whitehouse  
 Belvedere Road  
 London SE1 8GA  
 t 020 7202 1400  
 f 020 7202 1401  
 mail@gia.uk.com  
 www.gia.uk.com



Sources of Information

GIA  
 Partial Site Survey  
 Site Photographs

PURCELL MILLER TRITTON  
 Proposal Drawings for 5 King's Mews

HEBER PERCY & PARKER ARCHITECTS  
 Proposal Drawings for 7&8 King's Mews

BRANSON COATES ARCHITECTURE  
 2-4 Kings Mews Plans

AWW ARCHITECTURE  
 43 Gray's Inn Road scheme dated 14-11-11  
 Dwgs Nos. 2957-2200-2208, 1001, 2210-2218

Notes

Existing Development  
 ALL HEIGHTS GIVEN IN mm AOD

| Rev | Date | Description   | Initials |
|-----|------|---------------|----------|
| A   |      | Initial Issue |          |
|     |      |               |          |
|     |      |               |          |
|     |      |               |          |
|     |      |               |          |

Project  
 43 GRAY'S INN ROAD  
 LONDON WC1

Title  
 3D VIEW  
 EXISTING BUILDINGS

Scale  
 N/S @A3

Date  
 DEC 11

Drawn  
 SL

Checked  
 -


Drawing No. 6349/2

Rel No. 1

Revision A



The Whitehouse  
 Belvedere Road  
 London SE1 8GA  
 t 020 7202 1400  
 f 020 7202 1401  
 mail@gia.uk.com  
 www.gia.uk.com



Sources of Information

GIA  
 Partial Site Survey  
 Site Photographs

PURCELL MILLER TRITTON  
 Proposal Drawings for 5 King's Mews

HEBER PERCY & PARKER ARCHITECTS  
 Proposal Drawings for 7&8 King's Mews

BRANSON COATES ARCHITECTURE  
 2-4 Kings Mews Plans

AWW ARCHITECTURE  
 43 Gray's Inn Road scheme dated 14-11-11  
 Dwgs Nos. 2957-2200-2208, 1001, 2210-2218

Notes

Existing Development  
 ALL HEIGHTS GIVEN IN mm AOD

| Rev | Date | Description   | Initials |
|-----|------|---------------|----------|
| A   |      | Initial Issue |          |
|     |      |               |          |
|     |      |               |          |
|     |      |               |          |
|     |      |               |          |
|     |      |               |          |

Project  
 43 GRAY'S INN ROAD  
 LONDON WC1

Title  
 3D VIEW  
 EXISTING BUILDINGS


Scale  
 N/S @A3 Date  
 DEC 11

Drawn  
 SL Checked  
 -

Drawing No. Rel No. Revision  
 6349/3 1 A

**gia**  
 The Whitehouse  
 Belvedere Road  
 London SE1 8GA  
 t 020 7202 1400  
 f 020 7202 1401  
 mail@gia.uk.com  
 www.gia.uk.com





Sources of Information

GIA  
 Partial Site Survey  
 Site Photographs

PURCELL MILLER TRITTON  
 Proposal Drawings for 5 King's Mews

HEBER PERCY & PARKER ARCHITECTS  
 Proposal Drawings for 7&8 King's Mews

BRANSON COATES ARCHITECTURE  
 2-4 Kings Mews Plans

AWW ARCHITECTURE  
 43 Gray's Inn Road scheme dated 14-11-11  
 Dwgs Nos. 2957-2200-2208, 1001, 2210-2218

Notes

Proposed scheme

| Rev | Date | Description   | Initials |
|-----|------|---------------|----------|
| A   |      | Initial Issue |          |
|     |      |               |          |
|     |      |               |          |
|     |      |               |          |
|     |      |               |          |
|     |      |               |          |

Project  
 43 GRAY'S INN ROAD  
 LONDON WC1

Title  
 SITE PLAN  
 PROPOSED SCHEME 14-11-11

Scale  
 1:500 @A3

Date  
 DEC 11

Drawn  
 SL

Checked  
 -


Drawing No.  
 6349/4

Rel No.  
 1

Revision  
 A

**gia**

The Whitehouse  
 Belvedere Road  
 London SE1 8GA  
 t 020 7202 1400  
 f 020 7202 1401  
 mail@gia.uk.com  
 www.gia.uk.com



Sources of Information

GIA  
 Partial Site Survey  
 Site Photographs

PURCELL MILLER TRITTON  
 Proposal Drawings for 5 King's Mews

HEBER PERCY & PARKER ARCHITECTS  
 Proposal Drawings for 7&8 King's Mews

BRANSON COATES ARCHITECTURE  
 2-4 Kings Mews Plans

AWW ARCHITECTURE  
 43 Gray's Inn Road scheme dated 14-11-11  
 Dwgs Nos. 2957-2200-2208, 1001, 2210-2218

Notes

Proposed scheme  
 ALL HEIGHTS GIVEN IN mm AOD

| Rev | Date | Description   | Initials |
|-----|------|---------------|----------|
| A   |      | Initial Issue |          |
|     |      |               |          |
|     |      |               |          |
|     |      |               |          |
|     |      |               |          |
|     |      |               |          |

Project  
 43 GRAY'S INN ROAD  
 LONDON WC1

Title  
 3D VIEW  
 PROPOSED SCHEME 14-11-11

Scale  
 N/S @A3

Date  
 DEC 11

Drawn  
 SL

Checked  
 -


Drawing No. 6349/5

Rel No. 1

Revision A



The Whitehouse  
 Belvedere Road  
 London SE1 8GA  
 t 020 7202 1400  
 f 020 7202 1401  
 mail@gia.uk.com  
 www.gia.uk.com



Sources of Information

GIA  
 Partial Site Survey  
 Site Photographs

PURCELL MILLER TRITTON  
 Proposal Drawings for 5 King's Mews

HEBER PERCY & PARKER ARCHITECTS  
 Proposal Drawings for 7&8 King's Mews

BRANSON COATES ARCHITECTURE  
 2-4 Kings Mews Plans

AWW ARCHITECTURE  
 43 Gray's Inn Road scheme dated 14-11-11  
 Dwgs Nos. 2957-2200-2208, 1001, 2210-2218

Notes

Proposed scheme  
 ALL HEIGHTS GIVEN IN mm AOD

| Rev | Date | Description   | Initials |
|-----|------|---------------|----------|
| A   |      | Initial Issue |          |
|     |      |               |          |
|     |      |               |          |
|     |      |               |          |
|     |      |               |          |
|     |      |               |          |

Project  
 43 GRAY'S INN ROAD  
 LONDON WC1

Title  
 3D VIEW  
 PROPOSED SCHEME 14-11-11

Scale  
 N/S @A3  
 Date  
 DEC 11

Drawn  
 SL  
 Checked  
 -

Drawing No. 6349/6  
 Rel No. 1  
 Revision A

**gia**

The Whitehouse  
 Belvedere Road  
 London SE1 8GA  
 t 020 7202 1400  
 f 020 7202 1401  
 mail@gia.uk.com  
 www.gia.uk.com

# APPENDIX 3

DAYLIGHT AND SUNLIGHT TABLES OF RESULTS



| Vertical Sky Component    |        |          |          |      |      | Average Daylight Factor   |        |          |          |       |          |       |      |      |
|---------------------------|--------|----------|----------|------|------|---------------------------|--------|----------|----------|-------|----------|-------|------|------|
| Room                      | Window | Existing | Proposed | Loss | %    | Room                      | Window | Room Use | Existing |       | Proposed |       | Loss | %    |
|                           |        |          |          |      |      |                           |        |          | ADF      | Total | ADF      | Total |      |      |
| <b>51 GRAY'S INN ROAD</b> |        |          |          |      |      | <b>51 GRAY'S INN ROAD</b> |        |          |          |       |          |       |      |      |
| R1/11                     | W1/11  | 26.25    | 26.25    | 0.00 | 0.00 | R1/11                     | W1/11  |          | 1.49     | 1.49  | 1.49     | 1.49  | 0.00 | 0.00 |
| R2/11                     | W2/11  | 22.89    | 22.89    | 0.00 | 0.00 | R2/11                     | W2/11  |          | 1.33     | 1.33  | 1.33     | 1.33  | 0.00 | 0.00 |
| R1/12                     | W1/12  | 33.44    | 33.44    | 0.00 | 0.00 | R1/12                     | W1/12  |          | 1.76     |       | 1.76     |       |      |      |
| R1/12                     | W2/12  | 26.78    | 26.78    | 0.00 | 0.00 | R1/12                     | W2/12  |          | 1.47     | 3.23  | 1.47     | 3.23  | 0.00 | 0.00 |
| R2/12                     | W3/12  | 29.04    | 29.04    | 0.00 | 0.00 | R2/12                     | W3/12  |          | 2.11     |       | 2.11     |       |      |      |
| R2/12                     | W4/12  | 33.39    | 33.39    | 0.00 | 0.00 | R2/12                     | W4/12  |          | 1.74     | 3.85  | 1.74     | 3.85  | 0.00 | 0.00 |
| R1/13                     | W1/13  | 35.53    | 35.53    | 0.00 | 0.00 | R1/13                     | W1/13  |          | 1.81     |       | 1.81     |       |      |      |
| R1/13                     | W2/13  | 28.58    | 28.58    | 0.00 | 0.00 | R1/13                     | W2/13  |          | 1.49     | 3.30  | 1.49     | 3.30  | 0.00 | 0.00 |
| R2/13                     | W3/13  | 30.91    | 30.90    | 0.01 | 0.03 | R2/13                     | W3/13  |          | 2.21     |       | 2.21     |       |      |      |
| R2/13                     | W4/13  | 35.51    | 35.51    | 0.00 | 0.00 | R2/13                     | W4/13  |          | 1.76     | 3.97  | 1.76     | 3.97  | 0.00 | 0.00 |
| R1/14                     | W1/14  | 38.78    | 38.78    | 0.00 | 0.00 | R1/14                     | W1/14  |          | 0.84     |       | 0.84     |       |      |      |
| R1/14                     | W2/14  | 38.70    | 38.70    | 0.00 | 0.00 | R1/14                     | W2/14  |          | 1.27     | 2.11  | 1.27     | 2.11  | 0.00 | 0.00 |
| R2/14                     | W3/14  | 38.71    | 38.71    | 0.00 | 0.00 | R2/14                     | W3/14  |          | 1.34     |       | 1.34     |       |      |      |
| R2/14                     | W4/14  | 38.53    | 38.53    | 0.00 | 0.00 | R2/14                     | W4/14  |          | 2.39     | 3.74  | 2.39     | 3.74  | 0.00 | 0.00 |
| R3/14                     | W5/14  | 38.50    | 38.50    | 0.00 | 0.00 | R3/14                     | W5/14  |          | 2.34     |       | 2.34     |       |      |      |
| R3/14                     | W6/14  | 38.65    | 38.65    | 0.00 | 0.00 | R3/14                     | W6/14  |          | 1.31     | 3.64  | 1.31     | 3.64  | 0.00 | 0.00 |
| <b>49 GRAY'S INN ROAD</b> |        |          |          |      |      | <b>49 GRAY'S INN ROAD</b> |        |          |          |       |          |       |      |      |
| R1/21                     | W1/21  | 15.70    | 15.70    | 0.00 | 0.00 | R1/21                     | W1/21  |          | 0.75     | 0.75  | 0.75     | 0.75  | 0.00 | 0.00 |
| R2/21                     | W2/21  | 12.51    | 12.51    | 0.00 | 0.00 | R2/21                     | W2/21  |          | 0.59     |       | 0.59     |       |      |      |
| R2/21                     | W3/21  | 13.91    | 13.91    | 0.00 | 0.00 | R2/21                     | W3/21  |          | 0.63     |       | 0.63     |       |      |      |
| R2/21                     | W4/21  | 14.63    | 14.63    | 0.00 | 0.00 | R2/21                     | W4/21  |          | 0.66     |       | 0.66     |       |      |      |
| R2/21                     | W5/21  | 14.17    | 14.17    | 0.00 | 0.00 | R2/21                     | W5/21  |          | 0.65     |       | 0.65     |       |      |      |
| R2/21                     | W6/21  | 11.10    | 11.10    | 0.00 | 0.00 | R2/21                     | W6/21  |          | 0.56     | 3.08  | 0.56     | 3.08  | 0.00 | 0.00 |
| R1/22                     | W1/22  | 30.80    | 30.80    | 0.00 | 0.00 | R1/22                     | W1/22  |          | 1.39     | 1.39  | 1.39     | 1.39  | 0.00 | 0.00 |
| R2/22                     | W2/22  | 35.60    | 35.60    | 0.00 | 0.00 | R2/22                     | W2/22  |          | 3.00     | 3.00  | 3.00     | 3.00  | 0.00 | 0.00 |
| R1/23                     | W1/23  | 26.46    | 26.46    | 0.00 | 0.00 | R1/23                     | W1/23  |          | 1.00     |       | 1.00     |       |      |      |
| R1/23                     | W2/23  | 31.86    | 31.86    | 0.00 | 0.00 | R1/23                     | W2/23  |          | 1.15     | 2.15  | 1.15     | 2.15  | 0.00 | 0.00 |
| R1/24                     | W1/24  | 27.56    | 27.56    | 0.00 | 0.00 | R1/24                     | W1/24  |          | 0.93     |       | 0.93     |       |      |      |
| R1/24                     | W2/24  | 35.06    | 35.06    | 0.00 | 0.00 | R1/24                     | W2/24  |          | 1.12     | 2.05  | 1.12     | 2.05  | 0.00 | 0.00 |
| R1/33                     | W1/33  | 28.70    | 28.70    | 0.00 | 0.00 | R1/33                     | W1/33  | STAIR    | 1.10     | 1.10  | 1.10     | 1.10  | 0.00 | 0.00 |
| R1/34                     | W1/34  | 32.02    | 32.02    | 0.00 | 0.00 | R1/34                     | W1/34  | STAIR    | 2.00     | 2.00  | 2.00     | 2.00  | 0.00 | 0.00 |
| <b>47 GRAY'S INN ROAD</b> |        |          |          |      |      | <b>47 GRAY'S INN ROAD</b> |        |          |          |       |          |       |      |      |
| R1/39                     | W1/39  | 0.96     | 0.96     | 0.00 | 0.00 | R1/39                     | W1/39  |          | 0.22     | 0.22  | 0.22     | 0.22  | 0.00 | 0.00 |
| R2/39                     | W2/39T | 0.73     | 0.73     | 0.00 | 0.00 | R2/39                     | W2/39T |          | 0.25     |       | 0.25     |       |      |      |
| R2/39                     | W3/39T | 0.70     | 0.70     | 0.00 | 0.00 | R2/39                     | W3/39T |          | 0.25     |       | 0.25     |       |      |      |
| R2/39                     | W4/39T | 0.62     | 0.62     | 0.00 | 0.00 | R2/39                     | W4/39T |          | 0.23     | 0.73  | 0.23     | 0.73  | 0.00 | 0.00 |
| R1/40                     | W1/40  | 3.42     | 3.42     | 0.00 | 0.00 | R1/40                     | W1/40  |          | 0.21     | 0.21  | 0.21     | 0.21  | 0.00 | 0.00 |
| R2/40                     | W2/40  | 2.15     | 2.15     | 0.00 | 0.00 | R2/40                     | W2/40  |          | 0.58     |       | 0.58     |       |      |      |

| Vertical Sky Component    |        |          |          |      |       | Average Daylight Factor   |        |              |          |       |          |       |      |       |
|---------------------------|--------|----------|----------|------|-------|---------------------------|--------|--------------|----------|-------|----------|-------|------|-------|
| Room                      | Window | Existing | Proposed | Loss | %     | Room                      | Window | Room Use     | Existing |       | Proposed |       | Loss | %     |
|                           |        |          |          |      |       |                           |        |              | ADF      | Total | ADF      | Total |      |       |
| R2/40                     | W3/40  | 2.12     | 2.12     | 0.00 | 0.00  | R2/40                     | W3/40  |              | 0.57     |       | 0.57     |       |      |       |
| R2/40                     | W4/40  | 1.79     | 1.79     | 0.00 | 0.00  | R2/40                     | W4/40  |              | 0.53     | 1.68  | 0.53     | 1.68  | 0.00 | 0.00  |
| R1/41                     | W1/41  | 17.47    | 17.47    | 0.00 | 0.00  | R1/41                     | W1/41  |              | 0.56     | 0.56  | 0.56     | 0.56  | 0.00 | 0.00  |
| R2/41                     | W2/41  | 8.82     | 8.82     | 0.00 | 0.00  | R2/41                     | W2/41  |              | 1.27     |       | 1.27     |       |      |       |
| R2/41                     | W3/41  | 9.51     | 9.51     | 0.00 | 0.00  | R2/41                     | W3/41  |              | 1.34     |       | 1.34     |       |      |       |
| R2/41                     | W4/41  | 7.43     | 7.43     | 0.00 | 0.00  | R2/41                     | W4/41  |              | 1.18     | 3.79  | 1.18     | 3.79  | 0.00 | 0.00  |
| R1/42                     | W1/42  | 35.30    | 35.30    | 0.00 | 0.00  | R1/42                     | W1/42  |              | 1.30     |       | 1.30     |       |      |       |
| R1/42                     | W2/42  | 35.28    | 35.28    | 0.00 | 0.00  | R1/42                     | W2/42  |              | 1.30     |       | 1.30     |       |      |       |
| R1/42                     | W3/42  | 34.84    | 34.84    | 0.00 | 0.00  | R1/42                     | W3/42  |              | 1.24     | 3.84  | 1.24     | 3.84  | 0.00 | 0.00  |
| R1/43                     | W1/43  | 22.89    | 22.89    | 0.00 | 0.00  | R1/43                     | W1/43  |              | 1.30     |       | 1.30     |       |      |       |
| R1/43                     | W2/43  | 28.33    | 28.33    | 0.00 | 0.00  | R1/43                     | W2/43  |              | 1.85     | 3.15  | 1.85     | 3.15  | 0.00 | 0.00  |
| R1/44                     | W1/44  | 34.99    | 34.87    | 0.12 | 0.34  | R1/44                     | W1/44  |              | 1.70     | 1.70  | 1.70     | 1.70  | 0.00 | 0.12  |
| <b>41 GRAY'S INN ROAD</b> |        |          |          |      |       | <b>41 GRAY'S INN ROAD</b> |        |              |          |       |          |       |      |       |
| R1/51                     | W1/51  | 28.04    | 21.52    | 6.52 | 23.25 | R1/51                     | W1/51  | STAIRS       | 0.51     | 0.51  | 0.44     | 0.44  | 0.07 | 12.97 |
| R1/52                     | W1/52  | 32.35    | 24.49    | 7.86 | 24.30 | R1/52                     | W1/52  | STAIRS       | 2.83     | 2.83  | 2.32     | 2.32  | 0.50 | 17.83 |
| R1/53                     | W1/53  | 32.72    | 24.08    | 8.64 | 26.41 | R1/53                     | W1/53  | STAIRS       | 1.32     | 1.32  | 1.09     | 1.09  | 0.24 | 17.75 |
| R2/53                     | W3/53  | 34.95    | 26.44    | 8.51 | 24.35 | R2/53                     | W3/53  | WC           | 2.07     | 2.07  | 1.81     | 1.81  | 0.27 | 12.97 |
| R3/53                     | W2/53  | 35.92    | 32.75    | 3.17 | 8.83  | R3/53                     | W2/53  | KITCHEN      | 1.93     | 1.93  | 1.80     | 1.80  | 0.14 | 6.98  |
| R2/61                     | W1/61  | 29.52    | 26.37    | 3.15 | 10.67 | R2/61                     | W1/61  | BATHROOM     | 3.61     | 3.61  | 3.36     | 3.36  | 0.25 | 7.00  |
| R2/62                     | W1/62  | 33.65    | 30.02    | 3.63 | 10.79 | R2/62                     | W1/62  | BATHROOM     | 3.18     | 3.18  | 2.97     | 2.97  | 0.20 | 6.39  |
| <b>39 GRAY'S INN ROAD</b> |        |          |          |      |       | <b>39 GRAY'S INN ROAD</b> |        |              |          |       |          |       |      |       |
| R1/71                     | W1/71  | 24.68    | 24.64    | 0.04 | 0.16  | R1/71                     | W1/71  | KITCHEN      | 1.18     | 1.18  | 1.18     | 1.18  | 0.00 | 0.00  |
| R2/71                     | W2/71  | 25.66    | 25.63    | 0.03 | 0.12  | R2/71                     | W2/71  | BATHROOM     | 1.23     | 1.23  | 1.23     | 1.23  | 0.00 | 0.00  |
| R1/72                     | W1/72  | 30.24    | 30.18    | 0.06 | 0.20  | R1/72                     | W1/72  | BATHROOM     | 2.94     | 2.94  | 2.94     | 2.94  | 0.00 | 0.00  |
| R1/73                     | W1/73  | 35.23    | 34.40    | 0.83 | 2.36  | R1/73                     | W1/73  | BATHROOM     | 0.77     | 0.77  | 0.77     | 0.77  | 0.00 | 0.00  |
| R2/73                     | W2/73  | 33.98    | 33.62    | 0.36 | 1.06  | R2/73                     | W2/73  | BEDROOM      | 0.74     | 0.74  | 0.74     | 0.74  | 0.00 | 0.00  |
| R1/81                     | W1/81  | 20.40    | 20.28    | 0.12 | 0.59  | R1/81                     | W1/81  | STAIRS       | 1.23     | 1.23  | 1.23     | 1.23  | 0.00 | 0.00  |
| R1/82                     | W1/82  | 25.22    | 25.10    | 0.12 | 0.48  | R1/82                     | W1/82  | STAIRS       | 1.94     | 1.94  | 1.94     | 1.94  | 0.00 | 0.00  |
| <b>37 GRAY'S INN ROAD</b> |        |          |          |      |       | <b>37 GRAY'S INN ROAD</b> |        |              |          |       |          |       |      |       |
| R1/90                     | W1/90  | 20.66    | 20.65    | 0.01 | 0.05  | R1/90                     | W1/90  | COMMERCIAL   | 0.46     |       | 0.46     |       |      |       |
| R1/90                     | W2/90  | 4.67     | 4.67     | 0.00 | 0.00  | R1/90                     | W2/90  | COMMERCIAL   | 0.00     | 0.46  | 0.00     | 0.46  | 0.00 | 0.00  |
| R1/91                     | W1/91  | 26.89    | 26.88    | 0.01 | 0.04  | R1/91                     | W1/91  | BED/STUDY    | 3.09     | 3.09  | 3.09     | 3.09  | 0.00 | 0.00  |
| R2/91                     | W2/91  | 11.94    | 11.94    | 0.00 | 0.00  | R2/91                     | W2/91  | OFFICE/STUDY | 1.28     | 1.28  | 1.28     | 1.28  | 0.00 | 0.00  |
| R1/92                     | W1/92  | 31.52    | 31.51    | 0.01 | 0.03  | R1/92                     | W1/92  | BEDROOM      | 2.67     | 2.67  | 2.67     | 2.67  | 0.00 | 0.00  |
| R2/92                     | W2/92  | 16.16    | 16.16    | 0.00 | 0.00  | R2/92                     | W2/92  | BEDROOM      | 1.18     | 1.18  | 1.18     | 1.18  | 0.00 | 0.00  |

| Vertical Sky Component                     |        |          |          |      |      | Average Daylight Factor                    |        |              |          |       |          |       |      |      |  |
|--------------------------------------------|--------|----------|----------|------|------|--------------------------------------------|--------|--------------|----------|-------|----------|-------|------|------|--|
| Room                                       | Window | Existing | Proposed | Loss | %    | Room                                       | Window | Room Use     | Existing |       | Proposed |       | Loss | %    |  |
|                                            |        |          |          |      |      |                                            |        |              | ADF      | Total | ADF      | Total |      |      |  |
| R1/93                                      | W1/93  | 30.19    | 30.19    | 0.00 | 0.00 | R1/93                                      | W1/93  | BEDROOM      | 0.60     | 0.60  | 0.60     | 0.60  | 0.00 | 0.00 |  |
| R2/93                                      | W2/93  | 20.28    | 20.25    | 0.03 | 0.15 | R2/93                                      | W2/93  | BEDROOM      | 0.39     | 0.39  | 0.39     | 0.39  | 0.00 | 0.00 |  |
| R1/230                                     | W1/230 | 12.13    | 12.13    | 0.00 | 0.00 | R1/230                                     | W1/230 | STORE        | 0.43     |       | 0.43     |       |      |      |  |
| R1/230                                     | W2/230 | 18.16    | 18.16    | 0.00 | 0.00 | R1/230                                     | W2/230 | STORE        | 0.93     | 1.36  | 0.93     | 1.36  | 0.00 | 0.00 |  |
| R1/231                                     | W2/230 | 18.16    | 18.16    | 0.00 | 0.00 | R1/231                                     | W2/230 | OFFICE/STUDY | 0.44     |       | 0.44     |       |      |      |  |
| R1/231                                     | W1/231 | 16.94    | 16.94    | 0.00 | 0.00 | R1/231                                     | W1/231 | OFFICE/STUDY | 0.29     | 0.73  | 0.29     | 0.73  | 0.00 | 0.00 |  |
| R1/232                                     | W1/232 | 20.38    | 20.38    | 0.00 | 0.00 | R1/232                                     | W1/232 | BEDROOM      | 1.16     | 1.16  | 1.16     | 1.16  | 0.00 | 0.00 |  |
| <b>35 GRAY'S INN ROAD</b>                  |        |          |          |      |      | <b>35 GRAY'S INN ROAD</b>                  |        |              |          |       |          |       |      |      |  |
| R1/101                                     | W1/101 | 22.24    | 22.24    | 0.00 | 0.00 | R1/101                                     | W1/101 | HALLWAY      | 0.38     | 0.38  | 0.38     | 0.38  | 0.00 | 0.00 |  |
| R2/101                                     | W3/101 | 20.47    | 20.47    | 0.00 | 0.00 | R2/101                                     | W3/101 | STORE        | 0.24     | 0.24  | 0.24     | 0.24  | 0.00 | 0.00 |  |
| R3/101                                     | W2/101 | 17.83    | 17.83    | 0.00 | 0.00 | R3/101                                     | W2/101 | KITCHEN      | 1.84     | 1.84  | 1.84     | 1.84  | 0.00 | 0.00 |  |
| R1/102                                     | W1/102 | 26.12    | 26.11    | 0.01 | 0.04 | R1/102                                     | W1/102 | BATHROOM     | 1.55     | 1.55  | 1.55     | 1.55  | 0.00 | 0.00 |  |
| R1/103                                     | W1/103 | 29.96    | 29.96    | 0.00 | 0.00 | R1/103                                     | W1/103 | BATHROOM     | 1.71     | 1.71  | 1.71     | 1.71  | 0.00 | 0.00 |  |
| R1/104                                     | W1/104 | 35.54    | 35.54    | 0.00 | 0.00 | R1/104                                     | W1/104 | BEDROOM      | 1.60     | 1.60  | 1.60     | 1.60  | 0.00 | 0.00 |  |
| R2/112                                     | W1/112 | 20.97    | 20.96    | 0.01 | 0.05 | R2/112                                     | W1/112 | BEDROOM      | 1.32     | 1.32  | 1.32     | 1.32  | 0.00 | 0.00 |  |
| R2/113                                     | W1/113 | 23.78    | 23.78    | 0.00 | 0.00 | R2/113                                     | W1/113 | BEDROOM      | 1.23     | 1.23  | 1.23     | 1.23  | 0.00 | 0.00 |  |
| R2/114                                     | W1/114 | 30.19    | 30.19    | 0.00 | 0.00 | R2/114                                     | W1/114 | BEDROOM      | 1.29     | 1.29  | 1.29     | 1.29  | 0.00 | 0.00 |  |
| <b>4-10 THEOBALD'S ROAD</b>                |        |          |          |      |      | <b>4-10 THEOBALD'S ROAD</b>                |        |              |          |       |          |       |      |      |  |
| R2/123                                     | W2/123 | 22.00    | 21.77    | 0.23 | 1.05 | R2/123                                     | W2/123 | KITCHEN      | 1.16     | 1.16  | 1.15     | 1.15  | 0.01 | 0.60 |  |
| R2/124                                     | W2/124 | 23.95    | 23.85    | 0.10 | 0.42 | R2/124                                     | W2/124 | KITCHEN      | 1.22     | 1.22  | 1.22     | 1.22  | 0.00 | 0.25 |  |
| R2/125                                     | W2/125 | 29.97    | 29.97    | 0.00 | 0.00 | R2/125                                     | W2/125 | KITCHEN      | 1.04     | 1.04  | 1.04     | 1.04  | 0.00 | 0.00 |  |
| R1/132                                     | W1/132 | 5.37     | 5.37     | 0.00 | 0.00 | R1/132                                     | W1/132 | STAIRS       | 0.91     | 0.91  | 0.91     | 0.91  | 0.00 | 0.00 |  |
| R1/133                                     | W1/133 | 14.37    | 14.24    | 0.13 | 0.90 | R1/133                                     | W1/133 | STAIRS       | 1.62     | 1.62  | 1.61     | 1.61  | 0.01 | 0.62 |  |
| R1/134                                     | W1/134 | 22.22    | 22.19    | 0.03 | 0.14 | R1/134                                     | W1/134 | STAIRS       | 2.14     | 2.14  | 2.14     | 2.14  | 0.00 | 0.09 |  |
| <b>4-10 THEOBALD'S ROAD (Test Windows)</b> |        |          |          |      |      | <b>4-10 THEOBALD'S ROAD (Test Windows)</b> |        |              |          |       |          |       |      |      |  |
| R1/123                                     | W1/123 | 12.40    | 12.40    | 0.00 | 0.00 | R1/123                                     | W1/123 | KITCHEN      | 0.96     | 0.96  | 0.96     | 0.96  | 0.00 | 0.00 |  |
| R1/124                                     | W1/124 | 15.54    | 15.54    | 0.00 | 0.00 | R1/124                                     | W1/124 | KITCHEN      | 1.12     | 1.12  | 1.12     | 1.12  | 0.00 | 0.00 |  |
| R1/125                                     | W1/125 | 25.52    | 25.52    | 0.00 | 0.00 | R1/125                                     | W1/125 | KITCHEN      | 1.15     | 1.15  | 1.15     | 1.15  | 0.00 | 0.00 |  |
| <b>12 THEOBALD'S ROAD</b>                  |        |          |          |      |      | <b>12 THEOBALD'S ROAD</b>                  |        |              |          |       |          |       |      |      |  |
| R1/140                                     | W1/140 | 7.98     | 7.98     | 0.00 | 0.00 | R1/140                                     | W1/140 |              | 0.83     | 0.83  | 0.83     | 0.83  | 0.00 | 0.00 |  |
| R1/141                                     | W2/141 | 13.52    | 13.52    | 0.00 | 0.00 | R1/141                                     | W2/141 |              | 1.12     |       | 1.12     |       |      |      |  |
| R1/141                                     | W3/141 | 32.46    | 32.46    | 0.00 | 0.00 | R1/141                                     | W3/141 |              | 2.22     | 3.34  | 2.22     | 3.34  | 0.00 | 0.00 |  |

| Vertical Sky Component                      |        |          |          |      |      | Average Daylight Factor                     |        |               |          |       |          |       |      |      |
|---------------------------------------------|--------|----------|----------|------|------|---------------------------------------------|--------|---------------|----------|-------|----------|-------|------|------|
| Room                                        | Window | Existing | Proposed | Loss | %    | Room                                        | Window | Room Use      | Existing |       | Proposed |       | Loss | %    |
|                                             |        |          |          |      |      |                                             |        |               | ADF      | Total | ADF      | Total |      |      |
| R2/141                                      | W1/141 | 12.77    | 12.77    | 0.00 | 0.00 | R2/141                                      | W1/141 |               | 1.00     | 1.00  | 1.00     | 1.00  | 0.00 | 0.00 |
| R1/142                                      | W2/142 | 20.54    | 20.38    | 0.16 | 0.78 | R1/142                                      | W2/142 |               | 1.20     |       | 1.20     |       |      |      |
| R1/142                                      | W3/142 | 36.99    | 36.84    | 0.15 | 0.41 | R1/142                                      | W3/142 |               | 1.93     | 3.13  | 1.92     | 3.11  | 0.02 | 0.48 |
| R2/142                                      | W1/142 | 17.61    | 17.54    | 0.07 | 0.40 | R2/142                                      | W1/142 |               | 1.01     | 1.01  | 1.00     | 1.00  | 0.00 | 0.30 |
| R1/150                                      | W1/150 | 8.66     | 8.66     | 0.00 | 0.00 | R1/150                                      | W1/150 |               | 0.52     |       | 0.52     |       |      |      |
| R1/150                                      | W2/150 | 9.66     | 9.66     | 0.00 | 0.00 | R1/150                                      | W2/150 |               | 0.57     |       | 0.57     |       |      |      |
| R1/150                                      | W3/150 | 10.50    | 10.50    | 0.00 | 0.00 | R1/150                                      | W3/150 |               | 0.61     | 1.70  | 0.61     | 1.70  | 0.00 | 0.00 |
| <b>1 KING'S MEWS</b>                        |        |          |          |      |      | <b>1 KING'S MEWS</b>                        |        |               |          |       |          |       |      |      |
| R1/160                                      | W1/160 | 9.70     | 9.70     | 0.00 | 0.00 | R1/160                                      | W1/160 |               | 0.88     | 0.88  | 0.88     | 0.88  | 0.00 | 0.00 |
| R2/160                                      | W2/160 | 10.76    | 10.76    | 0.00 | 0.00 | R2/160                                      | W2/160 |               | 0.85     | 0.85  | 0.85     | 0.85  | 0.00 | 0.00 |
| R1/161                                      | W1/161 | 15.86    | 15.86    | 0.00 | 0.00 | R1/161                                      | W1/161 |               | 0.50     | 0.50  | 0.50     | 0.50  | 0.00 | 0.00 |
| <b>2 KING'S MEWS</b>                        |        |          |          |      |      | <b>2 KING'S MEWS</b>                        |        |               |          |       |          |       |      |      |
| R1/170                                      | W1/170 | 14.52    | 14.52    | 0.00 | 0.00 | R1/170                                      | W1/170 | L/K/D         | 1.24     | 1.24  | 1.24     | 1.24  | 0.00 | 0.00 |
| R4/171                                      | W1/171 | 27.93    | 27.56    | 0.37 | 1.32 | R4/171                                      | W1/171 | BEDROOM       | 3.66     | 3.66  | 3.63     | 3.63  | 0.04 | 1.01 |
| <b>4 KING'S MEWS</b>                        |        |          |          |      |      | <b>4 KING'S MEWS</b>                        |        |               |          |       |          |       |      |      |
| R2/170                                      | W2/170 | 17.34    | 17.34    | 0.00 | 0.00 | R2/170                                      | W2/170 | LIVINGROOM    | 1.36     | 1.36  | 1.36     | 1.36  | 0.00 | 0.00 |
| R1/171                                      | W4/171 | 29.89    | 29.53    | 0.36 | 1.20 | R1/171                                      | W4/171 | BEDROOM       | 1.97     | 1.97  | 1.95     | 1.95  | 0.02 | 1.01 |
| R2/171                                      | W3/171 | 29.49    | 29.09    | 0.40 | 1.36 | R2/171                                      | W3/171 | BEDROOM       | 3.10     | 3.10  | 3.07     | 3.07  | 0.03 | 1.10 |
| R3/171                                      | W2/171 | 29.19    | 28.81    | 0.38 | 1.30 | R3/171                                      | W2/171 | BEDROOM       | 1.28     | 1.28  | 1.26     | 1.26  | 0.01 | 1.10 |
| <b>5 KING'S MEWS (AS PROPOSED)</b>          |        |          |          |      |      | <b>5 KING'S MEWS (AS PROPOSED)</b>          |        |               |          |       |          |       |      |      |
| R1/181                                      | W1/181 | 27.33    | 27.33    | 0.00 | 0.00 | R1/181                                      | W1/181 | LIVING/KITCHE | 3.43     | 3.43  | 3.43     | 3.43  | 0.00 | 0.00 |
| R1/182                                      | W1/182 | 32.47    | 32.05    | 0.42 | 1.29 | R1/182                                      | W1/182 | BEDROOM       | 6.66     | 6.66  | 6.59     | 6.59  | 0.07 | 1.05 |
| <b>7-8 KING'S MEWS (AS PROPOSED)</b>        |        |          |          |      |      | <b>7-8 KING'S MEWS (AS PROPOSED)</b>        |        |               |          |       |          |       |      |      |
| R1/191                                      | W1/191 | 14.70    | 14.69    | 0.01 | 0.07 | R1/191                                      | W1/191 | LIVING/KITCHE | 0.55     |       | 0.55     |       |      |      |
| R1/191                                      | W2/191 | 26.75    | 26.75    | 0.00 | 0.00 | R1/191                                      | W2/191 | LIVING/KITCHE | 2.34     | 2.89  | 2.34     | 2.89  | 0.00 | 0.03 |
| R1/192                                      | W1/192 | 31.08    | 30.71    | 0.37 | 1.19 | R1/192                                      | W1/192 | LIVING/KITCHE | 4.20     |       | 4.16     |       |      |      |
| R1/192                                      | W2/192 | 32.32    | 32.00    | 0.32 | 0.99 | R1/192                                      | W2/192 | LIVING/KITCHE | 3.08     | 7.28  | 3.06     | 7.21  | 0.07 | 0.89 |
| <b>12-13 KING'S MEWS</b>                    |        |          |          |      |      | <b>12-13 KING'S MEWS</b>                    |        |               |          |       |          |       |      |      |
| R1/211                                      | W1/211 | 29.12    | 29.12    | 0.00 | 0.00 | R1/211                                      | W1/211 |               | 1.62     | 1.62  | 1.62     | 1.62  | 0.00 | 0.06 |
| R2/211                                      | W2/211 | 29.04    | 28.99    | 0.05 | 0.17 | R2/211                                      | W2/211 |               | 1.18     | 1.18  | 1.17     | 1.17  | 0.00 | 0.17 |
| <b>9-11 KING'S MEWS</b>                     |        |          |          |      |      | <b>9-11 KING'S MEWS</b>                     |        |               |          |       |          |       |      |      |
| R1/201                                      | W1/201 | 18.93    | 18.93    | 0.00 | 0.00 | R1/201                                      | W1/201 |               | 1.46     | 1.46  | 1.46     | 1.46  | 0.00 | 0.00 |
| <b>144-148 GRAY'S INN ROAD TEST WINDOWS</b> |        |          |          |      |      | <b>144-148 GRAY'S INN ROAD TEST WINDOWS</b> |        |               |          |       |          |       |      |      |
| R1/220                                      | W1/220 | 21.15    | 20.91    | 0.24 | 1.13 | R1/220                                      | W1/220 |               | 3.82     | 3.82  | 3.79     | 3.79  | 0.03 | 0.76 |

| Vertical Sky Component |        |          |          |      |      | Average Daylight Factor |        |          |          |       |          |       |      |      |
|------------------------|--------|----------|----------|------|------|-------------------------|--------|----------|----------|-------|----------|-------|------|------|
| Room                   | Window | Existing | Proposed | Loss | %    | Room                    | Window | Room Use | Existing |       | Proposed |       | Loss | %    |
|                        |        |          |          |      |      |                         |        |          | ADF      | Total | ADF      | Total |      |      |
| R2/220                 | W2/220 | 21.22    | 20.98    | 0.24 | 1.13 | R2/220                  | W2/220 |          | 3.83     | 3.83  | 3.79     | 3.79  | 0.03 | 0.81 |
| R1/221                 | W1/221 | 26.02    | 25.69    | 0.33 | 1.27 | R1/221                  | W1/221 |          | 1.51     |       | 1.50     |       | 0.03 | 1.06 |
| R1/221                 | W2/221 | 26.05    | 25.72    | 0.33 | 1.27 | R1/221                  | W2/221 |          | 1.51     | 3.03  | 1.50     | 3.00  | 0.03 | 1.06 |
| R2/221                 | W3/221 | 26.08    | 25.74    | 0.34 | 1.30 | R2/221                  | W3/221 |          | 1.52     |       | 1.50     |       | 0.03 | 1.02 |
| R2/221                 | W4/221 | 26.10    | 25.77    | 0.33 | 1.26 | R2/221                  | W4/221 |          | 1.52     | 3.04  | 1.50     | 3.00  | 0.03 | 1.02 |
| R1/222                 | W1/222 | 30.31    | 29.92    | 0.39 | 1.29 | R1/222                  | W1/222 |          | 1.70     |       | 1.68     |       | 0.04 | 1.06 |
| R1/222                 | W2/222 | 30.35    | 29.96    | 0.39 | 1.29 | R1/222                  | W2/222 |          | 1.70     | 3.41  | 1.69     | 3.37  | 0.04 | 1.06 |
| R2/222                 | W3/222 | 30.40    | 29.99    | 0.41 | 1.35 | R2/222                  | W3/222 |          | 1.71     |       | 1.69     |       | 0.04 | 1.03 |
| R2/222                 | W4/222 | 30.40    | 30.01    | 0.39 | 1.28 | R2/222                  | W4/222 |          | 1.71     | 3.41  | 1.69     | 3.38  | 0.04 | 1.03 |



43 GRAYS INN ROAD  
Proposed 43 Grays Inn Road Scheme dated 14/11/11  
DAYLIGHT DISTRIBUTION ANALYSIS

| Room/<br>Floor            | Room Use | Whole<br>Room | Prev<br>sq ft | New<br>sq ft | Loss<br>sq ft | %Loss |
|---------------------------|----------|---------------|---------------|--------------|---------------|-------|
| <b>51 GRAY'S INN ROAD</b> |          |               |               |              |               |       |
| R1/11                     |          | 183.3         | 173.0         | 173.0        | 0.0           | 0.0   |
| R2/11                     |          | 189.3         | 162.5         | 162.5        | 0.0           | 0.0   |
| R1/12                     |          | 183.3         | 182.6         | 182.6        | 0.0           | 0.0   |
| R2/12                     |          | 189.3         | 188.7         | 188.7        | 0.0           | 0.0   |
| R1/13                     |          | 183.3         | 182.3         | 182.3        | 0.0           | 0.0   |
| R2/13                     |          | 189.3         | 188.7         | 188.7        | 0.0           | 0.0   |
| R1/14                     |          | 196.6         | 191.7         | 191.7        | 0.0           | 0.0   |
| R2/14                     |          | 183.3         | 182.3         | 182.3        | 0.0           | 0.0   |
| R3/14                     |          | 189.3         | 188.7         | 188.7        | 0.0           | 0.0   |
| <b>49 GRAY'S INN ROAD</b> |          |               |               |              |               |       |
| R1/21                     |          | 204.8         | 159.9         | 159.9        | 0.0           | 0.0   |
| R2/21                     |          | 241.4         | 240.3         | 240.3        | 0.0           | 0.0   |
| R1/22                     |          | 65.2          | 63.7          | 63.7         | 0.0           | 0.0   |
| R2/22                     |          | 130.0         | 128.1         | 128.1        | 0.0           | 0.0   |
| R1/23                     |          | 149.3         | 147.3         | 147.3        | 0.0           | 0.0   |
| R1/24                     |          | 145.4         | 141.4         | 141.4        | 0.0           | 0.0   |
| R1/33                     | STAIR    | 54.8          | 50.3          | 50.3         | 0.0           | 0.0   |
| R1/34                     | STAIR    | 55.6          | 49.6          | 49.6         | 0.0           | 0.0   |
| <b>47 GRAY'S INN ROAD</b> |          |               |               |              |               |       |
| R1/39                     |          | 127.2         | 4.9           | 4.9          | 0.0           | 0.0   |
| R2/39                     |          | 136.7         | 9.4           | 9.4          | 0.0           | 0.0   |
| R1/40                     |          | 127.2         | 14.2          | 14.2         | 0.0           | 0.0   |
| R2/40                     |          | 136.7         | 28.5          | 28.5         | 0.0           | 0.0   |
| R1/41                     |          | 127.2         | 87.6          | 87.6         | 0.0           | 0.0   |
| R2/41                     |          | 136.7         | 136.3         | 136.3        | 0.0           | 0.0   |
| R1/42                     |          | 254.3         | 249.8         | 249.8        | 0.0           | 0.0   |
| R1/43                     |          | 155.5         | 154.1         | 154.1        | 0.0           | 0.0   |
| R1/44                     |          | 155.5         | 152.8         | 152.8        | 0.0           | 0.0   |
| <b>41 GRAY'S INN ROAD</b> |          |               |               |              |               |       |

43 GRAYS INN ROAD  
Proposed 43 Grays Inn Road Scheme dated 14/11/11  
DAYLIGHT DISTRIBUTION ANALYSIS

| Room/<br>Floor | Room Use | Whole<br>Room | Prev<br>sq ft | New<br>sq ft | Loss<br>sq ft | %Loss |
|----------------|----------|---------------|---------------|--------------|---------------|-------|
| R1/51          | STAIRS   | 98.7          | 88.1          | 88.1         | 0.0           | 0.0   |
| R1/52          | STAIRS   | 85.0          | 82.7          | 82.7         | 0.0           | 0.0   |
| R1/53          | STAIRS   | 26.3          | 25.6          | 25.6         | 0.0           | 0.0   |
| R2/53          | WC       | 12.3          | 12.0          | 11.6         | 0.4           | 3.3   |
| R3/53          | KITCHEN  | 107.8         | 103.5         | 101.6        | 1.9           | 1.8   |
| R2/61          | BATHROOM | 40.7          | 37.5          | 33.3         | 4.1           | 10.9  |
| R2/62          | BATHROOM | 56.9          | 54.2          | 51.3         | 2.9           | 5.4   |

39 GRAY'S INN ROAD

|       |          |       |       |       |     |     |
|-------|----------|-------|-------|-------|-----|-----|
| R1/71 | KITCHEN  | 66.4  | 56.9  | 56.9  | 0.0 | 0.0 |
| R2/71 | BATHROOM | 37.0  | 34.9  | 34.9  | 0.0 | 0.0 |
| R1/72 | BATHROOM | 31.0  | 23.5  | 23.5  | 0.0 | 0.0 |
| R1/73 | BATHROOM | 42.6  | 35.6  | 35.4  | 0.2 | 0.6 |
| R2/73 | BEDROOM  | 140.6 | 128.0 | 128.0 | 0.0 | 0.0 |
| R1/81 | STAIRS   | 78.7  | 77.9  | 77.9  | 0.0 | 0.0 |
| R1/82 | STAIRS   | 45.8  | 44.2  | 44.2  | 0.0 | 0.0 |

37 GRAY'S INN ROAD

|        |              |       |       |       |     |     |
|--------|--------------|-------|-------|-------|-----|-----|
| R1/90  | COMMERCIAL   | 103.3 | 73.5  | 73.5  | 0.0 | 0.0 |
| R1/91  | BED/STUDY    | 62.1  | 59.4  | 59.4  | 0.0 | 0.0 |
| R2/91  | OFFICE/STUDY | 116.3 | 109.4 | 109.4 | 0.0 | 0.0 |
| R1/92  | BEDROOM      | 62.1  | 59.4  | 59.4  | 0.0 | 0.0 |
| R2/92  | BEDROOM      | 116.3 | 111.3 | 111.3 | 0.0 | 0.0 |
| R1/93  | BEDROOM      | 183.2 | 149.4 | 149.4 | 0.0 | 0.0 |
| R2/93  | BEDROOM      | 101.2 | 51.6  | 51.6  | 0.0 | 0.0 |
| R1/230 | STORE        | 44.2  | 29.5  | 29.5  | 0.0 | 0.0 |
| R1/231 | OFFICE/STUDY | 151.5 | 89.8  | 89.8  | 0.0 | 0.0 |
| R1/232 | BEDROOM      | 152.7 | 118.6 | 118.6 | 0.0 | 0.0 |

35 GRAY'S INN ROAD

|        |         |      |      |      |     |     |
|--------|---------|------|------|------|-----|-----|
| R1/101 | HALLWAY | 73.8 | 53.3 | 53.3 | 0.0 | 0.0 |
| R2/101 | STORE   | 70.6 | 41.8 | 41.8 | 0.0 | 0.0 |

43 GRAYS INN ROAD  
Proposed 43 Grays Inn Road Scheme dated 14/11/11  
DAYLIGHT DISTRIBUTION ANALYSIS

| Room/<br>Floor                             | Room Use | Whole<br>Room | Prev<br>sq ft | New<br>sq ft | Loss<br>sq ft | %Loss |
|--------------------------------------------|----------|---------------|---------------|--------------|---------------|-------|
| R3/101                                     | KITCHEN  | 131.9         | 128.3         | 128.3        | 0.0           | 0.0   |
| R1/102                                     | BATHROOM | 110.0         | 106.5         | 106.5        | 0.0           | 0.0   |
| R1/103                                     | BATHROOM | 110.0         | 106.8         | 106.8        | 0.0           | 0.0   |
| R1/104                                     | BEDROOM  | 110.0         | 106.8         | 106.8        | 0.0           | 0.0   |
| R2/112                                     | BEDROOM  | 171.9         | 138.8         | 138.8        | 0.0           | 0.0   |
| R2/113                                     | BEDROOM  | 171.9         | 145.1         | 145.1        | 0.0           | 0.0   |
| R2/114                                     | BEDROOM  | 171.9         | 167.0         | 167.0        | 0.0           | 0.0   |
| <b>4-10 THEOBALD'S ROAD</b>                |          |               |               |              |               |       |
| R2/123                                     | KITCHEN  | 202.9         | 167.3         | 167.3        | 0.0           | 0.0   |
| R2/124                                     | KITCHEN  | 202.9         | 171.6         | 171.6        | 0.0           | 0.0   |
| R2/125                                     | KITCHEN  | 202.9         | 190.0         | 190.0        | 0.0           | 0.0   |
| R1/132                                     | STAIRS   | 104.6         | 73.9          | 73.9         | 0.0           | 0.0   |
| R1/133                                     | STAIRS   | 104.6         | 84.2          | 84.2         | 0.0           | 0.0   |
| R1/134                                     | STAIRS   | 104.6         | 101.3         | 101.3        | 0.0           | 0.0   |
| <b>4-10 THEOBALD'S ROAD (Test Windows)</b> |          |               |               |              |               |       |
| R1/123                                     | KITCHEN  | 147.3         | 64.9          | 64.9         | 0.0           | 0.0   |
| R1/124                                     | KITCHEN  | 147.3         | 77.4          | 77.4         | 0.0           | 0.0   |
| R1/125                                     | KITCHEN  | 147.3         | 133.0         | 133.0        | 0.0           | 0.0   |
| <b>12 THEOBALD'S ROAD</b>                  |          |               |               |              |               |       |
| R1/140                                     |          | 151.0         | 43.1          | 43.1         | 0.0           | 0.0   |
| R1/141                                     |          | 151.0         | 144.1         | 144.1        | 0.0           | 0.0   |
| R2/141                                     |          | 164.9         | 60.6          | 60.6         | 0.0           | 0.0   |
| R1/142                                     |          | 151.0         | 144.1         | 144.1        | 0.0           | 0.0   |
| R2/142                                     |          | 164.9         | 69.5          | 69.5         | 0.0           | 0.0   |
| R1/150                                     |          | 290.6         | 165.0         | 165.0        | 0.0           | 0.0   |
| <b>1 KING'S MEWS</b>                       |          |               |               |              |               |       |
| R1/160                                     |          | 51.6          | 13.8          | 13.8         | 0.0           | 0.0   |

| Room/<br>Floor                       | Room Use       | Whole<br>Room | Prev<br>sq ft | New<br>sq ft | Loss<br>sq ft | %Loss |
|--------------------------------------|----------------|---------------|---------------|--------------|---------------|-------|
| R2/160                               |                | 62.1          | 17.8          | 17.8         | 0.0           | 0.0   |
| R1/161                               |                | 122.8         | 28.9          | 28.9         | 0.0           | 0.0   |
| <b>2 KING'S MEWS</b>                 |                |               |               |              |               |       |
| R1/170                               | L/K/D          | 465.5         | 191.7         | 191.7        | 0.0           | 0.0   |
| R4/171                               | BEDROOM        | 165.8         | 165.0         | 165.0        | 0.0           | 0.0   |
| <b>4 KING'S MEWS</b>                 |                |               |               |              |               |       |
| R2/170                               | LIVINGROOM     | 489.8         | 184.5         | 184.5        | 0.0           | 0.0   |
| R1/171                               | BEDROOM        | 141.7         | 136.9         | 136.9        | 0.0           | 0.0   |
| R2/171                               | BEDROOM        | 191.0         | 190.5         | 190.5        | 0.0           | 0.0   |
| R3/171                               | BEDROOM        | 141.4         | 138.6         | 138.6        | 0.0           | 0.0   |
| <b>5 KING'S MEWS (AS PROPOSED)</b>   |                |               |               |              |               |       |
| R1/181                               | LIVING/KITCHEN | 407.3         | 304.5         | 296.1        | 8.4           | 2.8   |
| R1/182                               | BEDROOM        | 407.3         | 407.3         | 407.3        | 0.0           | 0.0   |
| <b>7-8 KING'S MEWS (AS PROPOSED)</b> |                |               |               |              |               |       |
| R1/191                               | LIVING/KITCHEN | 353.6         | 320.5         | 320.5        | 0.0           | 0.0   |
| R1/192                               | LIVING/KITCHEN | 258.1         | 257.6         | 257.6        | 0.0           | 0.0   |
| <b>12-13 KING'S MEWS</b>             |                |               |               |              |               |       |
| R1/211                               |                | 129.2         | 115.8         | 115.8        | 0.0           | 0.0   |
| R2/211                               |                | 204.7         | 177.6         | 175.5        | 2.2           | 1.2   |
| <b>9-11 KING'S MEWS</b>              |                |               |               |              |               |       |
| R1/201                               |                | 164.6         | 157.9         | 157.9        | 0.0           | 0.0   |

| Room/<br>Floor                              | Room Use | Whole<br>Room | Prev<br>sq ft | New<br>sq ft | Loss<br>sq ft | %Loss |
|---------------------------------------------|----------|---------------|---------------|--------------|---------------|-------|
| <b>144-148 GRAY'S INN ROAD TEST WINDOWS</b> |          |               |               |              |               |       |
| R1/220                                      |          | 171.0         | 72.4          | 72.4         | 0.0           | 0.0   |
| R2/220                                      |          | 171.0         | 76.4          | 77.2         | -0.8          | -1.0  |
| R1/221                                      |          | 155.5         | 154.9         | 154.9        | 0.0           | 0.0   |
| R2/221                                      |          | 155.5         | 154.3         | 153.7        | 0.6           | 0.4   |
| R1/222                                      |          | 155.5         | 154.9         | 154.9        | 0.0           | 0.0   |
| R2/222                                      |          | 155.5         | 154.9         | 154.9        | 0.0           | 0.0   |



| Position                  | Room Use | Existing |        |       | Proposed |        |       | % Loss |       |
|---------------------------|----------|----------|--------|-------|----------|--------|-------|--------|-------|
|                           |          | Summer   | Winter | Total | Summer   | Winter | Total | Winter | Total |
| <b>51 GRAY'S INN ROAD</b> |          |          |        |       |          |        |       |        |       |
| W1/11                     |          | 28       | 4      | 32    | 28       | 4      | 32    | 0.00   | 0.00  |
| W2/11                     |          | 27       | 5      | 32    | 27       | 5      | 32    | 0.00   | 0.00  |
| W1/12                     |          | 30       | 12     | 42    | 30       | 12     | 42    | 0.00   | 0.00  |
| W2/12                     |          | 22       | 11     | 33    | 22       | 11     | 33    | 0.00   | 0.00  |
| W3/12                     |          | 29       | 13     | 42    | 29       | 13     | 42    | 0.00   | 0.00  |
| W4/12                     |          | 33       | 13     | 46    | 33       | 13     | 46    | 0.00   | 0.00  |
| W1/13                     |          | 30       | 13     | 43    | 30       | 13     | 43    | 0.00   | 0.00  |
| W2/13                     |          | 22       | 13     | 35    | 22       | 13     | 35    | 0.00   | 0.00  |
| W3/13                     |          | 29       | 13     | 42    | 29       | 13     | 42    | 0.00   | 0.00  |
| W4/13                     |          | 33       | 14     | 47    | 33       | 14     | 47    | 0.00   | 0.00  |
| W1/14                     |          | 27       | 15     | 42    | 27       | 15     | 42    | 0.00   | 0.00  |
| W2/14                     |          | 32       | 15     | 47    | 32       | 15     | 47    | 0.00   | 0.00  |
| W3/14                     |          | 32       | 15     | 47    | 32       | 15     | 47    | 0.00   | 0.00  |
| W4/14                     |          | 35       | 15     | 50    | 35       | 15     | 50    | 0.00   | 0.00  |
| W5/14                     |          | 35       | 14     | 49    | 35       | 14     | 49    | 0.00   | 0.00  |
| W6/14                     |          | 32       | 15     | 47    | 32       | 15     | 47    | 0.00   | 0.00  |
| <b>49 GRAY'S INN ROAD</b> |          |          |        |       |          |        |       |        |       |
| W1/21                     |          | 16       | 0      | 16    | 16       | 0      | 16    | -      | 0.00  |
| W1/22                     |          | 26       | 5      | 31    | 26       | 5      | 31    | 0.00   | 0.00  |
| W2/22                     |          | 32       | 16     | 48    | 32       | 16     | 48    | 0.00   | 0.00  |
| W1/23                     |          | 25       | 14     | 39    | 25       | 14     | 39    | 0.00   | 0.00  |
| W2/23                     |          | 32       | 14     | 46    | 32       | 14     | 46    | 0.00   | 0.00  |
| W1/24                     |          | 24       | 15     | 39    | 24       | 15     | 39    | 0.00   | 0.00  |
| W2/24                     |          | 31       | 15     | 46    | 31       | 15     | 46    | 0.00   | 0.00  |
| W1/33                     | STAIR    | 23       | 5      | 28    | 23       | 5      | 28    | 0.00   | 0.00  |

43 GRAYS INN ROAD  
Proposed 43 Grays Inn Road Scheme dated 14/11/11  
SUNLIGHT ANALYSIS

| Position                  | Room Use | Existing |        |       | Proposed |        |       | % Loss |       |
|---------------------------|----------|----------|--------|-------|----------|--------|-------|--------|-------|
|                           |          | Summer   | Winter | Total | Summer   | Winter | Total | Winter | Total |
| W1/34                     | STAIR    | 29       | 7      | 36    | 29       | 7      | 36    | 0.00   | 0.00  |
| <b>47 GRAY'S INN ROAD</b> |          |          |        |       |          |        |       |        |       |
| W1/39                     |          | 0        | 0      | 0     | 0        | 0      | 0     | -      | -     |
| W1/40                     |          | 1        | 0      | 1     | 1        | 0      | 1     | -      | 0.00  |
| W1/41                     |          | 19       | 1      | 20    | 19       | 1      | 20    | 0.00   | 0.00  |
| W1/42                     |          | 35       | 13     | 48    | 35       | 13     | 48    | 0.00   | 0.00  |
| W2/42                     |          | 35       | 13     | 48    | 35       | 13     | 48    | 0.00   | 0.00  |
| W3/42                     |          | 34       | 13     | 47    | 34       | 13     | 47    | 0.00   | 0.00  |
| W1/43                     |          | 21       | 12     | 33    | 21       | 12     | 33    | 0.00   | 0.00  |
| W2/43                     |          | 28       | 7      | 35    | 28       | 7      | 35    | 0.00   | 0.00  |
| W1/44                     |          | 30       | 16     | 46    | 30       | 16     | 46    | 0.00   | 0.00  |
| <b>41 GRAY'S INN ROAD</b> |          |          |        |       |          |        |       |        |       |
| W1/51                     | STAIRS   | 20       | 6      | 26    | 16       | 6      | 22    | 0.00   | 15.38 |
| W1/52                     | STAIRS   | 32       | 11     | 43    | 26       | 11     | 37    | 0.00   | 13.95 |
| W1/53                     | STAIRS   | 27       | 10     | 37    | 21       | 10     | 31    | 0.00   | 16.22 |
| W3/53                     | WC       | 28       | 10     | 38    | 21       | 10     | 31    | 0.00   | 18.42 |
| W2/53                     | KITCHEN  | 31       | 17     | 48    | 30       | 17     | 47    | 0.00   | 2.08  |
| W1/61                     | BATHROOM | 31       | 7      | 38    | 31       | 7      | 38    | 0.00   | 0.00  |
| W1/62                     | BATHROOM | 32       | 11     | 43    | 31       | 11     | 42    | 0.00   | 2.33  |
| <b>39 GRAY'S INN ROAD</b> |          |          |        |       |          |        |       |        |       |
| W1/71                     | KITCHEN  | 25       | 6      | 31    | 25       | 6      | 31    | 0.00   | 0.00  |
| W2/71                     | BATHROOM | 23       | 3      | 26    | 23       | 3      | 26    | 0.00   | 0.00  |

43 GRAYS INN ROAD  
Proposed 43 Grays Inn Road Scheme dated 14/11/11  
SUNLIGHT ANALYSIS

| Position                  | Room Use     | Existing |        |       | Proposed |        |       | % Loss |       |
|---------------------------|--------------|----------|--------|-------|----------|--------|-------|--------|-------|
|                           |              | Summer   | Winter | Total | Summer   | Winter | Total | Winter | Total |
| W1/72                     | BATHROOM     | 29       | 6      | 35    | 29       | 6      | 35    | 0.00   | 0.00  |
| W1/73                     | BATHROOM     | 23       | 12     | 35    | 23       | 12     | 35    | 0.00   | 0.00  |
| W2/73                     | BEDROOM      | 29       | 12     | 41    | 29       | 12     | 41    | 0.00   | 0.00  |
| W1/81                     | STAIRS       | 20       | 2      | 22    | 20       | 2      | 22    | 0.00   | 0.00  |
| W1/82                     | STAIRS       | 23       | 3      | 26    | 23       | 3      | 26    | 0.00   | 0.00  |
| <b>37 GRAY'S INN ROAD</b> |              |          |        |       |          |        |       |        |       |
| W1/90                     | COMMERCIAL   | 10       | 0      | 10    | 10       | 0      | 10    | -      | 0.00  |
| W2/90                     | COMMERCIAL   | 0        | 0      | 0     | 0        | 0      | 0     | -      | -     |
| W1/91                     | BED/STUDY    | 30       | 2      | 32    | 30       | 2      | 32    | 0.00   | 0.00  |
| W2/91                     | OFFICE/STUDY | 20       | 2      | 22    | 20       | 2      | 22    | 0.00   | 0.00  |
| W1/92                     | BEDROOM      | 32       | 5      | 37    | 32       | 5      | 37    | 0.00   | 0.00  |
| W2/92                     | BEDROOM      | 21       | 3      | 24    | 21       | 3      | 24    | 0.00   | 0.00  |
| W1/93                     | BEDROOM      | 28       | 7      | 35    | 28       | 7      | 35    | 0.00   | 0.00  |
| W2/93                     | BEDROOM      | 14       | 2      | 16    | 14       | 2      | 16    | 0.00   | 0.00  |
| W1/230                    | STORE        | 14       | 0      | 14    | 14       | 0      | 14    | -      | 0.00  |
| W2/230                    | STORE        | 19       | 0      | 19    | 19       | 0      | 19    | -      | 0.00  |
| W1/231                    | OFFICE/STUDY | 18       | 1      | 19    | 18       | 1      | 19    | 0.00   | 0.00  |
| W1/232                    | BEDROOM      | 23       | 2      | 25    | 23       | 2      | 25    | 0.00   | 0.00  |
| <b>35 GRAY'S INN ROAD</b> |              |          |        |       |          |        |       |        |       |
| W1/101                    | HALLWAY      | 22       | 0      | 22    | 22       | 0      | 22    | -      | 0.00  |

| Position                                    | Room Use | Existing |        |       | Proposed |        |       | % Loss |       |
|---------------------------------------------|----------|----------|--------|-------|----------|--------|-------|--------|-------|
|                                             |          | Summer   | Winter | Total | Summer   | Winter | Total | Winter | Total |
| W3/101                                      | STORE    | 15       | 0      | 15    | 15       | 0      | 15    | -      | 0.00  |
| W2/101                                      | KITCHEN  | 14       | 0      | 14    | 14       | 0      | 14    | -      | 0.00  |
| W1/102                                      | BATHROOM | 24       | 2      | 26    | 24       | 2      | 26    | 0.00   | 0.00  |
| W1/103                                      | BATHROOM | 31       | 4      | 35    | 31       | 4      | 35    | 0.00   | 0.00  |
| W1/104                                      | BEDROOM  | 32       | 10     | 42    | 32       | 10     | 42    | 0.00   | 0.00  |
| W1/112                                      | BEDROOM  | 15       | 2      | 17    | 15       | 2      | 17    | 0.00   | 0.00  |
| W1/113                                      | BEDROOM  | 19       | 2      | 21    | 19       | 2      | 21    | 0.00   | 0.00  |
| W1/114                                      | BEDROOM  | 31       | 4      | 35    | 31       | 4      | 35    | 0.00   | 0.00  |
| <b>4-10 THEOBALD'S ROAD (Test Windows)</b>  |          |          |        |       |          |        |       |        |       |
| W1/123                                      | KITCHEN  | 8        | 0      | 8     | 8        | 0      | 8     | -      | 0.00  |
| W1/124                                      | KITCHEN  | 9        | 0      | 9     | 9        | 0      | 9     | -      | 0.00  |
| W1/125                                      | KITCHEN  | 28       | 0      | 28    | 28       | 0      | 28    | -      | 0.00  |
| <b>144-148 GRAY'S INN ROAD TEST WINDOWS</b> |          |          |        |       |          |        |       |        |       |
| W1/220                                      |          | 22       | 9      | 31    | 20       | 9      | 29    | 0.00   | 6.45  |
| W2/220                                      |          | 22       | 8      | 30    | 21       | 8      | 29    | 0.00   | 3.33  |
| W1/221                                      |          | 25       | 6      | 31    | 24       | 6      | 30    | 0.00   | 3.23  |
| W2/221                                      |          | 25       | 5      | 30    | 24       | 5      | 29    | 0.00   | 3.33  |
| W3/221                                      |          | 24       | 7      | 31    | 24       | 7      | 31    | 0.00   | 0.00  |
| W4/221                                      |          | 25       | 5      | 30    | 24       | 5      | 29    | 0.00   | 3.33  |
| W1/222                                      |          | 29       | 9      | 38    | 29       | 8      | 37    | 11.11  | 2.63  |
| W2/222                                      |          | 28       | 9      | 37    | 28       | 9      | 37    | 0.00   | 0.00  |
| W3/222                                      |          | 28       | 8      | 36    | 27       | 8      | 35    | 0.00   | 2.78  |
| W4/222                                      |          | 28       | 10     | 38    | 27       | 10     | 37    | 0.00   | 2.63  |